


DEMOLITION KEYNOTES

1. SAWCUT AND REMOVE ASPHALT PAVEMENT.
2. REMOVE CONCRETE PAVEMENT.
3. REMOVE CONCRETE SIDEWALK.
4. REMOVE BUSH/SHRUB.
5. REMOVE SHRUB LINE.
6. REMOVE TREE.
7. REMOVE AND SALVAGE LANDSCAPE ROCK, COORDINATE WITH AND RETURN TO VA FOR REUSE (NOT REUSED ON THIS PROJECT).
8. REMOVE SANITARY SEWER LINE UNDERNEATH BUILDING LIMITS, CAP SEWER TO REMAIN.
9. REMOVE UNDERGROUND POWER LINE PER EE101.
10. REMOVE UNKNOWN UTILITY. CONTRACTOR TO IDENTIFY AND VERIFY EACH IS ABANDONED PRIOR TO REMOVAL.
11. REMOVE LIGHT POLE AND BASE.
12. REMOVE ABANDONED UTILITY POLE PER EE101. COORDINATE WITH MLG&W.
13. REMOVE ELECTRIC PULL BOX.
14. REMOVE ELECTRIC MANHOLE.
15. REMOVE UNDERGROUND STORM LINE, TEMPORARILY CAP SEWER TO REMAIN UNTIL RECONNECTION.
16. REMOVE STORM STRUCTURE.
17. SAWCUT AND REMOVE CONCRETE CURB AND GUTTER.
18. REMOVE AND SALVAGE TRENCH DRAIN. REINSTALL PER CU101 AND CU501 AFTER FOUNDATION INSTALLATION.
19. REMOVE CONCRETE FLUME.
20. REMOVE TRAFFIC LOOP SENSORS.
21. REMOVE CAMERA, POLE, AND BASE PER EE101.
22. REMOVE DECORATIVE FENCE AS NECESSARY FOR ACCESS. SALVAGE FENCE FOR REINSTALLATION.
23. REMOVE UNDERGROUND TELECOM LINE PER EE101.
24. REMOVE SIGN AND BASE
25. CHAIN LINK CONSTRUCTION FENCE, 6' MIN. HEIGHT.



Order Plans

Scale bars for various increments: one eighth inch = one foot, one quarter inch = one foot, one half inch = one foot, three eighths inch = one foot, one inch = one foot, one and one half inches = one foot, two inches = one foot, three inches = one foot, four inches = one foot, six inches = one foot, eight inches = one foot, ten inches = one foot, twelve inches = one foot.

Revisions:	Date

VA U.S. Department of Veterans Affairs
 MEMPHIS VAMC
 1030 JEFFERSON AVE, MEMPHIS, TN 38104



ARCHITECT/ENGINEERS:
PROJECT LEAD
 Architect, Structural Engineer, Civil Engineer
GUIDON DESIGN
 905 N. CAPITOL AVE. SUITE 100 INDIANAPOLIS, IN 46204
 317.800.6388 WWW.GUIDONDESIGN.COM
 SUSTAINABLE ARCHITECTURE + ENGINEERING

MEP Engineer
 APOGEE CONSULTING GROUP
 1151 Kildaire Farm Rd. Suite 120 Cary, NC 27511
 Tele: 919-858-7420

Functional Design
 CARL WALKER INC.
 3211 Internet Blvd., Suite 220 Frisco, TX 75034
 Tele: 469-777-5143

BID SET			
Drawing Title DEMOLITION PLAN		Project Title CONSTRUCT PARKING GARAGE ON WEST LOT	
Approved for Design Concept: FACILITY MANAGEMENT DIVISION MANAGER		Project Number 15.1067	Office of Facilities Management
Location MEMPHIS, TN	Date 11/14/2016	Building Number	VA Project Number 614-319
Checked By KJC	Drawn By CMB	Drawing Number CD101	VA Department of Veterans Affairs