


- SITE LAYOUT KEYNOTES**
1. ASPHALT PAVEMENT
 2. CONCRETE CURB AND GUTTER
 3. CONCRETE CURB (GUTTERLESS)
 4. ADA CURB RAMP
 5. CROSSWALK STRIPING, WHITE, PAINTED, 2' WIDE X 8' LONG, 2' SPACING
 6. PARKING STRIPING, WHITE, PAINTED, 4" WIDE
 7. STOP BAR, WHITE, PAINTED, 2' WIDE X 12' LONG
 8. STOP SIGN (R1-1) PER MUTCD
 9. CONCRETE SIDEWALK
 10. REINSTALL SALVAGED DECORATIVE FENCE
 11. RIVER ROCK LANDSCAPE GRAVEL OVER GEOTEXTILE, 12" AVERAGE DIAMETER, 3" MINIMUM DEPTH
 12. RIP RAP OVER GEOTEXTILE, 4" AVERAGE DIAMETER, 12" MINIMUM DEPTH
 13. LIGHT POLE (SEE ELECTRICAL PLANS)
 14. WIDEN GUTTER TO 24" TO MATCH STORM INLET GRATE
 15. "CROSS TRAFFIC DOES NOT STOP" SIGN PLAQUE

Order Plans



ARCHITECT/ENGINEERS:

PROJECT LEAD
Architect, Structural Engineer, Civil Engineer
GUIDON DESIGN
905 N. CAPITOL AVE. SUITE 100 INDIANAPOLIS, IN 46204
317.800.6388 WWW.GUIDONDESIGN.COM
SUSTAINABLE ARCHITECTURE + ENGINEERING

MEP Engineer
APOGEE CONSULTING GROUP
1151 Kildaire Farm Rd. Suite 120 Cary, NC 27511
Tele: 919-858-7420

Functional Design
CARL WALKER INC.
3211 Internet Blvd., Suite 220 Frisco, TX 75034
Tele: 469-777-5143

Drawing Title SITE PLAN		Project Title CONSTRUCT PARKING GARAGE ON WEST LOT		Project Number 15.1067		Office of Facilities Management	
Approved for Design Concept: FACILITY MANAGEMENT DIVISION MANAGER		Location MEMPHIS, TN		Building Number		VA Project Number 614-319	
Date 11/14/2016		Checked By: KJC		Drawn By: CMB		Drawing Number CS101	

VA U.S. Department of Veterans Affairs
MEMPHIS VAMC
1030 JEFFERSON AVE, MEMPHIS, TN 38104



A three inches = one foot
 B one and one half inches = one foot
 C one inch = one foot
 D three quarters inch = one foot
 E one half inch = one foot
 F three eighths inch = one foot
 G one quarter inch = one foot
 H one eighth inch = one foot

Revisions: _____ Date _____