


one eighth inch = one foot  
one quarter inch = one foot  
one half inch = one foot  
three eighths inch = one foot  
one inch = one foot  
one and one half inches = one foot  
two inches = one foot  
three quarters inch = one foot  
three eighths inch = one foot  
one eighth inch = one foot

CONCRETE WALL SCHEDULE						
MARK	WALL THICKNESS	HORIZONTAL REINF		VERTICAL REINF		REMARKS
		INSIDE FACE	OUTSIDE FACE	INSIDE FACE	OUTSIDE FACE	
CW8	8"	#5 @ 18" OC		#5 @ 18" OC	#5 @ 12" OC	REINF CENTERED IN WALL
CW10	12"	#5 @ 18" OC	#5 @ 18" OC	#5 @ 12" OC	#5 @ 12" OC	
CW12	1'-0"	#5 @ 12" OC		#5 @ 18" OC	#5 @ 12" OC	
CW14	1'-2"	#5 @ 18" OC	#5 @ 18" OC	#5 @ 12" OC	#5 @ 12" OC	

WALL FOOTING SCHEDULE						
MARK	FTG SIZE (W x D)	LONGITUDINAL REINFORCEMENT		TRANSVERSE REINFORCEMENT		REMARKS
		TOP	BOTTOM	TOP	BOTTOM	
WF2	2'-0" X 1'-0"	#5 @ 9"	#5 @ 9"	#5 @ 9"	#5 @ 9"	
WF3	3'-0" X 1'-0"	#5 @ 12"	#5 @ 12"	#5 @ 12"	#5 @ 12"	
WF4	4'-0" X 1'-0"	#7 @ 12"	#7 @ 12"	#7 @ 9"	#7 @ 9"	
WF5	5'-0" X 1'-0"	#5 @ 18"	#5 @ 18"	#5 @ 12"	#5 @ 12"	
WF10	14'-0" X 3'-0"	#5 @ 9"	#11 @ 9"	#5 @ 9"	#5 @ 9"	

SPREAD FOOTING SCHEDULE						
TYPE	FOOTING SIZE			DEPTH	REINFORCEMENT	REMARKS
	WIDTH	LENGTH	DEPTH			
F1	22'-3"	13'-0"	2'-0"	#5 @ 18" TOP & BOTTOM	#5 @ 12" 1 WAY	SEE DETAIL 23/8601 FOR REINFORCING ANCHORAGE
F2	32'-0"	SEE PLAN	6'-0"	#10 @ 18" TOP & BOTTOM	#5 @ 12" 1 WAY	SEE DETAIL 23/8601 FOR REINFORCING ANCHORAGE
F1.0	11'-0"	11'-0"	1'-0"	#5 @ 18" TOP & BOTTOM	(18) #5 WA WAY BOTT	
F1.0A	11'-0"	11'-0"	1'-0"	#5 @ 18" TOP & BOTTOM	(18) #5 WA WAY BOTT	
F1.20	12'-0"	12'-0"	1'-0"	#5 @ 18" TOP & BOTTOM	(17) #5 WA WAY BOTT	
F1.30	13'-0"	13'-0"	1'-0"	#5 @ 18" TOP & BOTTOM	(17) #5 WA WAY BOTT	
F1.40	14'-0"	14'-0"	1'-0"	#5 @ 18" TOP & BOTTOM	(17) #5 WA WAY BOTT	
F1.40A	14'-0"	14'-0"	2'-0"	#5 @ 18" TOP & BOTTOM	(18) #5 WA WAY BOTT	
F1.50	15'-0"	15'-0"	2'-0"	#5 @ 18" TOP & BOTTOM	(17) #5 WA WAY BOTT	

CMU WALL SCHEDULE				
MARK	CMU SIZE	TYPE	REINFORCEMENT	REMARKS
MWB	8"	A	#5 @ 32" OC	



TYPE A

NOTES:

1. GROUT SOLID ALL CELLS CONTAINING REINFORCEMENT AND BELOW GRADE.
2. PROVIDE MATCHING HOOKED DOWELS INTO FOUNDATION FOR ALL VERTICAL REINFORCEMENT.
3. PROVIDE VERT. BARS AT ALL CORNERS, INTERSECTIONS, AND ENDS OF WALL. BAR SIZE TO MATCH TYP. VERT. REINFORCEMENT.
4. PROVIDE VERT. BARS AT JAMBS OF ALL OPENINGS.  
FOR OPENINGS W/ WIDTH <math>\le 3'-0''</math> PROVIDE VERT. BARS AT FIRST TWO CORES AT EACH JAMB.  
FOR OPENINGS W/ WIDTH > BAR SIZE TO MATCH TYP. VERT. REINFORCEMENT.
5. PROVIDE VERT. BAR AT FIRST CORE ON EACH SIDE OF CONTROL JOINTS. BAR SIZE AND SPACING TO MATCH TYP. VERT. REINFORCEMENT.
6. PROVIDE HORIZONTAL BOND BEAM W/ 1-#6 CONT. BELOW ALL WINDOW AND DOOR OPENINGS. EXTEND 2'-0" PAST OPENING.
7. SPLICE ALL REINFORCEMENT PER TABLE THIS SHEET.

MASONRY CONSTRUCTION LAP SPLICE LENGTHS	
#3	1'-0"
#4	2'-0"
#5	2'-0"
#6	3'-0"
#7	3'-0"
#8	4'-0"
#9	4'-0"


# Order Plans @

# WWW.LDILINE.COM

Revisions:	Date




**U.S. Department of Veterans Affairs**  
MEMPHIS VAMC  
1030 JEFFERSON AVE, MEMPHIS, TN 38104



**MARK A. VANDIERCK**  
REGISTERED PROFESSIONAL ENGINEER  
NO. 10809552  
STATE OF INDIANA

ARCHITECT/ENGINEERS:

PROJECT LEAD  
Architect, Structural Engineer, Civil Engineer  
**GUIDON DESIGN**  
905 N. CAPITOL AVE, SUITE 100 INDIANAPOLIS, IN, 46204  
317.660.0388 WWW.GUIDONDESIGN.COM  
SUSTAINABLE ARCHITECTURE + ENGINEERING

MEP Engineer  
APOGEE CONSULTING GROUP  
1151 Kildaire Farm Rd. Suite 120 Cary, NC 27511  
Tele: 919-856-7420

Functional Design  
CARL WALKER INC.  
3211 Internet Blvd., Suite 220 Frisco, TX 75034  
Tele: 469-777-5143

BID SET			
Drawing Title FOUNDATION SCHEDULES, SECTIONS AND DETAILS	Project Title CONSTRUCT PARKING GARAGE ON WEST LOT	Project Number 15.1067	OFFICE OF FACILITIES MANAGEMENT
Approved for Design Concept: FACILITY MANAGEMENT DIVISION MANAGER	Location MEMPHIS, TN	Building Number	VA Project Number 614-319
Date 11/14/2016	Checked By: MAV	Drawn By: WJT	Drawing Number <b>SB601</b>
			