ABBREVIATIONS AND ACRONYMS

THIS SCHEDULE IS REPRESENTATIVE OF THOSE TYPICALLY FOUND ON THE PLANS BUT NOT ALL MAY BE UTILIZED

A	AMPERE, AMMETER
AF	AMPERE FRAME
AFF	ABOVE FINISHED FLOOR
AIC	AMPERES INTERRUPTING CAPACITY
AT	AMPERE TRIP
ATS	AUTOMATIC TRANSFER SWITCH
C	CONDUIT
℄	CENTER LINE
CR	CARD READER ACCESS
CU	COPPER
EC	EMPTY CONDUIT
EMER	EMERGENCY
EWC	ELECTRIC WATER HEATER
G, GND	GROUND
GF	GROUND FAULT INTERRUPTER
HH	HANDHOLE
HP	HORSEPOWER
HZ	HERTZ
IG	ISOLATED GROUND
JB	JUNCTION BOX
KVA	KILOVOLT-AMPERES
KW	KILOWATTS
LC	LIGHTING CONTACTOR
LTG	LIGHTING
PROVIDE	FURNISH, INSTALL & CONNECT
RECPT	RECEPTACLE
SC	SECURITY CAMERA OUTLET
SN	SOLID NEUTRAL
SW	SWITCH
SWBD	SWITCHBOARD
TV	COMBINATION TV & RECEPT OUTLET
TYP	TYPICAL
UG	UNDER GROUND
UNO	UNLESS NOTED OTHERWISE
V	VOLT
WP	WEATHERTIGHT GFI
XFMR	TRANSFORMER

ELECTRICAL SYMBOL LEGEND

	SOLID LINE DENOTES CONDUIT RUN CONCEALED IN WALL, ABOVE CEILINGS, EXPOSED IN UNFINISHED AREAS. RUN PARALLEL OR PERPENDICULAR TO STRUCTURE OR WALL. DASHED LINE DENOTES CONDUIT RUN BELOW GRADE OR BELOW FINISHED FLOOR.
	HOMERUN TO PANELBOARD. QUANTITY OF ARROWS INDICATES NUMBER OF CIRCUITS.
	SURFACE, RECESSED, OR WALL MOUNTED LIGHTING FIXTURE CONNECTED TO NORMAL BRANCH CIRCUIT. SEE LIGHTING FIXTURE SCHEDULE FOR EXACT REQUIREMENTS.
	SURFACE, RECESSED, OR WALL MOUNTED FIXTURE CONNECTED TO LIFE SAFETY BRANCH CIRCUIT FOR PROJECTS W/ GENERATOR OR PROVIDE LOCAL BATTERY PACK W/O GEN. SEE LIGHTING FIXTURE SCHEDULE FOR EXACT REQUIREMENTS. LETTER INDICATES TYPE.
	SURFACE, RECESSED, OR WALL MOUNTED LIGHTING FIXTURE CONNECTED TO CRITICAL BRANCH CIRCUIT. LETTER INDICATES TYPE. SEE LIGHTING FIXTURE SCHEDULE FOR EXACT REQUIREMENTS.
	CEILING MOUNTED EXIT SIGN, SHADED AREA INDICATES FACE WITH DIRECTIONAL ARROWS AS SHOWN. SEE LTG. FIXT. SCHEDULE FOR EXACT REQUIREMENTS. CONNECT TO UNSWITCHED BRANCH CKT. INDICATED ON DWGS. SUBSCRIPT "WG" WHEN INDICATED DENOTES WIREGUARD.
	WALL MOUNTED EXIT SIGN, SHADED AREA INDICATES FACE WITH DIRECTIONAL ARROWS AS SHOWN. SEE LTG. FIXT. SCHEDULE FOR EXACT REQUIREMENTS. CONNECT TO UNSWITCHED BRANCH CKT. INDICATED ON DWGS. SUBSCRIPT "WG" WHEN INDICATED DENOTES WIREGUARD.
S	SINGLE-POLE, 20 AMP, 120/277 VOLT, TOGGLE SWITCH IN FLUSH (FINISHED SPACES) OR SURFACE (UNFINISHED SPACES) OUTLET BOX. MOUNT 46" A.F.F. UNLESS OTHERWISE INDICATED.
S3	THREE-WAY, 20 AMP, 120/277 VOLT, TOGGLE SWITCH IN FLUSH (FINISHED SPACES) OR SURFACE (UNFINISHED SPACES) OUTLET BOX. MOUNT 46" A.F.F. UNLESS OTHERWISE INDICATED.
SK	SINGLE-POLE, 20 AMP, HEAVY-DUTY 120/277 VOLT, KEY OPERATED SWITCH MOUNTED IN FLUSH (FINISHED SPACES) OR SURFACE (UNFINISHED SPACES) OUTLET BOX. MOUNT 46" A.F.F. UNLESS OTHERWISE INDICATED OR REQUIRED BY SITE CONDITIONS. PROVIDE STANDARD OR BARREL KEY OPERATED TYPE AS SELECTED AND APPROVED BY VA. SWITCH SHALL HAVE EITHER INTEGRAL GREEN LED LIGHT TO INDICATE SWITCH IS IN ON POSITION OR SEPARATE LED LIGHT IN BOX AND WALL PLATE ABOVE SWITCH.
OS	OCCUPANCY SENSOR. CEILING MOUNTED. REFER TO SPECIFICATIONS AND DRAWINGS FOR DETAILS.
OS	OCCUPANCY SENSOR. WALL MOUNTED. REFER TO SPECIFICATIONS AND DRAWINGS FOR DETAILS.
	NON-FUSED SAFETY SWITCH, SIZE AND NUMBER OF POLES AS INDICATED BY SUBSCRIPTS. SUBSCRIPT WP INDICATES IN NEMA 3R ENCLOSURE. HEAVY DUTY, UNLESS OTHERWISE NOTED.
	ELECTRIC PUSH PLATE IN FLUSH OUTLET BOX WHEN SHOWN IN FINISHED WALLS. MOUNT 46" A.F.F. UNLESS OTHERWISE INDICATED. PROVIDED BY DOOR OPERATOR VENDOR.
(PH1)	480/277 VOLT PANELBOARD, FLUSH AND SURFACE MOUNTED RESPECTIVELY. SEE PANEL SCHEDULE FOR DESIGN INFORMATION. DESIGNATION AS INDICATED.
(CL1)	208Y/120 OR 120/240 VOLT PANELBOARD, FLUSH AND SURFACE MOUNTED RESPECTIVELY. DESIGNATION AS INDICATED. SEE PANELBOARD SCHEDULE FOR EXACT REQUIREMENTS.
(J)	JUNCTION BOX MOUNTED ABOVE CEILING OR FLUSH IN FINISHED CEILING UNLESS INDICATED OTHERWISE. SIZE PER NEC.
(JH)	WALL MOUNTED JUNCTION BOX, SIZE PER NEC OR AS INDICATED. MOUNTING HEIGHT AS INDICATED. MOUNT FLUSH IN FINISHED SPACES OR SURFACE IN UNFINISHED SPACES UNLESS OTHERWISE INDICATED.
	SPECIAL EQUIPMENT CONNECTION. SUBSCRIPT INDICATES DESIGNATION. SEE EQUIPMENT CONNECTION SCHEDULE FOR EXACT REQUIREMENTS.
	20 AMP, 125 VOLT, 3 WIRE DUPLEX RECEPTACLE IN FLUSH (FINISHED SPACES) OR SURFACE (UNFINISHED SPACES) OUTLET BOX. MOUNT 18" A.F.F. UNLESS OTHERWISE INDICATED. "TL" SUBSCRIPT DENOTES TWIST-LOCK RECEPTACLE.
	20 AMP, 125 VOLT, 3 WIRE DUPLEX RECEPTACLE IN FLUSH (FINISHED SPACES) OR SURFACE (UNFINISHED SPACES) OUTLET BOX. MOUNT 46" ABOVE FINISHED FLOOR, 6" ABOVE DESK/ COUNTERTOP, OR 2" ABOVE BACKSPLASH UNLESS OTHERWISE INDICATED.
	TWO 20 AMP, 125 VOLT, 3 WIRE RECEPTACLES IN FLUSH (FINISHED SPACES) OR SURFACE (UNFINISHED SPACES) 2-GANG OUTLET BOX. MOUNT 18" A.F.F. UNLESS OTHERWISE INDICATED.
Y	SPECIAL PURPOSE RECEPTACLE. VERIFY EXACT NEMA CONFIGURATION, WIRING REQUIREMENTS, AND MOUNTING HEIGHT WITH PURCHASED EQUIPMENT MANUFACTURER UNLESS OTHERWISE INDICATED.
REFRIG	20 AMP, 125 VOLT, 3 WIRE DUPLEX RECEPTACLE IN FLUSH (FINISHED SPACES) OR SURFACE (UNFINISHED SPACES) OUTLET BOX. MOUNT 18" A.F.F. UNLESS OTHERWISE INDICATED. "TL" SUBSCRIPT DENOTES TWIST-LOCK RECEPTACLE.
E E	20 AMP, 125 VOLT, 3 WIRE DUPLEX RECEPTACLE CONNECTED TO EMERGENCY BRANCH CIRCUIT. PROVIDE RED RECEPTACLE AND ENGRAVED CIRCUIT DESIGNATION NAMEPLATE UNLESS OTHERWISE INDICATED.
GF GF	20 AMP, 125 VOLT, 3 WIRE GROUND FAULT TYPE DUPLEX RECEPTACLE(S). MOUNTING HEIGHT AS NOTED.
EWC EWC	20 AMP, 125 VOLT, 3 WIRE GROUND FAULT TYPE DUPLEX RECEPTACLE FOR ELECTRIC WATER COOLER. V.I.F. TO COORDINATE MOUNTING HEIGHT WITH PLUMBING CONTRACTOR.
RBS RBS	20 AMP, 125 VOLT, 3 WIRE DUPLEX RECEPTACLE. CONTROLED BY KEYED OPERATED SWITCH PROVIDE RED RECEPTACLE AND ENGRAVED CIRCUIT DESIGNATION NAMEPLATE UNLESS OTHERWISE INDICATED.

ELECTRICAL SYMBOL LEGEND (CONTINUED)

	VOICE OUTLET 18" AFF., UNLESS OTHERWISE NOTED. INSTALL OUTLET FLUSH IN FINISHED SPACES OR SURFACE MOUNTED IN UNFINISHED AREAS.
	DATA OUTLET. INSTALL OUTLET IN FLUSH MOUNTED FLOORBOX.
	TELECOMMUNICATIONS OUTLET MOUNTED 18" AFF U.O.I. SUBSCRIPT 'XD' AND/OR 'XV' AND /OR 'XF', WHEN SHOWN, DENOTES NUMBER OF DATA AND/OR VOICE CABLES AND/OR FIBERS AND JACKS RESPECTIVELY. SUBSCRIPT "WT" DENOTES WIRELESS TRANSMITTER.
	TELECOMMUNICATIONS OUTLET MOUNTED 46" A.F.F. OR 6" ABOVE DESK/COUNTERTOP UNLESS OTHERWISE INDICATED. SUBSCRIPT 'XD' AND/OR 'XV' DENOTES QTY. OF DATA/ VOICE CABLES/JACKS RESPECTIVELY (BY OWNER). SUBSCRIPT 'P' DENOTES PAY PHONE.
TV	TELEVISION SYSTEM OUTLET FLUSH MOUNTED 18" A.F.F. UNLESS OTHERWISE INDICATED.
CR	SECURITY SYSTEM CARD READER FLUSH MOUNTED 46" A.F.F. UNLESS OTHERWISE INDICATED.
KP	SECURITY SYSTEM DOOR ACCESS KEYPAD FLUSH MOUNTED 46" A.F.F. UNLESS OTHERWISE INDICATED.
NM	NURSE CALL SYSTEM MASTER CONTROL STATION.
NA	NURSE CALL SYSTEM ANNUNCIATOR.
NP	NURSE CALL SYSTEM SINGLE PATIENT STATION MOUNTED 46" A.F.F. UNLESS OTHERWISE INDICATED. SUBSCRIPT, WHEN SHOWN, INDICATES ZONE. SUBSCRIPT "DP" WHEN SHOWN, DENOTES DUAL PATIENT STATION.
CB	NURSE CALL CODE BLUE STATION MOUNTED 46" A.F.F. UNLESS OTHERWISE INDICATED. SUBSCRIPT, WHEN SHOWN, INDICATES ZONE. VANDAL RESISTANT.
NE	NURSE CALL SYSTEM STAFF EMERGENCY STATION MOUNTED 46" A.F.F. UNLESS OTHERWISE INDICATED. SUBSCRIPT, WHEN SHOWN, INDICATES ZONE.
NS	NURSE CALL SYSTEM STAFF STATION MOUNTED 46" A.F.F. UNLESS OTHERWISE INDICATED. VANDAL RESISTANT.
ND	NURSE CALL SYSTEM DUTY STATION MOUNTED 46" A.F.F. UNLESS OTHERWISE INDICATED. SUBSCRIPT, WHEN SHOWN, INDICATES ZONE.
E S	NURSE CALL SYSTEM TOILET/SHOWER STATION WITH PULL CORD AS REQUIRED AS INDICATED ON PLANS. PULL CORD TO BE MAXIMUM 8" ABOVE FINISHED FLOOR. LABEL WITH "S" INDICATES TWO SHOWER STATIONS, ONE MOUNTED AT 18" AFF AND THE OTHER AT 46" A.F.F.
D	NURSE CALL SYSTEM CEILING MOUNTED DOME LIGHT. SUBSCRIPT, WHEN SHOWN INDICATES ZONE.
Z	NURSE CALL SYSTEM CEILING MOUNTED ZONE LIGHT. SUBSCRIPT, WHEN SHOWN, INDICATES ZONE.
CCTV	SECURITY SYSTEM CLOSED CIRCUIT TELEVISION CAMERA, CEILING OR WALL MOUNTED AS INDICATED. REFER TO DRAWINGS AND/OR SPECIFICATIONS FOR ADDITIONAL INFORMATION. FIELD VERIFY EXACT MOUNTING HEIGHT WITH ARCHITECT.
1	PLAN NOTE ON SAME SHEET. NOTE NUMBERS AS INDICATED.
L1	ELECTRICAL EQUIPMENT DESIGNATION.
L1	LOW VOLTAGE SYSTEM CABINET, FLUSH AND SURFACE MOUNTED RESPECTIVELY. DESIGNATION AS INDICATED.
XX	DURESS/ASSIST EQUIPMENT OR DEVICES. LETTERS INDICATE EQUIPMENT OR DEVICE TYPE. (AR-ADDRESSABLE RECEIVER, DL-DOOR LIGHT, ETC.) REFER TO SHEET E502 FOR COMPLETE DETAILS INCLUDING LEGEND FOR THIS SYSTEM.

GENERAL NOTES

A. THE CONTRACTOR BEARS A PRIME RESPONSIBILITY TO COMPLY WITH THE 2011 NATIONAL ELECTRICAL CODE AND 2006 INTERNATIONAL BUILDING CODE (WITH GEORGIA AMENDMENTS), EVEN WHEN THE PLANS OR SPECIFICATIONS DENOTE AN APPARENT VIOLATION. THIS SHOULD BE CAREFULLY AND CONTINUOUSLY, PARTICULARLY DURING ESTIMATING FOR PROPOSAL, AND ANY DISCREPANCIES OBSERVED SHOULD BE BROUGHT TO THE ATTENTION OF THE ENGINEER FOR RESOLUTION.

B. THE ELECTRICAL CONTRACTOR SHALL MAINTAIN, ON THE SITE, AN ADEQUATE ADMINISTRATIVE AND WHERE ONE COMPLETE SET OF PLANS AND SPECIFICATIONS SHALL BE KEPT FOR THE WORK OF TRADES ON THE PROJECT. THESE PLANS AND SPECIFICATIONS SHALL BE IN ADDITION TO THE SETS USED BY THE INSTALLING ELECTRICIAN IN CARRYING OUT THEIR DAY-TO-DAY WORK ON THE PROJECT. THE PROJECTED LOCATION OF EVERY OUTLET, RACEWAY, OR ITEM OF EQUIPMENT TO BE INSTALLED UNDER THIS CONTRACT SHALL BE CHECKED AGAINST THE PLANS AND SPECIFICATIONS OF ALL THE OTHER TRADES AS WELL AS BY DAILY CONFERENCE WITH WORKMEN AND SUPERVISORS OF ALL OTHER TRADES TO THE EXTENT THAT ANY CONFLICTS OR UNCERTAINTIES ABOUT LOCATION ARE RESOLVED BEFORE WORK IS INSTALLED, PARTICULARLY WITH REGARD TO THE INTERACTION OF LIGHTING FIXTURES, AIR HANDLING OPENINGS, ACCESS DOORS, SPRINKLER HEADS, ETC. CEILING CONSTRUCTION INSTALLATION SHALL BE MADE IN ACCORD WITH REFLECTED CEILING PLANS AND/OR INSTRUCTIONS BY THE ARCHITECT'S REPRESENTATIVES ON THE SITE. MOVING ITEMS FROM LOCATIONS SHOWN, REROUTING, OR CHANGES TO ACCOMPLISH ANY WORK AS SHOWN ON PLANS OR SPECIFICATIONS IN ORDER TO ACCOMPLISH THIS COORDINATION SHALL NOT BE CAUSE FOR CLAIM FOR ADDITIONAL COMPENSATION FOR THE WORK. PARTICULAR CARE SHALL BE TAKEN TO LOCATE BOXES SO THEY ARE NOT BACK-TO-BACK IN WALLS AND TO LOCATE OUTLETS OFF COLUMNS (UNLESS VITAL THEY BE THERE) OR OTHER PLACES WHERE THEY CONFLICT WITH STRUCTURAL STEEL OR REINFORCING BARS.

C. CONTRACTOR SHALL ALSO MAINTAIN ON THE SITE A COMPLETE SET OF ALL SHOP DRAWINGS, EQUIPMENT LISTS, MANUFACTURER'S WIRING DIAGRAMS AND INSTALLATION DATA. INSTALLING PERSONNEL SHALL STUDY THESE DATA BEFORE AND DURING INSTALLATION AND ROUGH-IN SO AS TO BECOME FAMILIAR WITH PROPER AND FUNCTION UPON COMPLETION.

D. COMPLETE AND ADEQUATE HOUSING SHALL BE PROVIDED ON THE SITE FOR ORDERLY AND CAREFUL STORAGE OF ALL MATERIALS AND EQUIPMENT. NOTHING SHALL BE STORED WHERE EXPOSED TO WEATHER, EXCEPT CONDUIT, WHICH MAY BE STORED IN RACKS SO IT IS AT LEAST 12 INCHES ABOVE GROUND AND NOT SUBJECT TO MUD BEING SPATTERED ON IT.

E. ATTENTION IS DIRECTED SPECIFICALLY TO SPECIFICATION SECTIONS REQUIRING CONTINUOUS QUALITY CONTROL TESTING.

F. IN GENERAL, MOUNTING HEIGHTS OF DEVICES ARE NOT NOTED ON THE CONSTRUCTION DOCUMENTS. SCHEDULES AND NOTES SPECIFY "STANDARD" MOUNTING HEIGHTS FOR THESE ITEMS (SEE SPECS). STUDY CAREFULLY ELEVATIONS OF ALL WALLS AND CABINET WORK AS SHOWN ON ARCHITECTURAL DRAWINGS AND FIT OUTLETS TO SPACE AND TO AVOID CONFLICTS. OUTLETS SHALL ALWAYS BE LOCATED ABOVE, AND NOT IN, BACKSPLASHES. COORDINATE OUTLET LOCATIONS WITH OTHER TRADES TO AVOID CONFLICTS. ANY CONFLICT THAT CANNOT BE RESOLVED ON THE JOB SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT OR ENGINEER PRIOR TO ROUGH-IN.

G. BRANCH CIRCUIT WIRE SIZING WILL BE IN ACCORDANCE WITH THE FOLLOWING TABLES:

VOLTS	DISTANCE	HOME RUN	REMAINDER OF CIRCUIT
120/208	0' – 50'	#12	#12
	50' – 100'	#10	#12
	100' – 150'	# 8	#10

VOLTS	DISTANCE	HOME RUN	REMAINDER OF CIRCUIT
277/480	0' – 50'	#12	#12
	50' – 100'	#10	#12
	100' – 150'	# 8	#10

H. ALL RACEWAYS SHALL BE METAL UNLESS SPECIFICALLY NOTED OR APPROVED OTHERWISE. REFER TO SPECIFICATIONS FOR ALL OTHERS. ALL RACEWAY TO BE 3/4" MINIMUM.

I. NO MORE THAN ONE EXTENSION RING WILL BE ALLOWED PER JUNCTION BOX. EXISTING JUNCTION BOXES BEING REUSED SHALL COMPLY.

J. CONTRACTOR SHALL TEST ALL "LIFE SAFETY" EQUIPMENT AND SYSTEMS FOR PROPER FUNCTION AND OPERATION. UPON SUCCESSFUL COMPLETION OF TESTS, CONFIRMATION SHALL BE SENT TO THE ENGINEER OF RECORD, STATING THE TESTS PERFORMED, THE RESULTS, AND THE DATE TESTS WERE SUCCESSFULLY COMPLETE. "LIFE SAFETY" EQUIPMENT AND SYSTEMS CONSIST OF THOSE AS SPECIFIED IN NFPA 101 AND NFPA 99.

K. EXISTING PORTIONS OF THIS FACILITY ARE TO REMAIN IN OPERATION DURING THIS CONSTRUCTION. CONTRACTOR SHALL COOPERATE FULLY WITH THE ADMINISTRATION IN ORDER TO CAUSE AS LITTLE DISRUPTION AS POSSIBLE TO THE FUNCTIONING OF THE FACILITY, AND TO MAINTAIN THE COMFORT AND SAFETY OF ALL PERSONNEL AND STAFF.

L. PENETRATIONS OF REQUIRED SMOKE TIGHT PARTITIONS SHALL BE SEALED USING U.L. LISTED METHODS.

M. WHERE PENETRATIONS ARE MADE THROUGH A REQUIRED FIRE-RESISTIVE WALL, FLOOR, OR PARTITION FOR THE PURPOSE OF RUNNING RACEWAY CARRYING ELECTRICAL, TELEPHONE, TELEVISION, OR LOCAL COMMUNICATION AND/OR SIGNALING CIRCUITS, THE OPENING AROUND THE RACEWAY SHALL BE FIRE STOPPED. USE ONLY APPROVED ASSEMBLIES SUCH AS THE FOLLOWING:
CONDUIT PENETRATIONS OF 1 & 2 HOUR GYPBOARD WALLS – U.L.#WL1001
CONDUIT PENETRATIONS OF 1 & 2 HOUR CONCRETE OR BLOCK WALLS – U.L.#CAJ1001
CONDUIT PENETRATIONS OF 1 & 2 HOUR CONCRETE FLOORS – U.L.#CAJ1001

SEE DRAWINGS GI105 AND GI106, UL ASSEMBLIES, FOR DETAILING.

N. IN REQUIRED FIRE RATED WALLS AND PARTITIONS, OPENINGS FOR INSTALLATION OF BOXES THAT ARE GREATER THAN 16 SQUARE INCHES SHALL BE PROTECTED AS REQUIRED BY U.L. COORDINATE CLOSELY WITH THE OWNER AND ENGINEER TO INSURE THE INTEGRITY OF THE U.L. RATING IS MAINTAINED. BOXES OF 16 SQUARE INCHES OR LESS SHALL BE INSTALLED IN ACCORDANCE WITH U.L. "FIRE RESISTANCE RATINGS – ANSI/UL263 (BXUV) FOR WALL AND PARTITION ASSEMBLIES.

O. ALL ELECTRICAL MATERIALS, DEVICES, APPLIANCES AND EQUIPMENT SHALL BE U.L. LISTED AND LABELED.

P. PROVIDE CADDY TYPE METALLIC BOX SUPPORTS, (RBS OR SGB STYLE) BETWEEN TWO METAL STUDS FOR SUPPORTING ELECTRICAL BOXES RIGIDLY ON BOTH SIDES, IN LIEU OF SECURING BOX ONLY ON ONE SIDE WITH RIGHT ANGLE TYPE SUPPORT. EQUIVALENTS WITH LIKE FEATURES ACCEPTABLE.

Q. ALL PRODUCTS THROUGHOUT THIS PROJECT SHALL COMPLY WITH THE "BUY AMERICAN ACT" AS STATED IN THE SPECIFICATIONS WITHOUT EXCEPTION.

Order Plans Online
www.DLI.inc.com

REVISION NO.	REVISION DESCRIPTION	
Revisions		By Date

Department of Veterans Affairs
Charlie Norwood
VA Medical Center
1 Freedom Way
Augusta, Ga. 30904

NORTH CAROLINA REGISTERED SEAL 3857 ENGINEER JOHN G. ROSS 2/10/2017
SEAL

Architect/Engineer Address
Harrell, Saltrick & Hopper
Design & Management Solutions for the Built Environment
8016 TOWER POINT DRIVE CHARLOTTE, NC 28227
P 704.814.1220 F 704.321.0833
WWW.HSHPC.COM
COPYRIGHT © 2012 HARRELL SALTRICK & HOPPER, PC
HSH PROJECT # 12015

Recommended Approvals:	
1. MEDICAL CENTER DIRECTOR	6. OPERATIONS SERVICE LINE MANAGER
2. ASSISTANT DIRECTOR	7. INFECTION CONTROL MANAGER
3. CHIEF OF STAFF	8. SAFETY MANAGER
4. ASSOC. DIRECTOR	9. GENERAL ENGINEER
5. SERVICE LINE MGRS.	10. COR

Drawing Title: SYMBOLS, LEGENDS AND NOTES
100% CONSTRUCTION DOCUMENTS
FULLY SPRINKLERED

Project Title: RENOVATE MENTAL HEALTH UNITS
Drawn: WAO
Building Number:
AutoCAD File Name:
Checked:
Reviewed:
Const. Contract No.:

Date: February 10, 2017
Project Number: 509-12-104
DRAWING No. E001

Veterans Affairs