


Order Plans @

1 POWER DROP PLAN
1" = 20'-0"



KEYNOTES

16.145	CONNECT TO EXISTING BRANCH CIRCUIT. VERIFY PRIOR TO ROUGH-IN THAT EXISTING CIRCUIT HAS CAPACITY TO ACCOMMODATE NEW LOAD. VERIFY CONDITION OF BRANCH CIRCUIT, CONDUIT AND WIRE PRIOR TO USE TO INSURE THAT THEY MEET ALL U.L. RATINGS AND REPLACE AS REQUIRED.
16.489	RELOCATE, EXTEND, AND RECONNECT CIRCUITRY AND ELECTRICAL DEVICES FOR RELOCATED EQUIPMENT. VERIFY CONDITION OF BRANCH CIRCUITRY, CONDUIT AND WIRE TO ENSURE THEY MEET ALL U.L. RATINGS AND REPLACE AS REQUIRED. VERIFY FINAL LOCATION OF RELOCATED EQUIPMENT WITH WALMART CONSTRUCTION MANAGER PRIOR TO ROUGH-IN. CONNECT CIRCUIT(S) TO EXISTING BRANCH CIRCUITRY. MINIMUM WIRE SIZE AND PANELBOARD CIRCUIT ARE NOTED. VERIFY SIZE, RATING AND CONDITION OF EXISTING BRANCH CIRCUIT CONDUIT AND WIRE PRIOR TO USE TO ENSURE THAT THEY MEET REQUIRED SIZE, AND ALL U.L. RATINGS AND REPLACE AS REQUIRED.
16.957	

POWER DROP SCHEDULE

NO.	DESCRIPTION
PD1	MOUNT RECEPTACLE(S) ON TOP OF DISPLAY UNIT(S)
PD2	MOUNT RECEPTACLE(S) 6" ABOVE BASE OF DISPLAY UNIT(S) SO THAT RECEPTACLE(S) AND CONDUIT DO NOT INTERFERE WITH SHELF HEIGHT ADJUSTMENTS
PD3	PROVIDE DIRECT CONNECTION TO EQUIPMENT
PD4	OPEN STRUCTURE MOUNT RECEPTACLE AT BAR JOIST AND INSTALL FURNISHED CORD REEL. LAY-IN CEILING: PROVIDE RECESSED CEILING RECEPTACLE AND INSTALL FURNISHED CORD REEL BELOW CEILING. CORD REEL SHALL BE MOUNTED TO CEILING FAN RATED JUNCTION BOX SECURED TO LAY-IN CEILING WITH T-BAR BOX HANGER. PROVIDE 1/2" THREADED STEEL ROD FROM JUNCTION BOX TO BOTTOM OF STRUCTURAL JOIST OR CHANNEL STRUT BRIDGING ABOVE FOR SUPPORT.

POWER DROP NOTES

NO.	DESCRIPTION
1	POWER DROPS WILL BE IDENTIFIED BY AN IPTV TAG OR POWER TAG, I.E. 44A, 46E, ETC. ALL CHECKOUT POWER SHALL BE CONSIDERED POWER DROPS.
2	A REVISION OF THIS PLAN BASED ON THE FINAL MERCHANDISE LAYOUT MAY BE ISSUED TO SHOW FINAL LOCATIONS FOR THE POWER DROPS. IF THE MERCHANDISE PLAN DOES NOT CHANGE THIS PLAN WILL NOT BE REISSUED. PROVIDE CIRCUITRY TO DISPLAY TRACKS AS THE TRACKS ARE SET. IN ADDITION, THE FOLLOWING POWER DROP NOTES APPLY: A. THERE WILL BE NO ADDITIONAL CHARGE FOR DROP RELOCATION WITHIN POWER DROP ZONES DEFINED ON DRAWING. B. AT CLOSE OF PROJECT THE GENERAL CONTRACTOR AND CONSTRUCTION MANAGER SHALL REVIEW ADDITIONAL OR DELETED POWER DROPS. EACH ZONE TO VERIFY ANY ADDITIONAL CHARGE CREDITS THAT APPLY DUE TO CHANGES. C. ADDING OR SUBTRACTING POWER DROPS TO ANY ZONE WILL RESULT IN A CREDIT OR DEBIT, ACCORDING TO SPECIAL CONDITIONS.
3	PROVIDE JUNCTION BOX AND CIRCUITRY TO NEW POWER DROPS ABOVE LOCATION SHOWN ON DRAWING. CONDUIT AND CIRCUITRY FROM JUNCTION BOX TO END OF DISPLAY RACK AWAY FROM ACTION ALLEY. FINAL CONDUIT, RECEPTACLE AND FINAL CONNECTIONS AT DISPLAY RACK SHELVING PER POWER DROP SCHEDULE UNLESS NOTED OTHERWISE ON DRAWING. VERIFY EXACT HEIGHT LOCATION OF RECEPTACLE(S) WITH STORE PLANNING SET-UP SUPERVISOR PRIOR TO INSTALLATION. POWER DROPS FED FROM TRACK BUSWAY: POWER DROPS FED FROM TRACK BUSWAY AT POWER ARREST TO POWER DROP(S)

CONTRACTOR TO PURCHASE AND INSTALL NEW STARLINE BUS CIRCUIT BREAKER PLUG-IN UNITS AS REQUIRED.
CONTACT: MEGREPS, JON MATTHEWS OR RANDY MATTHEWS (501) 821-2203 EXT. 301. WALMART@MEGREPS.COM



RETAIL DESIGN COLLABORATIVE
1001 E. 37th St. #100
Tulsa, OK 74109
711.53.65
rdcoll.com

STIPULATION FOR THE CONTRACTOR TO VERIFY THE EXISTING CONDITIONS PRIOR TO ROUGH-IN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING THE EXISTING CONDITIONS AND NOTIFY THE ARCHITECT IMMEDIATELY IN WRITING OF ANY DISCREPANCIES OR OMISSIONS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND INSURANCE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY APPROVALS FROM THE LOCAL AUTHORITIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY APPROVALS FROM THE LOCAL AUTHORITIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY APPROVALS FROM THE LOCAL AUTHORITIES.

CONSULTANTS
JASON C. ADAMS
ARCHITECT
1411 N. W. 11th St.
Tulsa, OK 74103
918.438.4477
jadam@jadamarch.com
PROJECT NO. 1852-223
ISSUED BY: JAD

Walmart
GORDONSVILLE, VA
164 CAMP CREEK PKWY., LOUISA, VA 23083
STORE NO.: 1852-223
17-127-25
143 SGROR

ISSUE BLOCK

NO.	DESCRIPTION	DATE

CHECKED BY: BMD
DRAWN BY: JRL
PROTO CYCLE: 02/23/18
DOCUMENT DATE: 04/10/18
BG PROJECT NO: 1852
This document is original and issued by Janna Christopher Adams, P.E. REG. 312 on 08/09/2018. This document should not be considered a certified document. NOT FOR CONSTRUCTION

POWER DROP PLAN

SHEET: E2.1

EACH SUBCONTRACTOR IS RESPONSIBLE FOR HAVING A THOROUGH KNOWLEDGE OF ALL DRAWINGS AND SPECIFICATIONS IN THEIR RELATED FIELD. THE FAILURE TO ACQUAINT THEMSELVES WITH THIS KNOWLEDGE DOES NOT RELIEVE THE RESPONSIBILITY OF PERFORMING THE WORK PROPERLY. NO ADDITIONAL COMPENSATION SHALL BE ALLOWED BECAUSE OF CONDITIONS THAT OCCUR DUE TO FAILURE TO FAMILIARIZE WORKERS WITH THIS KNOWLEDGE.
EXISTING CONDITIONS WERE TAKEN FROM ORIGINAL DRAWINGS AND MAY NOT REFLECT EXACT "AS-BUILT" CONDITIONS. CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS PRIOR TO SUBMITTING FINAL BIDS. CONTRACTOR SHALL CAREFULLY COORDINATE NEW WORK AND DEMOLITION WITH ALL OTHER DISCIPLINES AND EXISTING CONDITIONS.