MATERIAL FINISH SCHEDULE

V-1.0

GROUP	TAG	DESCRIPTION	PRODUCT	COLOR/FINISH	MFR.	DETAILS	REMARKS	NOTES
FLOORING	F-1	STAINED & POLISHED CONCRETE	CLASSIC	GOLD	AMERIPOLISH	APPLICATION PER MANUFACTURER DIRECTIONS	REFERENCE FLOOR FINISH PLAN FOR CONC. SLAB AREAS TO RECEIVE STAIN & SEALER.	F2, F3, GN-10
	F-2	SEALED CONCRETE	MASTERKURE CC 300SB	TRANSPARENT - GLOSS	BASF	2-PART APPLICATION TO BE INSTALLED PER MANUFACTURER DIRECTIONS	REFERENCE FLOOR FINISH PLAN FOR CONC. SLAB AREAS TO RECEIVE SEALER	F6
	F-3	SEALED CONCRETE (FREEZER)	CLEARPROTECT SOLVENT-BASED CURE AND SEAL	TRANSPARENT - GLOSS	H&C	ADD "SHARKGRIP" NON-SLIP ADDITIVE PER MANUFACTURER DIRECTIONS	REFERENCE FLOOR FINISH PLAN FOR SLAB AREAS TO RECEIVE FINISH	F5
	F-4	EPOXY (GRAY)	EVERLAST EPOXY	ELEGANT GRAY	EVERLAST		REFERENCE FINISH SCHEDULE FOR LOCATIONS	F9
	F-5	EPOXY (RED)	EVERLAST EPOXY	CHEROKEE RED	EVERLAST		REFERENCE FINISH SCHEDULE FOR LOCATIONS	F9
	F-6	WALK-OFF MAT					SUPPLIED & INSTALLED BY LM FLOORING VENDOR	
	F-7	QUARRY TILE - GRAY	QUARRY TILE	ASHEN GRAY OT03	DAL-TILE	ALTERNATE BID - INSTALLER TO CONFIRM FLOOR LEVELING REQUIREMENT PRIOR TO BID INSTALLATION	THINSET GROUT: 24 NATURAL GREY - LATICRETE	F1
	F-8	QUARRY TILE - RED	QUARRY TILE	& DIABLO RED OT01	DAL-TILE	ALTERNATE BID - INSTALLER TO CONFIRM FLOOR LEVELING REQUIREMENT PRIOR TO BID INSTALLATION	THINSET GROUT: 46 QUARRY RED - LATICRETE	F1
	F-9	CONCRETE		NATURAL			NO FINISH	F7
BASE	B-1	VINYL BASE	4"	V4860 - JET BLACK	ARMSTRONG	DO NOT CUT AT CORNERS, SCRIBE IF NECESSARY	REFERENCE FINISH SCHEDULE FOR LOCATIONS	W5, W6, GN-4, GN-5
	B-2	EPOXY - 1 GRAY	EVERLAST EPOXY	ELEGANT GRAY	EVERLAST	APPLICATION PER MANUFACTURER DIRECTIONS	REFERENCE FINISH SCHEDULE FOR LOCATIONS	F9
	B-3	EPOXY -2 RED	EVERLAST EPOXY	CHEROKEE RED	EVERLAST	APPLICATION PER MANUFACTURER DIRECTIONS	REFERENCE FINISH SCHEDULE FOR LOCATIONS	F9
	B-4	QUARRY TILE BASE - GRAY	QUARRY TILE	ASHEN GRAY OT03	DAL-TILE	Alternate Bid - INSTALLER TO CONFIRM FLOOR LEVELING REQUIREMENT PRIOR TO BID INSTALLATION	GROUT: 24 NATURAL GREY - LATICRETE	F1
	B-5	QUARRY TILE BASE - RED	QUARRY TILE	DIABLO RED OT01	DAL-TILE	Alternate Bid - INSTALLER TO CONFIRM FLOOR LEVELING REQUIREMENT PRIOR TO BID INSTALLATION	GROUT: 46 QUARRY RED - LATICRETE	F1
	B-6	2x4 WOOD	2" X 4" RECLAIMED OAK	TRANSPARENT - SATIN	-	USE AS BASE BELOW GALVALUME- COORDINATE INSTALLATION WITH MILLWORK CONTRACTOR	REQUIRED FLAME RETARDANT FINISH	GN-1, G8
	B-7	2x8 PT WOOD	PRESSURE TREATED 2" X 8"	PAINTED PURE WHITE SEMI-GLOSS	-	PRESSURE TREATED-PAINTED PURE WHITE		GN-1, G8
WALLS	W-1	TAPED & PATCHED	-	-	-	MUD AND TAPE ONLY, NO PRIME OR PAINT		W2
	W-2	PAINT: (WHITE ON WHITE)	SATIN ACRYLIC GLN6211N SERIES	GLDC 26	GLIDDEN	COORDINATE APPROPRIATE BASE FROM GLN6211 SERIES WITH PAINT COLOUR CODE	REFERENCE FINISH SCHEDULE & PLANS FOR LOCATIONS	P1 - P17, G3, GN3
	W-3	PAINT: (CHOCOLATE FROTH)	SATIN ACRYLIC GLN6211N SERIES	BEHR #720C-2	GLIDDEN	COORDINATE APPROPRIATE BASE FROM GLN6211 SERIES WITH PAINT COLOUR CODE	REFERENCE FINISH SCHEDULE & PLANS FOR LOCATIONS	P1 - P17, G3, GN3
	W-4	PAINT (PACIFIC PINES)	SATIN ACRYLIC GLN6211N SERIES	HDGG25	GLIDDEN	COORDINATE APPROPRIATE BASE FROM GLN6211 SERIES WITH PAINT COLOUR CODE	REFERENCE FINISH SCHEDULE & PLANS FOR LOCATIONS	P1 - P17, G3, GN3
	W-5	PAINT (STOLEN KISSES)	SATIN ACRYLIC GLN6211N SERIES	SW 7586	GLIDDEN	COORDINATE APPROPRIATE BASE FROM GLN6211 SERIES WITH PAINT COLOUR CODE	REFERENCE FINISH SCHEDULE & PLANS FOR LOCATIONS	P1 - P17, G3, GN3
	W-6	Paint (Chalkboard)	KRYLON	CHALKBOARD - BLACK	KRYLON	ACCENT WALL	REFERENCE FINISH SCHEDULE & PLANS FOR LOCATIONS	P1 - P17, G3, GN3
	W-7	PRIMER			GLIDDEN	COORDINATE APPROPRIATE PRIMER FOR FINISH COLOUR		P1 - P17, G3
	W-8	CORRUGATED METAL	MULTI-CORE GALVALUME PLUS 26	STANDARD	MCELROY	26 GAUGE - 33-1/2" GP80 PANELS. CORRUGATED HEAD TRIM 26 BARE X LF	ABOVE 42" HT: SEE FINISH PLAN FOR FINISH (IF ANY) ABOVE CORRUGATED METAL	GN-1, G8
	W-9	SYNTHETIC WOOD	TRIM BOARD	-	-	COORDINATE INSTALLATION WITH GC	INSTALLED BY MILLWORK CONTRACTOR	GN-1, G8
	W-10	1" x 4" CHAIR RAIL	BEETLE KILL / BLUE PINE	Transparent Fire Proof	Beatle Board 1x4	TONGUE & GROOVE, WITH FIRE RETARDANT CLEAR FINISH	ABOVE J-CHANNEL INSTALL 1" X 4" BLUE PINE/BEETLE KILL (GLUE & PIN)	GN-1, G8
	W-11	FRP (White) SUBWAY TILE	SYMMETRIX FRP	C 100-G63 White	MARLITE	SUBWAY TILE	REFER TO PLANS FOR LOCATION(S)	W1
	W-12	FRP (WHITE) PEBBLED SURFACE	STANDARD FRP	P 100 White	MARLITE	PEBBLED SURFACE	REFER TO PLANS FOR LOCATION(S)	W1
	W-13	FRP TILE (SILVER)	Symmetrix FRP	C 145-G44 SILVER	MARLITE	3X3 TILE	REFER TO PLANS FOR LOCATION(S)	W1
	W-14	FACTORY FINISH (GALVANIZED)	COOLER WALLS	GALVANIZED	-	BY MANUFACTURER	COOLERS/FREEZERS	W3
	W-15	FACTORY FINISH (WHITE)	COOLER WALLS	WHITE	-	BY MANUFACTURER	MEAT CUTTING ROOM/COOLER	W3
	W-16	5/8" PLYWOOD	5/8" ACX PLYWOOD	NATURAL	NONE	FIRE RETARDANT TREATED WHEN APPLIED DIRECTLY TO STUDS	48" BOH WAINSCOT. INSTALL WITH TIGHT NEAT JOINTS AND CORNERS.	G7
	W-17	T&G BEETLE KILL/BLUE PINE	BEETLE KILL / BLUE PINE T&G	CLEAR FIRE PROOF FINISH	-	MUST MEET CLASS C REQUIREMENTS	REFER TO PLANS FOR LOCATION(S)	GN-1, G8
	W-18	SHEET METAL WALL PROTECTION	STAINLESS STEEL	STANDARD	-	18 GAUGE	PROVIDED BY GC ALLOWANCE	GN-1, G8
	W-19	CHICKEN WIRE	-	-	-	USED AS ACCESS PREVENTION ABOVE COOLER BOXES	-	
	W-20	RECLAIMED OAK	TRIM BOARD	CLEAR FIRE PROOF FINISH	-	COORDINATE INSTALLATION WITH GC	INSTALLED BY MILLWORK CONTRACTOR	GN-1, G8
CEILING	C-1	EXPOSED (PAINTED) GENTLE CREAM	WATERBORNE INTERIOR FLAT DRY FALL 1280-1200	SW-6357	SHERWIN WILLIAMS	"CHOICE" CREAM	REFERENCE FINISH SCHEDULE FOR LOCATIONS	P4, 6, P9, P15,
	C-2	2x4 CEILING TILE	PERFORATED CEILING TILE	WHITE	ARMSTRONG	CORTEGA-24" x 48" PERFORATED ACT - WHITE	CEILING GRID "WHITE" TO MATCH TILE COLOR	
	C-3	2x4 CEILING TILE (VINYL)	VINYL COATED CEILING TILE	WHITE	ARMSTRONG	24" x 48" NON-PERFORATED ACT - WHITE	CEILING GRID "WHITE" TO MATCH TILE COLOR	C1, C3
	C-4	PAINT: (WHITE ON WHITE)	FLAT ACRYLIC GLN90XX	GLDC 26	GLIDDEN	COORDINATE APPROPRIATE BASE FROM GLN90XX SERIES WITH PAINT COLOUR CODE	REFER TO PLANS FOR LOCATION(S)	P2, P4, P9, P11, G3
	C-5	FACTORY FINISH	-	-	PER MFR.	-	COOLERS/FREEZERS	W3,
	C-6	EXPOSED (UN-PAINTED)	-	-	-	-	REFER TO PLANS FOR LOCATION(S)	
	C-7	2x2 CEILING TILE (VINYL)	VINYL COATED CEILING TILE	WHITE	ARMSTRONG	24" x 24" NON-PERFORATED ACT - WHITE	CEILING GRID "WHITE" TO MATCH TILE COLOR	C1, C3
MISC.	M1	STAINLESS STEEL PLATE	CORNER GUARDS	18 GA. S.S. PLATE	-	BOTTOM 48" ON COLUMNS. SECURE W/ STAINLESS STEEL ROUNDHEAD SHEET METAL SCREWS. SEAMS TO FACE REAR OF STORE.	APRON AT COMPACTOR DOOR. CLOSURE PANELS @ DELI WALL/HOOD. PROVIDED BY LM METALWORK VENDOR	GN-1, G8
		DOORS & WINDOWS						
	D1	SC WOOD DOOR	5-PLY	OAK - CLEAR LOW SHEEN	-	PRE-FINISHED	REFER TO SPECIFICATIONS	
	D2	SC WOOD DOOR W/ WINDOW	5-PLY	OAK - CLEAR LOW SHEEN	-	PRE-FINISHED	REFER TO SPECIFICATIONS	
	D3	HM DOORS	ALKYD SEMI-GLOSS PAINT 1507-XXX	SW-6258 TRICORN BLACK	GLIDDEN	-	REFER TO SPECIFICATIONS	
	D4	HM FRAME	ALKYD SEMI-GLOSS PAINT 1507-XXX	SW-6258 TRICORN BLACK	GLIDDEN	-	REFER TO SPECIFICATIONS	
	D5	Welded Metal Frame	ALKYD SEMI-GLOSS PAINT 1507-XXX	SW-6258 TRICORN BLACK	GLIDDEN	-	REFER TO SPECIFICATIONS	
	D6	TRAFFIC DOOR (SALES)	502002	BLACK	CHASE	WITH TEARDROP BUMPERS & ADA WINDOW(S)	REFER TO SPECIFICATIONS	
	D7	TRAFFIC DOOR FRAME (SALES)	ALKYD SEMI-GLOSS PAINT 1507-XXX	SW-6258 TRICORN BLACK	GLIDDEN	-	REFER TO SPECIFICATIONS	
	W1	HM WINDOW FRAME	ALKYD SEMI-GLOSS PAINT 1507-XXX	SW-6258 TRICORN BLACK	GLIDDEN	-	REFER TO SPECIFICATIONS	
FIXTURES	FX1	CART BUMPER			McCUE	FLOOR MOUNTED - CARTSTOP	PROVIDED & INSTALLED BY LM VENDOR	
	FX2	RESTROOM PARTITIONS	SOLID PHENOLIC	LIMOUSINE-GREY	BOBRICK	FLOOR MOUNT, OVERHEAD BRACED at 8'-0" PARTITIONS	-	GN-1, G8
	FX3	CART CORAL	720 Series	Galvanized, 30FT LENGTH	National Cart	Custom Signage - Coordinate with Lucky's Market	-	

GENERAL NOTES:

- GN-1 REFER TO RESPONSIBILITY SCHEDULE FOR ADDITIONAL INFORMATION
- GN-2 NOT USED
- GN-3 WHERE CASES OR SHELVING ARE IN FRONT OF A FINISHED WALL, TERMINATE WALL FINISHES 12" BEHIND FIXTURE, AND USE PRIMER BELOW
- GN-4 VINYL BASE TO BE INSTALLED BY GC ON WALLS, COOLER AND FREEZER WALLS. - DO NOT INSTALL VINYL BASE WHERE FIXTURES OR CASES WILL BE INSTALLED.
- GN-5 MILLWORK SUPPLIER TO INCLUDE VINYL BASE ON MILLWORK WHICH MATCHES LUCKY'S MARKET STANDARD
- GN-6 COOLER AND FREEZER WALLS SHALL BE SET IN A WATERTIGHT SEAL TO THE FLOOR PROVIDED BY THE COOLER INSTALLER.
- GN-7 ALL COUNTERTOPS, TABLE TOPS, BUTCHBLOCK BY MILLWORK CONTRACTOR TO BE SEALED WITH FOOD SAFE CLEAR EPOXY
- GN-8 ALL INTERIOR WALL AND FLOOR FINISHES ARE REQUIRED TO MEET THE ASTME84 STANDARDS FOR CLASS C CONSTRUCTION
- GN-9 ALL INTERIOR WOOD TRIM IS REQUIRED TO MEET NFPA701 CLASS C FLAME SPREAD INDEX, 76-200 SMOKE DEVELOPED INDEX 0-450
- GN-10 AMERIPOLISH CONCRETE STAIN SYSTEM:
  1. VERIFY SLAB AND ALL PATCHED AND LEVELED AREAS OF SLAB TO BE STAINED HAVE CURED FOR A MINIMUM OF 28 DAYS. BEFORE APPLICATION VERIFY A MAXIMUM MOISTURE CONTENT OF 5 POUNDS PER 1000 SQUARE FEET IN 24 HOURS.
  2. REMOVE ALL PREVIOUS COATINGS, FILL JOINTS, AND CLEAN CONCRETE IN STRICT ACCORDANCE WITH STAIN MANUFACTURER'S RECOMMENDATIONS.
  3. GRIND SURFACE OF SLAB TO CPAA CLASS C-MEDIUM AGGREGATE 400 GRIT LEVEL.
  4. APPLY 2 COATS OF AMERIPOLISH CLASSIC COLOR SOLVENT-BASED CONRETE DYE (COLOR: GOLD) IN STRICT ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
  5. POLISH SURFACE OF SLAB TO 800 GRIT LEVEL.
  6. APPLY AMERIPOLISH 3D HS DENSIFIER AND POLISH TO FINISHED GLOSS LEVEL 2 - MEDIUM GLOSS.
  7. APPLY PROGUARD STAIN SHEILD IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.
  8. PROTECT FINISHED FLOOR FROM TRAFFIC, WEATHER AND ALL CAUSTIC OR ACIDIC CHEMICALS OR DETERGENTS FOR BALANCE OF CONSTRUCTION.
  9. KEEP SURFACE CLEAN AT ALL TIMES. REMOVE DRY SOILS ON A DAILY BASIS. WET CLEAN USING PROGUARD SERIES CONDITIONING CLEANER IN A WALK-BEHIND SCRUBBER OR A BUCKET AND MOP. DRY BUFF A DRY, CLEAN [illegible] TO TURNING OVER TO OWNER.

ROOM FINISH SPECIFICATIONS

PAINT SPECS.

- P1 OBTAIN BLOCK FILLERS, PRIMERS AND UNDERCOAT MATERIALS FOR EACH COATING SYSTEM FROM THE SAME MANUFACTURER AS THE FINISH COATS.
- P2 PAINT ALL EXPOSED SURFACES, UNLESS OTHERWISE INDICATED.
- P3 DO NOT PAINT PREFINISHED ITEMS, FINISHED METAL SURFACES, OPERATING PARTS, LABELS AND MATERIALS OBVIOUSLY INTENDED TO BE LEFT EXPOSED SUCH AS BRICK AND TILE. DO NOT PAINT CONCEALED SURFACE WITH THE FOLLOWING EXCEPTIONS:
  A. LABEL MECHANICAL PIPING IN ACCESSIBLE CEILING SPACES.
  B. PAINT THE BACK SIDE OF ACCESS PANELS.
  DELIVER TO LUCKY'S MARKET, A 1 GAL. (3.8 LITER) CONTAINER, PROPERLY LABELED AND SEALED, OF EACH COLOR AND TYPE OF FINISH COAT PAINT USED ON THE PROJECT. CONTAINER TO BE TURNED OVER TO LUCKY'S MARKET REPRESENTATIVE ON SITE.
- P4 MANUFACTURER'S BEST QUALITY MATERIAL BY GLIDDEN OR LUCKY'S MARKET APPROVED EQUAL
- P5 SEE DRAWINGS FOR LOCATION OF PAINT COLORS. FINAL COLORS TO BE SELECTED BY LUCKY'S MARKET.
- P6 PAINT EXPOSED ROOF STRUCTURE, ROOF DECKING, EXPOSED PIPE CONDUIT, WIRING DEVICE BOXES, COVERPLATES, BRACING, SUPPLEMENTAL SUPPORTS, ALL HANGING LIGHT FIXTURE HARDWARE, CONDUITS: GENTLE CREAM. DO NOT PAINT SPRINKLER SYSTEM HEADS. GLIDDEN PRODUCT WATERBORNE INTERIOR FLAT DRY FALL 1280-1200. REFER TO SPECIFICATIONS FOR COLOR FORMULA
- P7 PAINT OTHER AREAS AND ROOMS IN OTHER COLORS PER THE CONSTRUCTION DOCUMENTS AND AS DIRECTED BY LUCKY'S MARKET.
- P8 WOOD TREATMENT. not used
- P9 COMPLY WITH PAINT MANUFACTURER'S WRITTEN INSTRUCTIONS FOR SURFACE PREPARATION, ENVIRONMENTAL AND SUBSTRATE CONDITIONS, PRODUCT MIXING AND APPLICATION.
  a) GYPSUM BOARD: SATIN, LOW-LUSTER, LATEX: (2) COATS OVER PRIMER.
  b) CLEAR COAT WOODWORK:
     1. WOOD PRIDE 1800 SATIN (OR LUCKY'S MARKET APPROVED EQUAL) ON 2" X 4" BASEBOARDS - BY LUCKY'S MILLWORK CONTRACTOR.
     2. (2) COATS CLEAR FOOD-SAFE SEALER ON RECLAIMED OAK AT JUICE BAR TOP- BY LUCKY'S MARKET MILLWORK CONTRACTOR.
     3. KLEAR KOAT TABLE TOP EPOXY ON ALL COUNTERTOPS, BAR TOPS, TABLE TOPS - BY LUCKY'S MARKET MILLWORK CONTRACTOR.
     4. RAW LINSEED OIL ON BUTCHER BLOCK – BY LUCKY'S MARKET MILLWORK CONTRACTOR.
  c) FERROUS METALS. (AS FOLLOWS)
     1. SEMI-GLOSS ACRYLIC: ONE COAT OVER UNDERCOATER AND PRIMER
- P10 PAINT TO BE NON COMBUSTIBLE WHEN USED ON DELI GREASE DUCTWORK
- P11 SEE DRAWINGS FOR LOCATIONS OF MULTIPLE WALL FINISHES IN ANY ONE ROOM.
- P12 CLEAN, TREAT AND PAINT EXPOSED SURFACES OF HOLLOW METAL DOOR AND FRAME UNITS. APPLY SHOP COAT OF PRIME PAINT ON EVEN CONSISTENCY TO PROVIDE A UNIFORMLY FINISHED SURFACE READY TO RECEIVE FINISH PAINT.
- P13 ALL EXPOSED WOOD TRIM, DOORS AND FRAMES TO COMPLY WITH APPLICABLE REQUIREMENTS OF REFERENCED AWI STANDARD FOR TYPES OF FINISH SYSTEMS INDICATED.
- P14 PAINT EXPOSED SURFACES WHETHER OR NOT COLORS ARE DESIGNATED IN "SCHEDULES", EXCEPT WHERE A SURFACE OR MATERIAL IS SPECIFICALLY INDICATED NOT TO BE PAINTED OR IS TO REMAIN NATURAL. WHERE AN ITEM OR SURFACE IS NOT SPECIFICALLY MENTIONED, PAINT THE SAME AS SIMILAR ADJACENT MATERIALS OR SURFACES. IF COLOR OR FINISH IS NOT DESIGNATED, THE LUCKY'S CONSTRUCTION MANAGER WILL SELECT FROM STANDARD COLORS OR FINISHES AVAILABLE
- P15 PAINTING INCLUDES FIELD PAINTING EXPOSED BARE AND COVERED PIPES AND DUCTS (INCLUDING COLOR CODING), HANGERS, EXPOSED STEEL AND IRON WORK, AND PRIMED METAL SURFACES OF MECHANICAL AND ELECTRICAL EQUIPMENT.
- P16 PAINTING IS NOT REQUIRED ON PREFINISHED ITEMS, FINISHED METAL SURFACES, CONCEALED SURFACES, OPERATING PARTS AND LABELS.
- P17 PAINT THE INTERIOR FACE OF THE EXTERIOR DOORS AND FRAMES BLACK, SEMI-GLOSS LATEX. SEE MATERIAL FINISH SCHDULE FOR COLOR FORMULA.
- P18 ACCENT WALL PAINT COLOUR TO BE APPLIED TO WALL OPPOSITE THE ENTRY DOOR TO THE ROOM

FLOOR NOTES

- F1 ALL QUARRY FLOOR TILE AS SCHEDULED SHALL CONFORM WITH ADAAG REQUIREMENTS FOR SLIP RESISTANCE. WITH A 4" COVED BASE. CONFIRM MIN. BASE HT REQUIRMENT WITH LOCAL JURISTICTION. ALL FLOOR AND BASE GROUT SHALL BE LATAPOXY SP-100 STAINLESS EPOXY GROUT IN COLORS TO APPROXIMATE THE TILE COLOR USED AT EACH LOCATION. SEE FINISH SCHDEULE FOR GROUT SELECTIONS.
- F2 TERMINATE SALES FLOOR STAINED & SEALED CONCRETE FINISH AT THE DELI/BAKERY; MEAT/SEAFOOD AISLES, AND GRAB & GO ISLAND AT CENTER OF CASE AS NOTED ON THE FLOOR FINISH PLAN.
- F3 TERMINATE SALES FLOOR STAINED & SEALED CONCRETE FINISH AT JUICE ISLAND AT INSIDE EDGE OF OF PARTITION.
- F4 APPLY CLEAR SILICONE SEALANT AT JOINT BETWEEN WALL AND TOP OF WALL BASE
- F5 FREEZER FLOOR CONCRETE SEALER TO BE SLIP RESISTANT & ADEQUATE FOR COLD TEMP (-20 F) CONDITIONS - CLEARPROTECT BY H&C. PROVIDE "SHARKGRIP" NON-SLIP ADDITIVE.
- F6 CONCRETE FLOORS TO BE SEALED - MASTERKURE CC 300 SB - 30% SOLID (TYPICAL)
- F7 GENERAL CONTRACTOR TO INSTALL CONCRETE FLOOR SLAB IN BOH AS PER SPECIFICATIONS INCLUDING CURING COMPOUND.NO ADDITIONAL FINISH REQUIRED
- F8 SEE DRAWINGS FOR LOCATIONS OF MULTIPLE FLOOR FINISHES IN ANY ONE ROOM.
- F9 EVERLAST EPOXY FLOOR SYSTEM SHALL BE INSTALLED ON FLOOR AT LEAST 1/8" THICK WITH A 4" INTEGRAL SANITARY COVE BASE. CONFIRM MIN. BASE HT REQUIREMENT WITH LOCAL JURISTICTION.

WALL NOTES

- W1 PROVIDE FRP WALL PANELS AS INDICATED BY WALL FINISHES NOTED ON PLAN. INSTALL DIRECTLY ON MOISTURE RESISTANT GWB SUBSTRATE AS RECOMMENDED BY THE MFR. MAKE FULL USE OF THE ACCESSORIES AND ADHESIVES FOR A COMPLETE AND SANITARY WALL FINISH.
- W2 WALL TO BE GWB - MUDDED & TAPED - UNPAINTED. SEE FINISH SCHEDULE.
- W3 ALL COOLER AND FREEZER WALLS TO BE STANDARD FACTORY FINISH. MEAT CUT ROOM/COOLER INTERIOR FINISH SHALL BE WHITE.
- W4 ALL STOCKROOM WALLS TO BE PAINTED TO DECK.
- W5 VINYL BASE TO BE INSTALLED PER FINISH SCHDULE BY GENERAL CONTRACTOR. DO NOT INSTALL BEHIND CASES AND FIXTURES.
- W6 VINYL BASE AT ALL FIXTURES PROVIDED BY MILLWORK CONTRACTOR TO BE INSTALLED BY MILLWORK CONTRACTOR AND MATCH LOCATION STANDARD VINYL BASE.

CEILING NOTES

- C1 CEILING TILE IN PREP AREAS SHALL BE VINYL-COATED, USDA ACCEPTED, NON-PERFORATED, LAY-IN ACOUSTICAL TILE.
- C2 NOT USED
- C3 PAINT UNDERSIDE OF ALL VALANCE WALLS AND SOFFITS W-2. SEE MATERIAL FINISH SCHDULE FOR COLOR FORMULA.
- C4 PROVIDE HOLD DOWN CLIPS FOR LAY-IN SYSTEM IN VESTIBULE. COORDINATE INSTALLATION WITH LUCKY'S MARKET FOR SIGN INSTALLATION.
- C5 PAINT GWB CEILINGS W-2. SEE MATERIAL FINISH SCHDULE FOR COLOR FORMULA.

GENERAL CEILING NOTES:

1. LAY-IN PANELS AND GRID TO BE ARMSTRONG, CORTEGA, RECTANGULAR, 48"X24"X5/8" OR 24"X24"X5/8", WHITE 15/16" PRELUDE GRID, WHITE.
2. ATTACHMENT DEVICES SHALL BE SIZED FOR 5 TIME THE DESIGN LOAD INDICATED IN THE ASTM C635, TABLE 1, DIRECT HUNG.
3. HANGER WIRE SHALL BE GALVANIZED CARBON STEEL WIRE, ASTM A641, SOFT TEMPER, PRE-STRETCHED, CLASS 1 COATING, SIZED SO THAT STRESS AT 3 TIMES HANGER DESIGN LOAD (ASTM C635, TABLE 1, DIRECT HUNG). WILL BE LESS THAN YIELD STRESS OF WIRE, BUT PROVIDE NOT LESS THAN 12 GAUGE.
4. DOUBLE WEB STEEL SUSPENSION SYSTEM SHALL BE MANUFACTURER'S STANDARD SYSTEM ROLL FORMED FROM PRE FINISHED COLD-ROLLED STEEL SHEET WITHIN 15/16" WIDE EXPOSED FACES ON STRUCTURAL MEMBERS. STRUCTURAL CLASSIFICATION SHALL BE INTERMEDIATE-DUTY SYSTEM. FINISH SHALL BE PAINTED WHITE.
5. INSTALL SUSPENSION SYSTEM TO COMPLY WITH ASTM C636, WITH HANGERS SUPPORTED ONLY FROM BUILDING STRUCTURAL MEMBERS. LOCATE HANGERS NOT LESS THAN 6" FROM EACH END AND SPACED 4'-0" ALONG EACH CARRYING CHANNEL OR DIRECT-HUNG RUNNER, UNLESS OTHERWISE INDICATED, LEVELING TO TOLERANCE OF 1/8" IN 12'-0".
   A. SECURE WIRE HANGERS BY LOOPING AND WIRE-TYING, EITHER DIRECTLY TO STRUCTURES OR TO INSERTS, EYE-SCREWS, OR OTHER DEVICES WHICH ARE SECURE AND APPROPRIATE FOR SUBSTRATE, AND WHICH WILL NOT DETERIORATE OR FAIL WITH AGE OR ELEVATED TEMPERATURES.
   B. INSTALL HANGERS PLUMB AND FREE FROM CONTACT WITH INSULATION OR OTHER OBJECTS WITHIN CEILING PLENUM WHICH ARE NOT PART OF SUPPORTING STRUCTURAL OR CEILING SUSPENSION SYSTEM. SLPAY HANGERS ONLY WHERE REQUIRED TO MISS OBSTRUCTION AND OFFSET RESULTING HORIZONTAL FORCE BY BRACING, COUNTER-SPLAYING OR OTHER EQUALLY EFFECTIVE MEANS.
6. NOTE: THE ACOUSTICAL CEILING SUBCONTRACTOR SHALL:
   A. INSTALL HANGER WIRE AS SPECIFIED ABOVE EACH CORNER OF THE GRID AT EVERY LIGHT, AIR DIFFUSER, AIR RETURN GRILL AND OTHER EQUIPMENT ITEMS WHICH ARE IN[illegible] WITHIN OR PENETRATE THE CEILING SYSTEM.
   B. INSTALL EDGE MOLDINGS AT PERIMETER OF ACOUSTICAL CEILING AREA AND AT LOCATIONS WHERE NECESSARY TO CONCEAL EDGES OF ACOUSTICAL UNITS.
7. 7. PROVIDE UNI-STRUT SUPPORTS ABOVE TO SPAN BAR JOISTS AS REQUIRED.

GENERAL NOTES

- G1 PAINT HOLLOW METAL DOORS AND HOLLOW METAL FRAMES AND OTHER SURFACES NOT SCHEDULED TO RECEIVE OTHER FINISHES. COORDINATE C[illegible]ORS WITH L[illegible]RKET.
- G2 TOILET ROOM GRAB BARS, TOILET PARTITIONS, MIRRORS, BABY CHANGING STATIONS BY G.C. PAPER & SOAP DISPENSERS BY LUCKY'S MARKET [illegible]R, GC TO PROVID[illegible]G & INSTALLATION. PROVIDE SOLID PHENOLIC TOILET PARTITIONS
- G3 ALL SURFACE PENETRATIONS, CRACKS AND CREVICES ARE TO BE SEALED.
- G4 PERIMETER WALLS TO HAVE 5/8" MOISTURE MOLD TOUGH GWB UP TO 8'-0" AFF. WALL FINISH TO CONTINUE TO 12" BELOW T[illegible] OF CASE/FIXTURE [illegible]D THEN PRIME ONLY BELOW. [illegible] FINISH SCHDEULE FOR APPLICABLE FINISH(ES)
- G5 PROVIDE WALL BLOCKING FOR THE FOLLOWING BUT NOT LIMITED TO: SHELVING, PAPER DISPENSERS, SOAP DISPE[illegible]NOB DAMAGE, WA[illegible]ESK, WALL MOUNTED HAND-SINKS, OVER COMPARTMENT SINK SHELVING OR WHEREVER REQUIRED.
- G6 ALL COLUMNS ON SALES FLOOR TO RECEIVE STAINLESS STEEL WRAP TO 4'-0" (BY ALLOWANCE) AND CHO[illegible]ATE FROTH PAINT A[illegible]OTTOM OF B[illegible] JOIST.
- G7 GC SHALL USE NON-COMBUSTIBLE (FRT) PLYWOOD WHEN INSTALLED DIRECTLY TO WALL STUDS. [illegible]CTION WITH-IN THE [illegible]ORAGE [illegible]EA TO A 48" HT A.F.F. AND 2" X 8" PT WOOD BASE. GC SHALL CONTINUOUSLY CAULK/SEAL THE TOP EDGE OF PLYWOOD AND 2" X 8" [illegible]E. CUT ALL PANE[illegible] [illegible]NER[illegible]EAT AND TIGHT.
- G8 REFER TO RESPONSIBILITY SCHEDULE TO CONFIRM JOB SCOPE.
- G9 NOT USED
- G10 REFER TO INTERIOR ELEVATIONS AND FLOOR PLANS FOR VALANCE PAINT COLORS.

INTERIOR FINISH NOTES:

ALL INTERIOR WALL AND CEILI[illegible] FINISHES [illegible] SHALL BE NOT LESS THAN CLASS 'C' AS REQUIRED BY 5th ED. FBC TA[illegible]E 803.9, GR[illegible]UP M, S[illegible]NKLERED.

CLASS 'C'' = FLAME SPREAD I[illegible]DEX 76-200 [illegible]d SMOKE [illegible]VELOPE[illegible] INDE[illegible] 0-450.

ALL FLOOR FINISHES AND CO[illegible]ERINGS S[illegible]L BE CLA[illegible] or II MATERIA[illegible] IN ACCORDANCE WITH NFPA 253 AND SHALL COMPLY WITH THE REQU[illegible]MENTS OF [illegible]-1 "pill te[illegible]" (CPSF 16 CFR PART 1630) OR ASTM D2859.

ALL DECO[illegible]ATIVE MATERIALS SH[illegible]L MEET T[illegible]AME SPREAD CR[illegible]ERIA OF NFPA 701 PER 5th ED. FBC SECT[illegible] 2

P[illegible]-FABRICATED WALK-IN BOX PANELS [illegible]BE CONSTRU[illegible] OF FOAMED IN PLACE URETHANE IN[illegible]ATION CLASS I, UL TESTED AND CLASSI[illegible] BE IN ACCORDANCE WITH 5th ED. FBC SECTION 26[illegible]

RESTROOMS SHAL[illegible]AVE:
SMOOT[illegible] HARD NO[illegible]ABSORBANT FINISHES, INCLUDING MIN 4" HIGH VERTICAL BASE, INSTALLED OVER [illegible]OISTUR[illegible]ANT GYP BOARD OR CEMENTITIOUS BOARD. WALL FINISHES WITHIN TWO (2') FEET [illegible] SINKS, [illegible]RINALS, OR WATER CLOSETS SHALL BE NON-ABSORBANT (W-13 FRP) AND EXTEND A [illegible]MUM FOUR (4') FEET ABOVE FINISHED FLOOR.

ROOM FINISH SCHEDULE

NOTE: THE FINISHES THAT APPLY FOR THIS PROJECT ARE MARKED BELOW. THE MATERIAL FINISH SCHEDULE ON THIS SHEET CONTAINS MATERIAL FINISHES THAT MAY NOT BE INCLUDED ON THIS PROJECT.
• INDICATES THE FINISH THAT IS TO BE USED

Naples Fla 04/10/2018

- • SEE SHEET A1.5 FOR FLOORING TYPE (F-#), AND LOCATION ON FINISH FLOOR PLAN.
- • SEE SHEET A1.5.1 FOR WALL FINISH TYPE LOCATION ON FLOOR PLAN.
- • SEE SHEET A2.3 FOR WALL FINISH TYPE ON INTERIOR ELEVATIONS
- • SEE SHEET A1.3.1 FOR REFLECTED CEILING PLAN
- • SEE MATERIAL FINISH SCHEDULE AT LEFT

FLOOR / BASE

NO.	ROOM NAME	F-1 STAINED & POLISHED CONCRETE	F-2 SEALED CONCRETE	F-3 SEALED CONCRETE (FREEZER)	F-4 EPOXY (GRAY)	F-5 EPOXY (RED)	F-6 WALK-OFF MAT	F-7 QUARRY TILE - GRAY	F-8 QUARRY TILE - RED	F-9 CONCRETE	B-1 VINYL BASE	B-2 EPOXY - 1 GRAY	B-3 EPOXY -2 RED	B-4 QUARRY TILE BASE - GRAY	B-5 QUARRY TILE BASE - RED	B-6 2x4 WOOD	B-7 2x8 PT WOOD
100	VESTIBULE (EXITING)	●									●						
101	ENTRY CHECK-OUT	●									●					●	
102	SEATING AREA	●									●					●	
103	CAFÉ				●							●					
104	STORAGE (CAFÉ)		●								●						
105	CASH ROOM		●								●						
106	COMMUNITY ROOM	●									●						
107	GRAB-n-GO				●							●					
108	MEN TOILET	●									●						
109	WOMEN TOILET	●									●						
110	not used																
111	RESTROOM HALL	●									●					●	
112	MEAT PREP				●							●					
113	CUT ROOM COOLER					●							●				
114	MEAT COOLER		●								●						
115	DELI PREP				●							●					
116	DELI/BAKERY COOLER		●								●						
117	BAKERY PREP				●							●					
118	CULINARY FREEZER			●							●						
118A	CULINARY FREEZER			●							●						
119	DAIRY COOLER		●								●						
120	PRODUCE COOLER		●								●						
121	PRODUCE PREP.		●								●						
122	B.W. STORAGE									●							●
123	NATURAL LIVING STORAGE									●							●
124	not used																
125	SCAN ROOM		●								●						
126	TEAM MEMBER BREAKROOM		●								●						
127	DEPARTMENT MANAGER		●								●						
128	not used																
129	STORE DIRECTOR		●								●						
130	OFFICE MANAGER		●								●						
131	[illegible]				●							●					
132	RACK ROOM									●	●						
133	ELECTRICAL ROOM									●	●						
134	RECEIVING AREA									●							●
135	STOCKROOM									●							●
140	GENERAL SALES AREA	●									●					●	
	open																

WALLS

NO.	W-1 TAPED & PATCHED	W-2 PAINT: (WHITE ON WHITE)	W-3 PAINT: (CHOCOLATE FROTH)	W-4 PAINT (PACIFIC PINES)	W-5 PAINT (STOLEN KISSES)	W-6 Paint (Chalkboard)	W-7 PRIMER	W-8 CORRUGATED METAL	W-9 SYNTHETIC WOOD	W-10 1" x 4" CHAIR RAIL	W-11 FRP (White) SUBWAY TILE	W-12 FRP (WHITE) PEBBLED SURFACE	W-13 FRP TILE (SILVER)	W-14 FACTORY FINISH (GALVANIZED)	W-15 FACTORY FINISH (WHITE)	W-16 5/8" PLYWOOD	W-17 T&G BEETLE KILL/BLUE PINE	W-18 SHEET METAL WALL PROTECTION	W-19 CHICKEN WIRE	W-20 RECLAIMED OAK
100			●	●																
101		●		●				●												
102		●		●		●		●									●			
103									●		●	●								
104		●																		
105		●																		
106		●			●															
107											●									
108		●		●									●							
109		●		●									●							
110																				
111		●		●				●		●										
112											●									
113															●					
114														●						
115											●	●								
116														●						
117											●	●								
118														●						
118A														●						
119														●						
120														●						
121														●						
122	●																			
123	●																			
124																				
125		●																		
126		●		●																
127		●																		
128																				
129		●																		
130		●																		
131								●			●	●								
132	●																			
133	●																			
134	●															●				
135	●															●				
140	●	●	●	●	●	●		●		●							●			
0																				

CEILING / HEIGHT / REMARKS

NO.	C-1 "CHOICE" CREAM	C-2 2x4 CEILING TILE	C-3 2x4 CEILING TILE (VINYL)	C-4 PAINT: (WHITE ON WHITE)	C-5 FACTORY FINISH	C-6 EXPOSED (UN-PAINTED)	C-7 2x2 CEILING TILE (VINYL)	HEIGHT (A.F.F.)	REMARKS: SEE ROOM FINISH SPECIFICATIONS & MATERIAL FINISH SCHEDULE THIS SHEET
100	●							EXIST	GN-1, GN-10, P1 - P7, P9 -P12, P14 - P17, G8
101	●							EXP.	GN-1, GN-10, P1 - P7, P9 -P12, P14 - P17, G8
102	●							EXP.	GN-1, GN-4, GN-10, G4, GN-7, GN-8, GN-9, P1 - [illegible] G1, G3, G8, G9, G10
103							●	10'-2"	GN-1, GN-4, GN-7, [illegible] G6, G8, [illegible]
104						●		EXP.	GN-4, GN-8, P1 - [illegible] P9 - P17, G3, G8, G10
105				●				9'-0"	GN-1, GN-4, GN-[illegible]-8, GN-10, P1 - P5, P7 - P[illegible]7, G3, G8, G10
106		●						9'-0"	GN-1, GN-5, GN-7, [illegible] GN-9, P1-P5, P9, P-1[illegible] P16, F2, W5, W6, G5, G8
107				●				[illegible]'-0" 13'-	GN-1, GN-7, GN-8, GN[illegible] F7, G3, G5, G8, G10
108				●				[illegible]	GN-1, GN-7, GN-8, GN-9, P4, P6, P8, P9, P13 - 16, F2, F9, P13, P16, W1, C3, G3, G5, G8, G11
109				●				9'-0"	GN-1, GN-4, [illegible]N-10, P1 - P5, P9 - P14, P16, W1, W5, [illegible], G2, G3, G[illegible]10
110									
111							●	[illegible]	[illegible]N-1, GN-8, GN-9, GN-10, P1 - P5, P8 - P14, P16, G3, G8, G10
112							●	10'-2"	GN-1, GN-8, P1 - P5, P9, P11, P14 - P16, F-7, G3, G5, G8, G9, G10
113					●			9'-0"	GN-1, GN-6, GN-8, F-8, W3, G8, G9
114					●			9'-0"	GN-1, GN-6, F1, F4, F9, W3, G8, G9
115							●	10'-2"	GN-1, GN-8, P1 - P5, P9, P11, P14 - P16, F-1, F2, F-9, W1, C1, C3, G3, G5, G8, G9, G10
116					●			9'-0"	GN-1, GN-4, GN-6, GN-8, F4, F6, W3, W5, G3, G8
117							●	10'-2"	GN-1, GN-8, P1 - P5, P9, P11, P14- P16, F-1, F2, F-9, W1, W5, C1, C3, G3, G5, G8, G9, G10
118					●			9'-0"	GN-1, GN-4, GN-6, , GN-8, F4, F5, F6, W3, W5, G3, G8
118A					●			9'-0"	GN-1, GN-4, GN-6, , GN-8, F4, F5, F6, W3, W5, G3, G8
119					●			9'-0"	GN-1, GN-4, GN-6, GN-8. F4, F6, W3, W5, G3, G8
120					●			9'-0"	GN-1, GN-4, GN-6, GN-8, F4, F6, W3, W5, G3, G8
121					●			9'-0"	GN-1, GN-4, GN-6, GN-8, F4, F6, W3, W5, G3, G8
122						●		EXP.	GN-1, GN-4, GN-8, P1 - P5, P8, P9, P10, P12, P13, F7, W4, W5, G1, G3,
123						●		EXP.	GN-1, GN-4, GN-8, P1 - P5, P8, P9, P10, P12, P13, F7, W4, W5, G1, G3,
124									open
125		●						9'-0"	GN-1, GN-4, GN-8, P1 - P5, P8, P9, P10, P12, P13, F6, W5, G1, G3, G5, G8
126		●						9'-0"	GN-1, GN-4, GN-7, GN-8, P1 - P5, P8, P9, P11, P13, P16, P18, F6,
127		●						9'-0"	GN-1, GN-8, P1 - P5, P9, P-11 - P16, F6, W5, W6, G5G8, G10
128									open
129		●						9'-0"	GN-1, GN-4, GN-8, P1 - P5, P8, P9, P10, P12, P13, F6, W5, G1, G3, G5, G8
130		●						9'-0"	GN-1, GN-4, GN-8, P1 - P5, P8, P9, P10, P12, P13, F6, W5, G1, G3, G5, G8
131				●				10'-0"	GN-1, GN-8, G3, G8, G10
132						●		EXP.	GN-1, GN-4, GN-8, F7, W2, W5, G1, G3, G8
133						●		EXP.	GN-1, GN-4, GN-8, F7, W2, W5, G1, G3, G8
134						●		EXP.	GN-1, GN-8, GN-9, P1 - P5, P7 - P9, P12 - P17, F7, F8, W4, G1, G3, G5, G7, G8, G10
135						●		EXP.	GN-1, GN-8, GN-9, P1 - P5, P7 - P9, P12- P17, F7, F8, W4, G1, G3, G5, G7, G8, G10, G3, G5, G8, G10
140	●							EXP.	GN-1, GN-3, GN-4, GN-8, GN-9, GN-10, P1 - P9, P11 - P16, W5, G3, G6, G8, G10
0									open

wd
[illegible] DISCOVE[illegible]Y BLVD
[illegible]LIN, OH 43[illegible]
61[illegible]4.7000 T
WDPA[illegible]NERS.COM

LUCKY'S MARKET
PROMENADE at NAPLES
6424 NAPLES BLVD.
NAPLES, FL 34109

REVISIONS

PERMIT ISSUE
MAY 7, 2018
BID ISSUE 05/07/18
STORE NUMBER
57

WD PROJECT NUMBER
LKYUF0011

A6.1.2 GENERAL FINISH SCHEDULE

Order Plans @ www.LDIILine.com