ALL DESIGNS, DRAWINGS AND SPECIFICATIONS DEPICTED ON THIS SHEET ARE PROPERTY OF COAST ARCHITECTS, INC. COPYRIGHT © 5/31/2018 10:08:06 AM ANY UNAUTHORIZED USE OR REPRODUCTION IS SUBJECT TO LEGAL PROSECUTION. POSSESSION IN ANY FORM CONSTITUTES ACCEPTANCE OF THESE CONDITIONS.

PAVILION (BID ALT. NO. 2)

OSE CERTIFICATIONS

ZONING CERTIFICATION

"I hereby certify that, to the best of my knowledge, these plans comply with applicable zoning ordinances, and that plans have been submitted to appropriate authority for their review and/or approval."

Signed: SEE SHEET 0.G002 (Architect/Engineer) 06.01.2018 (Date)

EROSION AND SEDIMENT REDUCTION/STORMWATER MANAGEMENT

Designer's Certification:

"I hereby certify that the measures in this plan are designed to control erosion, retain sediment on the site, and manage stormwater in a manner that neither any on-site nor off-site damage or problem is caused or increased, that all structural measures are designed to the minimum standards for health and safety, and that all the provisions of the plan are in compliance with the Regulations contained in Chapter 72, Article 2, SC Code of Regulations (Erosion and Sediment Reduction and Stormwater Management Regulations)."

Signed: SEE SHEET 0.G002 (Engineer or Registered Landscape Architect (Circle one)) 06.01.2018 (Date)

TABLE 1 FLOOD HAZARD INFORMATION & FLOOD LOADS

FLOOD HAZARD AREA

Flood Map Information: Flood Zone: AE-14 *(A Floodplain Permit is required for A and V Zones)* — Community Number: 455412 — Panel Number: 45019C0512J

Is the Project Site in a 100-Year Flood Plain? Yes [X] No [ ] — NGVD or FIRM; IBC 1612.3 and ASCE 24

Base Flood Elevation 14.0 MSL

Design Flood Elevation 15.0 MSL

NON HIGH-VELOCITY WAVE ACTION

Elevation of Lowest Proposed Floor 9.0 MSL — Meet ASCE 24 Section 2.6.2.1/ 2.6.2.2

Dry floodproofing Yes [X] No [ ] per ASCE 24

HIGH-VELOCITY WAVE ACTION

Elevation of bottom of Lowest Horizontal Structural Member of lowest floor 18.0 MSL

Flotation resistant Yes [X] No [ ] per ASCE 24

Breakaway wall Yes [ ] No [X] per ASCE 24

TABLE 2 SOILS & SITE

SOILS INVESTIGATION (If required) Yes [X] No [ ] per IBC 1803.2

SOILS CLASSIFICATION

Site Class E per IBC 1613.3.2

Classes Soil of Materials (UCS System) SP, SM, SC per IBC 1803.5.1

Allowable Footing Bearing Pressure SEE GEOTECH REPORT psf

MINIMUM DESIGN SOIL BEARING LOAD SEE GEOTECH REPORT psf per IBC table 1806.2

COMPACTION

Subgrade: 95% Percent — [ ]ASTM D698 [ ]ASTM D1557 [ ]AASHTO (only for paving & roads)

Base: 95% Percent — [ ]ASTM D698 [ ]ASTM D1557 [ ]AASHTO (only for paving & roads)

Other: ____ Percent — [ ]ASTM D698 [ ]ASTM D1557 [ ]AASHTO (only for paving & roads)

MINIMUM DESIGN SOIL LATERAL LOAD ____ psf per IBC 1610.1

FOOTINGS

Undisturbed footings Yes [ ] No [X]

Compacted Fill Material Yes [X] No [ ] per IBC 1804.6

ELEVATIONS

Elevation of Water Table: APPROX. 2.0 MSL

Elevation of lowest footing 7.0 MSL

Elevation of lowest floor or basement: 9.0 MSL

TABLE 3 BASIC BUILDING CODE INFORMATION

CONSTRUCTION CLASSIFICATION	Type: VB (IBC 602)		
OCCUPANCY CLASSIFICATION (indicate all) (Note IBC 504.2)	A-2 (IBC 302)		
MOST RESTRICTIVE OCCUPANCY CLASSIFICATION	A-2 (IBC Tables 504.3, 504.4 & 506.2)		
Does building require Incidental Use Area Separation?	Yes [ ] No [X]	(IBC 509.1)	
Does building have Accessory Occupancy (ies)? If so, what percent of story is Accessory Occupancy?	Yes [ ] No [X]	(IBC 508.2)	____ SF ____ %
Mixed Occupancy	Yes [ ] No [X]	(IBC 508)	
Non separated	Yes [ ] No [ ]	(IBC 508.3)	
Separated	Yes [ ] No [ ]	(IBC 506.2.2) (IBC 506.2.4) (IBC 508.4)	
2-way Communication Required	Yes [ ] No [X]	(IBC 1009.8) (IBC 1009.6.5)	
Fire Apparatus Access and Water Line	Yes [ ] No [X]	(IFC 503 & 507)	

OTHER FIRE PROTECTION SYSTEMS, DEVICES or FEATURES

If the building has any special or notable fire protection or safety feature or hazard the designers should list them here, describe the performance characteristics and refer to locations in construction documents. (e.g. fire extinguishers, smoke-evacuation/control/compartments. Note IBC 414.1.3.)

TABLE 4 BUILDING AREA

AREA LIMIT BY TABLE 506.2 OF IBC 18,000 SF (area limitation per story)

AREA INCREASES BY SECTION 506.2 AND 506.3 OF IBC 4,500 SF (maximum modified area per story)

EXPLANATION OF INCREASES: FRONTAGE INCREASE 506.2.4 & 506.3.3

AREA AS ALLOWED IN IBC PER STORY

- Story/Level: GROUND — 22,500 SF (area per story)
- Story/Level: FIRST — 22,500 SF (area per story)
- Story/Level: ____ — ____ SF (area per story)
- Story/Level: ____ — ____ SF (area per story)

TOTAL ALLOWED AREA OF BUILDING (summary of all stories) 45,000 SF

AREA AS DESIGNED PER STORY

- Story/Level: GROUND — 1,200 SF (area per story)
- Story/Level: ____ — ____ SF (area per story)
- Story/Level: ____ — ____ SF (area per story)
- Story/Level: ____ — ____ SF (area per story)

TOTAL DESIGNED AREA OF BUILDING (summary of all stories) 1,200 SF

TABLE 5 BUILDING HEIGHT

	AS DESIGNED		AS ALLOWED BY IBC	
	In Feet	In Stories	In Feet	In Stories
PER TABLE 504.3	23'-0"	N/A	40'	N/A
PER TABLE 504.4	N/A	1	N/A	1
TOTAL HEIGHT (including any Allowable Increase)	23'-0"	1	40'	1

TABLE 6 BUILDING DESIGN OCCUPANT LOAD

STORY/ LEVEL	FUNCTION OF SPACE [1]	A: FLOOR AREA [2] (NSF or GSF)	B: MAX AREA ALLOWED PER OCCUPANT [3] (NSF or GSF)	C: OCCUPANTS ON FLOOR FOR THIS FUNCTION [4]	D: DESIGN OCCUPANT LOAD [5]
GROUND	ASSEMBLY (UNCONC.)	549 NSF	15 NSF	37	
	----	----	----	----	
	----	----	----	----	
	----	----	----	----	
	Subtotal Design Occupant Load for This Story				37
----	----	----	----	----	
	----	----	----	----	
	----	----	----	----	
	----	----	----	----	
	Subtotal Design Occupant Load for This Story				----
----	----	----	----	----	
	----	----	----	----	
	----	----	----	----	
	----	----	----	----	
	Subtotal Design Occupant Load for This Story				----
----	----	----	----	----	
	----	----	----	----	
	----	----	----	----	
	----	----	----	----	
	Subtotal Design Occupant Load for This Story				----
TOTAL BUILDING DESIGN OCCUPANT LOAD					37 [6]

FOOTNOTES:

1. Provide the complete name of the Function of Space using the left column of Table 1004.1.2 of the IBC [1]
2. Design Area per each occupant of this Function on this Story in either Gross (GSF) or Net (NSF) Square Footage [2]
3. Allowed Floor Areas in SF per Occupant per right column in Table 1004.1.2 of the IBC [3]
4. Divide Column A (2) by Column B (3) for each function and enter result, rounded up to the nearest whole person [4]
5. Subtotal all Column C values for this floor to yield the Design Occupant Load [5]
6. Total Building Design Occupant Load - sum of all Column D value [6]

TABLE 7 GENERAL FIRE PROTECTION REQUIREMENTS

SEPARATIONS			
Fireblocking Required	Yes [ ]	No [X]	per IBC Section 718
Draftstopping Required	Yes [ ]	No [X]	per IBC Section 718
Smoke Control System Required	Yes [ ]	No [X]	per IBC Section 909
Smoke Barriers Required	Yes [ ]	No [X]	per IBC Section 407 and 408
Smoke Partitions Required	Yes [ ]	No [X]	per IBC Section 407
Fire Partition Required	Yes [ ]	No [X]	per IBC Section 708
Fire Barrier Required	Yes [ ]	No [X]	per IBC Section 707
ALARM & DETECTION			
Fire Alarm System Required	Yes [ ]	No [X]	per IFC Section 907
Emergency/Voice Alarm Communications System Required	Yes [ ]	No [X]	per IFC Section 907.2.2
Emergency Alarm System Required	Yes [ ]	No [X]	per IFC Section 908
SUPPRESSION			
Standpipes Required	Yes [ ]	No [X]	per IFC Section 905
Sprinklers Required	Yes [ ]	No [X]	per IFC Section 903
Sprinklers Provided	Yes [X]	No [ ]	----
Portable extinguishers required	Yes [X]	No [ ]	per IFC 906
Other suppression systems required	Yes [ ]	No [X]	per IFC 904
Smoke & heat vents required	Yes [ ]	No [X]	per IFC 910

OTHER: *(Indicate other provided fire and life safety features not listed above, if any)*

TABLE 8 FIRE RESISTANCE RATING OF BUILDING ELEMENTS

BUILDING ELEMENT	RATING AS REQUIRED (in hours)	RATING AS DESIGNED (in hours)	TESTING AGENCY & DESIGN NO. (UL, FM, etc)	DESIGNERS WALL/PARTITION KEY CODE
Primary Structural Frame (per IBC Table 601)	0	0	----	
Bearing Walls Exterior Interior (per IBC Table 601)	 0 0	 0 0	----	----
Nonbearing Walls & Partitions Exterior Interior (per IBC Table 601 & 602) Note footnote "d" from Table 601	 0 0	 0 0	----	----
Floor Construction including supporting beams & joists (per IBC Table 601)	0	0	----	
Roof Construction including supporting beams & joists (per IBC Table 601)	0	0	----	
Fire Walls (per IBC Section 706)	0	0	----	----
Fire Barriers (per IBC Section 707)	0	0	----	----
Shaft Enclosures (per IBC Section 713)	1	NA	----	----
Fire Partitions (per IBC Section 708)	0	0	----	----
Opening & Protective Listing by Category (fire shutters, doors, etc. per IBC Section 716)	0	0	----	----
Others (as required by Designer)	1	NA	----	----

TABLE 9 STRUCTURAL DESIGN INFORMATION

RISK CATEGORY: II — IBC Table 1604.5

LIVE LOADS

Floor Live Load(s) - List the F_{ll} for each occupancy/use:

- Occupancy/Use: ASSEMBLY — F_{ll} = 100 PSF
- Occupancy/Use: ____ — F_{ll} = ____ PSF
- Occupancy/Use: ____ — F_{ll} = ____ PSF
- Occupancy/Use: ____ — F_{ll} = ____ PSF

Roof Live Load R_{ll} = 20 PSF

Ground Snow Load p_g = 5 PSF — IBC Figure 1608.2 (or ASCE 7)

WIND LOADS

Analysis Procedure: DIRECTIONAL	ASCE 7 or IBC 1609
Ultimate Design Wind Speed: V_{ULT} = 146 MPH	IBC Fig's. 1609.3(1)-(3)
Exposure Category: D	IBC 1609.4.3
Internal Pressure Coefficient: GC_{pi} = +/-0.18	ASCE 7
External Pressure Coefficient: GC_p = VARIES	ASCE 7
Protection of Openings Required Yes [X] No [ ]	IBC 1609.1.2
If "Yes", check one: Impact Resistant Glazing [X]; Impact Resistant Covering [ ]	

SEISMIC LOADS

Seismic Importance Factor: I_e = 1.0	ASCE 7 Table 1.5-2
Site Class: E	IBC 1613.3.2
Mapped Spectral Response Accelerations:	S_s = 1.165 S_1 = 0.371
Design Spectral Response Acceleration Parameters:	S_{DS} = 0.699 S_{D1} = 0.622
Seismic Design Category: D	IBC Tables 1613.3.5(1) & 1613.3.5(2)
Basic Seismic Force Resisting System: SPEC. REINF. MASONRY SHEARWALLS	ASCE 7 Chapter 12
Design Base Shear: 190 KIPS	
Seismic Response Coefficient(s): C_s = 0.14	ASCE 7
Response Modification Factor(s): R = 5	ASCE 7
Analysis Procedure: ELF	

ARCHITECTURAL-MECHANICAL-ETC. LOADS

Provide as applicable: architectural items, mechanical, plumbing, etc. per ASCE 7

SPECIAL LOADS

Provide as applicable: abnormal items, moving loads, impact, hoisting, etc. per ASCE 7

TABLE 10 PLUMBING INFORMATION

WATER SYSTEM: Service Line Size: 2 Inches; Peak Flow: 41 GPM; Total Demand: 94 DFU No. Fixture Units

SANITARY SEWER SYSTEM: Loading: 65 DFU GPD; Service Line Size: 4 Inches; Slope: 1/8 min inches/ft

MINIMUM PLUMBING FIXTURES REQUIRED/PROVIDED (Per IPC Section 403 & Table 403.1)

Occupancy Classification(s) (as shown in Table 5-3): A-2

Total Building Design Occupant Load (as shown in Table 5-6): 37

1. Occupancy: ASSEMBLY (A-2) Total Load for this Occupancy: 37 Male: 19 Female: 19

	Male REQUIRED	Female REQUIRED
Water Closets/ Urinals*	(19/75) = 0.25 (# Urinals allowed 0.12)	(19/75) = 0.25
Lavatories	(19/200) = 0.01	(19/200) = 0.01
OTHER FIXTURES (Per IPC Section 403 & Table 403.1)		**REQUIRED**
Drinking Fountains		(37/500) = 0.07
Unisex Toilet		
Service Sink		1
Other (list) ____		____

2. Occupancy: ____ Total Load for this Occupancy: ____ Male: ____ Female: ____

	Male REQUIRED	Female REQUIRED
Water Closets/ Urinals*	(# Urinals allowed ____)	____
Lavatories	____	____
OTHER FIXTURES (Per IPC Section 403 & Table 403.1)		**REQUIRED**
Drinking Fountains		____
Unisex Toilet		____
Service Sink		____
Other (list) ____		____

3. Occupancy: ____ Total Load for this Occupancy: ____ Male: ____ Female: ____

	Male REQUIRED	Female REQUIRED
Water Closets/ Urinals*	(# Urinals allowed ____)	____
Lavatories	____	____
OTHER FIXTURES (Per IPC Section 403 & Table 403.1)		**REQUIRED**
Drinking Fountains		____
Unisex Toilet		____
Service Sink		____
Other (list) ____		____

TOTAL BUILDING COUNT (add all occupancies)

	Male REQUIRED	Male PROVIDED (round up ≥ Required)	Female REQUIRED	Female PROVIDED (round up ≥ Required)
Total Water Closets/ Urinals*	0.25 (# Urinals allowed 0.12)	1# (# Urinals provided 0)	0.25	1#
Total Lavatories	0.01	1#	0.01	1#
OTHER FIXTURES (Per IPC Section 403 & Table 403.1)			**REQUIRED**	**PROVIDED** (round up)
Total Drinking Fountains			0.07	1^
Total Unisex Toilets			____	____
Total Service Sinks			1	1^
Total Other (list)				

* Urinals - See IPC 419.2 #PROVIDED IN DOCK HOUSE ^PROVIDED IN BOAT HOUSE

TABLE 11 MECHANICAL INFORMATION

AIR COMFORT SYSTEMS

Overall Thermal Transfer Value (OTTV): NA BTU/(HR x °F x SF)

Building Cooling Load: NA SF / Ton

Building Heating Load: NA BTU/(HR x SF)

OTHER LOADING FEATURES

Glass: U Factor: NA — Window to wall ratio: NA

Insulation Values: Roof: NA — Exterior Walls: NA

Outside Air minimum while occupied: NA CFM 37 Occupants

MECHANCIAL SYSTEMS, SERVICE SYSTEMS & EQUIPMENT

Briefly describe mechanical system: NO MECHANICAL SYSTEMS IN PAVILION

TABLE 12 ELECTRICAL INFORMATION

SERVICE TRANSFORMER: [ ] By Utility Company [X] By Agency (if by Agency) TBD KVA Primary; 208V/3 Voltage/Phase

ELECTRICAL SERVICE INFORMATION

Service Voltage/Phase:	SEE SHEET 0.G002	Amperes
Service Entrance Conductors Size:	SEE SHEET 0.G002	Quantity per Phase
Total Connected Load:	SEE SHEET 0.G002	KVA
Estimated Maximum Demand:	SEE SHEET 0.G002	KVA
Available Fault Current in Symmetrical Amperes:	SEE SHEET 0.G002	
Interrupting Capacity of Service Overcurrent Device:	SEE SHEET 0.G002	
Grounding Electrode System Components:	SEE SHEET 0.G002	(NEC 250)

EMERGENCY SERVICE INFORMATION

Emergency Generator: Yes [ ] No [X] ____ KVA ____ Voltage/Phase ____ Fuel

Exit/Emergency Lights Backup Power [X] Integral Battery [ ] Generator

Fire Alarm System: [ ] Manual [ ] Automatic [ ] Addressable [ ] Class A [ ] Class B

LIGHTNING PROTECTION PROVIDED [ ] Yes [X] No

COMMUNICATIONS COORDINATED [ ] Yes [X] Not Required

Contact DSIT Network/Infrastructure Planning for applicability at (803) 896-0001

NOTES

SEE LIFE SAFETY LEGEND ON SHEET 0.G003



A8 / 0.G004 **PAVILION GROUND FLOOR PLAN**

SCALE: 1/8" = 1'-0"

BID DOCUMENTS

coast architects

671 St. Andrews Blvd. Charleston, SC 29407
Phone: 843.763.7064 Fax: 843.763.7061
www.coastarchitects.net

STATE OF SOUTH CAROLINA — COAST ARCHITECTS INC. Charleston, SC No. 03038 — REGISTERED ARCHITECT

STATE OF SOUTH CAROLINA — FRANK A. McCLURE, III CHARLESTON, SC NO. 4804 — 06.01.2018 — REGISTERED ARCHITECT

BOATING CENTER REDEVELOPMENT - SWAIN BOATING CENTER

H09-9617-PG-C

THE CITADEL — THE MILITARY COLLEGE OF SOUTH CAROLINA

11 HAMMOND AVENUE
CHARLESTON, SC

Revisions	
Rev. No.	Rev. Date

DRAWN BY: FAM

CHECKED BY: FAM

DATE: 06.01.2018

COAST PROJECT NO.: 1722.00

PAVILION CODE TABLES AND LIFE SAFETY PLAN

0.G004

Order Plans @ WWW.LDILine.com