


ALL DESIGNS, DRAWINGS AND SPECIFICATIONS DEPICTED ON THIS SHEET ARE PROPERTY OF COAST ARCHITECTS, INC. COPYRIGHT © 2010. ANY UNAUTHORIZED USE OR REPRODUCTION IS SUBJECT TO LEGAL PROSECUTION. POSSESSION IN ANY FORM CONSTITUTES ACCEPTANCE OF THESE CONDITIONS.

BID ALTERNATE NO. 2
 1. THIS WORK IS PART OF BID ALTERNATE NO.2. ALL GENERAL REQUIREMENTS AND SPECIFICATIONS APPLY TO THIS WORK. SEE SHEET 0.E001 FOR GENERAL REQUIREMENTS, SCHEDULES, AND LEGEND.


PANEL P		60 AMP MAINS		SURFACE <input checked="" type="checkbox"/>					
208/120 V, 1 PH, 3 W, 60 HZ		60 AMP MAIN SHUNT TRIP TYPE BKR							
ALL BREAKERS SHALL HAVE A MINIMUM INTERRUPTING RATING OF 22,000 AMPS. PANEL SHALL BE PROVIDED WITH SEPARATE GROUND BUS.									
CKT No.	LOAD DESCRIPTION	BREAKERS POLE	AMP	KVA	BREAKERS AMP POLE	LOAD DESCRIPTION	CKT No.		
1	LIGHTING	1	20	1.0	0.4	20	1	RECEPTACLES	2
3	FANS	1	20	0.8		20	1	SHUNT TRIP	4
5									6
7									8
9									10
11									11
				TOTAL CONNECTED LOAD		2.2 KVA			



PAVILION ELECTRICAL PLAN
 SCALE: 1/4" = 1'-0"

TO PANEL IN BOATHOUSE. SEE SITE PLAN AND BOATHOUSE PLANS FOR DISTANCE.
 #8G, 1 1/2" C

FLOAT SWITCH FOR SHUNT-TRIP CONTROL OF MAIN CIRCUIT BREAKER MAGNETROL MODEL FLS 120VAC OR APPROVED EQUAL. MOUNT ON WALL AT MAXIMUM FLOOD ELEVATION HEIGHT.



PAVILION SINGLE LINE DIAGRAM
 SCALE: NTS

Order Plans @

WWW.LDLINE.COM

coast architects
 671 St. Andrews Blvd., Charleston, SC 29407
 Phone: 843.763.7064 Fax: 843.763.7061
 www.coastarchitects.net



DAVID F. WILSON, P.E.
 1421 BRIAN ROAD
 CHARLESTON, SC 29407
 TEL: (843) 225-7191

BOATING CENTER REDEVELOPMENT- SWAIN BOATING CENTER
 H09-9617-PG-C
THE CITADEL
 11 HAMMOND AVENUE
 CHARLESTON, SC
THE MILITARY COLLEGE OF SOUTH CAROLINA

Revisions	
Rev. No.	Rev. Date

DRAWN BY: DFW
 CHECKED BY: DFW
 DATE: 06.01.2018

COAST PROJECT NO.: 1722.00

PAVILION LIGHTING AND POWER PLANS

2.E101

BID DOCUMENTS