



2701 1st Avenue S  
 Birmingham, AL 35233  
 T 205.879.4462  
 GMCNETWORK.COM



ISSUE	DATE
100%	2018.04.18
Issue for Bid	2018.05.25

USA SIMULATION LAB  
 MOBILE, ALABAMA  
 ABC # 2017372  
 GMC # AMOB160019

3RD FLOOR FRAMING  
 PLAN  
**S1.3**  
 Sheet of



**TYPICAL ELEVATED FLOOR SLAB CONSTRUCTION**  
 3" CLEAR CONCRETE OVER 2" - 20 GAGE GALV. COMPOSITE METAL DECK (5" TOTAL). REINFORCE SLAB WITH 4x4 - W4.0xW4.0 FLAT SHEETS SUPPORTED ON BOLSTER CHAIRS. SET FLAT SHEETS 1" CLEAR FROM TOP OF SLAB.

**3RD FLOOR FRAMING PLAN**  
 SCALE: 1/8"=1'-0"  
 TOP OF SLAB ELEVATION= +30'-8"  
 TOP OF STEEL ELEVATION = +30'-3" U.N.O.

- LEGEND**
- (+ 2 1/2") RELATIVE TOP OF STEEL ELEVATION
  - ▶ DENOTES MOMENT END CONNECTION
  - ◀ DENOTES AXIAL TIE CONNECTION TO WALL
  - INDICATES DECK ORIENTATION
  - c=1" DENOTES CAMBER AT MID SPAN
  - (24) INDICATES NUMBER OF 3/4" x 4" LG. HEADED STUDS (SLAB TYPE "A")
  - BOTTOM FLANGE BRIDGING FOR TORNADO UPLIFT, SEE DETAIL 4/S4.2
  - ← DENOTES BOTTOM FLANGE BRACE

- NOTES:**
1. REFERENCE SHEET S4.2 FOR TYPICAL BEAM CONNECTION SCHEDULE.
  2. REFER TO ARCHITECTURAL LIFE SAFETY PLANS FOR FIRE PROTECTION REQUIREMENTS.
  3. SEE TYPICAL DETAIL ON SHEET S4.1 FOR SLEEVE OPENINGS IN ELEVATED SLABS.
  4. PROVIDE 2-#4x5'-0" LONG BARS SET IN TOP OF SLAB AT REENTRANT SLAB CORNERS, TYPICAL AS INDICATED.
  5. INTERMEDIATE LANDINGS FOR STAIR ST-1 SHALL BE SUSPENDED FROM THE STRUCTURE ABOVE AT LOCATIONS INDICATED. STAIR DESIGNER TO PROVIDE DESIGN FOR HANGER AND CONNECTION TO THE SUPPORTING STRUCTURE.

Order Plans @ www.OnLine.com