SHEET NOTES

1. NEMA L5-30R RECEPTACLE. HOMERUN SHALL BE 2#10, #10G, 3/4"C.
2. NEMA 14-30R DRYER RECEPTACLE. HOMERUN SHALL BE 3#10, #10G, 3/4"C.
3. COORDINATE RECEPTACLE REQUIREMENTS WITH ICE MACHINE MANUFACTURER.
4. PROVIDE JUNCTION BOX ABOVE CEILING FOR CONNECTION TO AUTOMATIC DOOR OPENER. PROVIDE RELAY AS REQUIRED TO INTERFACE TO ACCESS CONTROL SYSTEM.
5. PROVIDE JUNCTION BOX AT 48"AFF FOR CONNECTION TO FIRE ALARM CONTROL PANEL.
6. COORDINATE EXACT HEAD WALL REQUIREMENTS WITH EQUIPMENT BEING PROVIDED. ONE CIRCUIT SHALL POWER RED ONE (1) "EMERGENCY" RECEPTACLES, OTHER CIRCUIT SHALL POWER ONE (1) "NORMAL" POWER RECEPTACLES.
7. 30A/3 POLE NEMA 1 SAFETY SWITCH FOR CONNECTION TO SKYFOLD PARTITION WALL SYSTEM. COORDINATE EXACT LOCATION AND REQUIREMENTS WITH EQUIPMENT PROVIDED. HOMERUN SHALL BE 3#10, #10G, 3/4"C.
8. SKYFOLD PARTITION WALL SYSTEM FACTORY PROVIDED CONTROL SWITCH. COORDINATE EXACT LOCATION OF SWITCH WITH MANUFACTURER REQUIREMENTS AND ARCHITECT. PROVIDE 3/4" CONDUIT FROM PARTITION ELECTRICAL BOX TO SWITCH LOCATIONS. REFER TO MANUFACTURER INSTALLATION REQUIREMENTS FOR CABLE REQUIREMENTS.
9. COORDINATE EXACT LOCATION AND REQUIREMENTS OF CONNECTION TO MOTORIZED ROLL UP DOOR WITH EQUIPMENT INSTALLATION INSTRUCTIONS.
10. PROVIDE JUNCTION BOX AT 48"AFF FOR CONNECTION TO ACCESS CONTROL SYSTEM.
11. REFER TO SINGLE LINE DIAGRAM FOR MINI POWER ZONE REQUIREMENTS. PROVIDE ADDITIONAL BLOCKING AS REQUIRED TO SUPPORT WALL MOUNTED EQUIPMENT WITH APPROX. WEIGHT OF 850LBS. CONTRACTOR TO VERIFY EXACT WEIGHT PRIOR TO ROUGH-IN.

STORM SHELTER EXTENTS

PLAN NORTH

1 1ST FLOOR POWER PLAN

SCALE: 3/16"=1'-0"

SCHMIDT CONSULTING GROUP, INC.
MECHANICAL ELECTRICAL STRUCTURAL COMMUNICATIONS INDUSTRIAL
ALABAMA LICENSE NUMBER 3542
601 W. Garden St. Pensacola FL 32502
P: 850.438.0000 F: 850.432.6631
TODD NICHOLSON P.E.
ALABAMA LICENSE NUMBER 29943-E
SCG PROJECT: 2016-151

2701 1st Avenue S
Birmingham, AL 35233
T 205.879.4462
@MCNETWORK.COM

ISSUE	DATE
ISSUE FOR BID	2018.05.25

DRAWN BY: JTH
CHECKED BY: TAN

SIMULATION LABORATORY
BUILDING - USA JOB #16-07
MOBILE, ALABAMA
ABC #2017372
GMC # AMOB160019

ALABAMA 29943-E PROFESSIONAL 5/14/18 ENGINEER TODD ALAN NICHOLSON

1ST FLOOR POWER PLAN

E301

sheet of

5/23/2018 8:01:21 AM

Order Plans @ WWW.LDLine.com GMC