

GENERAL NOTES

1. VERIFY ALL DEVICE LOCATIONS AND MOUNTING HEIGHTS.
2. VERIFY LOCATIONS OF ALL MECHANICAL EQUIPMENT.
3. ALL EQUIPMENT USED SHALL BEAR THE LABEL OF A RECOGNIZED STANDARD SETTING LABOR (i.e. UL, ETC.)
4. ALL SWITCHES AND RECEPTACLES TO BE IVORY.
5. ALL EQUIPMENT AND ACCESSORIES SHALL BE NEW AND UNUSED, UNLESS OTHERWISE NOTED.
6. ALL EXTERIOR OUTLETS SHALL BE WP, GFCI.
7. NOT USED.
8. SEAL ALL PENETRATIONS OF FIRE RATED SURFACES TO MAINTAIN THE FIRE RATED INTEGRITY.
9. PROVIDE ALL LABOR AND MATERIAL NECESSARY FOR A COMPLETE AND FUNCTIONING ELECTRICAL SYSTEM.
10. MATERIALS AND INSTALLATIONS SHALL COMPLY WITH CODES, LAWS AND ORDINANCES OF FEDERAL, STATE AND LOCAL GOVERNING BODIES HAVING JURISDICTION.
11. PROVIDE LOCAL DISCONNECT SWITCHES FOR ALL MOTORS.
12. SECURE AND PAY FOR ALL PERMITS, GOVERNMENTAL FEES, TAXES AND LICENSES NECESSARY FOR THE PROPER EXECUTION AND COMPLETION OF THE ELECTRICAL WORK.
13. NOTIFY THE ARCHITECT/ENGINEER/OWNER OF ANY MATERIALS OR APPARATUS BELIEVED TO BE INADEQUATE, UNSUITABLE, OR IN VIOLATION OF LAWS, ORDINANCES, RULES OR REGULATIONS OF AUTHORITIES HAVING JURISDICTION.
14. PROVIDE TEMPORARY POWER AND WIRING FOR THE PERFORMANCE OF ALL TRADES, FOR THE ENTIRE PERIOD OF CONSTRUCTION. REMOVE ALL TEMPORARY WIRING AT THE COMPLETION OF CONSTRUCTION.
15. ALL MATERIALS AND EQUIPMENT SHALL BE ERRECTED, INSTALLED, CONNECTED, CLEANED, ADJUSTED, TESTED, CONDITIONED AND PLACED IN SERVICE IN ACCORDANCE WITH THE MANUFACTURER'S DIRECTIONS AND RECOMMENDATIONS.
16. ALL CUTTING, DRILLING AND PATCHING OF MASONRY, STEEL OR IRON WORK BELONGING TO THE BUILDING MUST BE DONE BY THIS CONTRACTOR IN ORDER THAT THIS WORK MAY BE PROPERLY INSTALLED, BUT UNDER NO CONDITIONS, MAY STRUCTURAL WORK BE CUT, EXCEPT AT THE DIRECTION OF THE ARCHITECT, DESIGNER OR THEIR REPRESENTATIVE.
17. PROVIDE "AS-BUILT" DRAWINGS AND SUBMIT TO THE OWNER.
18. IN SUSPENDED CEILINGS, SUPPORT JUNCTION AND CONDUIT BOXES DIRECTLY FROM THE STRUCTURAL SLAB, DECK OR FRAMING PROVIDED FOR THAT PURPOSE.
19. COORDINATE WITH MECHANICAL AND PLUMBING DRAWINGS AND INFORM ARCHITECT/ENGINEER OF ANY CONFLICTS/DISCREPANCIES.
20. WHERE FLOOR FITTINGS REQUIRE PENETRATION OF THE FLOOR SLAB, THEY SHALL BE STANDARD DEVICE LISTED BY UL FOR THAT PURPOSE AND HAVE A UL FIRE RATING EQUAL TO THE FLOOR RATING.
21. NUMBERED CIRCUITS AND RACEWAY ROUTINGS ARE FOR CONVENIENCE OF DESIGN ONLY. ACTUAL FIELD CONDITIONS WILL VARY. INDICATE THE CIRCUIT NUMBER USED ON THE "AS-BUILT" DRAWINGS.
22. ELECTRICAL EQUIPMENT INSTALLED IN PLENUMS SHALL BE APPROVED FOR USE AS SUCH.
23. E.C. TO COORDINATE WITH LOCAL UTILITY COMPANY, TRANSFORMER, C.T. AND METER LOCATIONS AND CONNECTION REQUIREMENTS.

LIGHTING FIXTURE SCHEDULE (SIMILAR MANUFACTURERS ACCEPTABLE)

(VERIFY ALL FINISHES WITH OWNER)

- SINGLE NUMERAL PREFIX IN LAMP COLUMN INDICATES NUMBER OF LAMPS IN FIXTURE (3-F-40WW). NO PREFIX INDICATES SINGLE LAMP (150A-A19).
- MOUNTING HEIGHTS AND DETAILED INFORMATION ARE INDICATED IN REMARKS COLUMN.
- USE THE FOLLOWING MOUNTING ABBREVIATIONS: C=CEILING R=RECESSED S=SURFACE W=WALL T=TRACK

SYMBOL	TYPE	MANUFACTURER	CATALOG NUMBER	VOLTS	LAMP	MTG	REMARKS
○	D	LITHONIA		120	4100 K (LED)	R	DOWNLIGHT FIXTURE - INTERIOR
●	D1	LITHONIA		120	4100 K (LED)	R	WALL WASH FIXTURE ON DIMMER
○	H	LITHONIA	NARROW BAND VANITY - 24" HIGH	120		W	MOUNT ONE EACH SIDE OF MIRROR
⎓	UC	LITHONIA	UCEL (12IN TO 36IN) 40K 90CRI WH	120	4000 K (LED)	S	UNDERCABINET LED (2' LONG) (3' LONG) VERIFY W/ CABINETS, HARD WIRED TO WALL SWITCH
□	WS	LITHONIA - GATEWAY	VGR5C 40LED 120 DDBT PE LFI	120	LED	S	WALL SCONCE
⊙	CF	CASA VIEJA	STYLE 7D657	120	N/A	S	44" INNOVATOR BRUSHED NICKEL LED HUGGER CEILING FAN
⎓	X2	LITHONIA OR DUAL LITE	EXIT SIGN AND EMERGENCY LIGHT COMBO	120	FURNISHED	W/C	LED EXIT SIGN AND EMERGENCY LIGHT
	SL	SHOP LITE	4'-0" WITH REFLECTOR		2-BULB	S	
⎓	X1	LITHONIA	QUANTUM ELM SERIES	120/ 277	FURNISHED		SELF-CONTAINED NON-ADJUSTABLE TWIN HEAD EMERGENCY LIGHTING UNIT COMPLETE WITH AUTOMATIC CHARGER, 90 MINUTE LEAD CALCIUM BATTERY & HALOGEN LAMPS. MOUNT HIGH ON WALL FOR WIDE COVERAGE.
○	L	LITHONIA	4" RECESSED LED CAN LIGHT	120	4000K LED	R	ON DIMMER SWITCH (TYPICAL)
⊙	GN	BARNLIGHT.COM	BLE-G-Y/K-SP	120	4000 K LED	S	GOOSENECK - VERIFY FINISH WITH OWNER
⎓	EE	LITHONIA	AFN-B-EXT	120		S	WET LOCATION - EMERGENCY EGRESS LIGHT
⎓	T1	JUNO	4" SURFACE TRACK UNIT (4 LIGHTS) 252L-4000-N-BL	120		P	TRACK ON 24" HIGH PENDANT SUPPORTS
FLAG	WSP	SPAULDING	FLAG & POLE FLOOD LT., LED, WET LOCATION LABELED, TEMPERED GLASS LENS, DARK BRONZE FINISH, GLARE SHIELD. YOK / KNUCKLE MOUNT, BEAM-SPREAK NEMA 3X3	UNV 120	LED, 4,692 LUMEN OUTPUT, 30k 80 CRI	CONCRETE BASE AIM	LED DRIVER AND POWER SUPPLY PER MANUFACTURER SPAULDING: ARF2-Y/K-42L-30L-070-N-Unv-DB
SIGN	WSS	SPAULDING	SIGNAGE FLOOD LT., LED, WET LOCATION LABELED, TEMPERED GLASS LENS, DARK BRONZE FINISH, GLARE SHIELD. YOK / KNUCKLE MOUNT, BEAM-SPREAK NEMA 6X6	UNV 120	LED, 4,692 LUMEN OUTPUT, 30k 80 CRI	CONCRETE BASE AIM	LED DRIVER AND POWER SUPPLY PER MANUFACTURER SPAULDING: ARF2-Y/K-42L-30L-070-W-Unv-DB
WALL	WSW	SPAULDING	BUILDING FLOOD LT., LED, WET LOCATION LABELED, TEMPERED GLASS LENS, DARK BRONZE FINISH, GLARE SHIELD. YOK / KNUCKLE MOUNT, BEAM-SPREAK NEMA 6X6	UNV 120	LED, 9,535 LUMEN OUTPUT, 30k 80 CRI	CONCRETE BASE AIM	LED DRIVER AND POWER SUPPLY PER MANUFACTURER SPAULDING: ARF3-Y/K-42L-30L-070-W-Unv-DB
□	G	LITHONIA	DESIGN BASED ON LITHONIA LIGHTING EPAN 24, 40L, 40K, 4000 K				
□	G2		SAME AS TYPE 'G' EXCEPT 2'X2'				
○ ^E	E		WET LOCATION EXTERIOR LED RECESSED CAN FIXTURE (TO BE DETERMINED) 200 CASH ALLOWANCE				
⊙ ^{SP}	SP		EXTERIOR SPOT LIGHT ON SWITCH. ECO-STAR 13" WIDE LED SECURITY FLOOD LIGHT - STYLE IG655				
○ ^P	P		SEAGULL LIGHTING - PAINTED SHADE PENDANT LED-6519 WITH METAL ROD SUPPORT				
□	W	LITHONIA	4'-0", 41-WATT WHITE INTEGRATED LED LOW PROFILE WRAPAROUND SURFACE MOUNT 4000K				
○	I		RECESSED WET LOCATION - SHOWER LIGHT - LED				



SIGNATURE REQUIRED

SMITH DESIGN GROUP, INC.
200 WEST HUNTERSON STREET
LAGRANGE, GEORGIA 30240
706-882-5511 www.SDGarch.net

REVISIONS

DATE	DESCRIPTION

PROJECT:
VERNON ROAD FIRE STATION

VERNON ROAD
LAGRANGE GEORGIA

TITLE:

LIGHTING FIXTURE SCHEDULE

MODIFIED DATE:	JOB NO: 1731
ISSUED DATE: FOR BID AND PERMIT 07 MAY 2018	SHEET: E-3

Order Plans