ROOFTOP UNIT SCHEDULE

MARK	MANUFACTURER	MODEL	AIRFLOW SUPPLY (CFM)	AIRFLOW O.A. (CFM)	AIRFLOW E.S.P. (IN.W.C.)	DX COOLING COIL AMB. O.A.T. (°F)	DX COOLING COIL ENTERING AIR D.B. (°F)	DX COOLING COIL ENTERING AIR W.B. (°F)	DX COOLING COIL NOM. TONS	DX COOLING COIL TOTAL (MBH)	DX COOLING COIL SENSIBLE (MBH)	GAS HEAT FUEL	GAS HEAT INPUT (MBH)	GAS HEAT OUTPUT (MBH)	ELECTRICAL VOLTS	ELECTRICAL Ø	ELECTRICAL HZ	ELECTRICAL FAN HP SUP.	ELECTRICAL MCA (A)	ELECTRICAL MOP (A)	WEIGHT (LBS)	REMARKS
RTU - 1	TRANE	YHD120	3300	1000	0.75	10	105	80	67	167.6	84.3	NG	200.0	160.0	480	3	60	3	25.3	30	1560	NOTE 1,2,3,4,5,6,7,8,9,10,11,12
RTU - 1A	TRANE	YHD072	1650	600	0.75	6	105	80	67	88.9	49.7	NG	120.0	97.2	480	3	60	1	17.5	25	1400	NOTE 1,2,3,4,5,6,7,8,9,10,11,12
RTU - 2	TRANE	YHD120	3233	1100	0.75	10	105	80	67	167.6	84.3	NG	200.0	160.0	480	3	60	3	25.3	30	1560	NOTE 1,2,3,4,5,6,7,8,9,10,11,12
RTU - 3	TRANE	YHD120	3310	1000	0.75	10	105	80	67	167.8	84.3	NG	200.0	160.0	480	3	60	3	25.3	30	1560	NOTE 1,2,3,4,5,6,7,8,9,10,11,12
RTU - 4	TRANE	YHD130	3215	1100	0.75	10	105	80	67	167.8	84.3	NG	200.0	160.0	480	3	60	3	25.3	30	1560	NOTE 1,2,3,4,5,6,7,8,9,10,11,12
RTU - 5	TRANE	YHD130	2799	900	0.75	10	105	80	67	167.8	84.3	NG	200.0	160.0	480	3	60	3	25.3	30	1600	NOTE 1,2,3,4,5,6,7,8,9,10,11,12
RTU - 6	TRANE	YHD072	1440	450	0.75	6	105	80	67	66.8	49.7	NG	120.0	97.2	460	3	60	1	17.5	25	1400	NOTE 1,2,3,4,5,6,7,8,9,10,11,12
RTU - 7	TRANE	YHD072	1440	450	0.75	6	105	80	67	66.8	49.7	NG	120.0	97.2	460	3	60	1	17.5	25	1400	NOTE 1,2,3,4,5,6,7,8,9,10,11,12
RTU - 8	TRANE	YHD120	5210	1550	0.75	10	105	80	67	129	96	NG	200.0	160.0	480	3	60	3	25.3	30	1560	NOTE 1,2,3,4,5,6,7,8,9,10,11,12
RTU - 9	TRANE	YSD210	5600	1070	0.80	17.5	105	80	67	210	153	NG	350.0	284.9	480	3	60	3	44	60	2700	NOTE 1,2,3,4,5,6,7,8,9,10,11,12
RTU - 10	TRANE	YSD120	3360	720	0.80	10	105	80	67	120	96	NG	200.0	202.0	480	3	60	3	26.9	35	1500	NOTE 1,2,3,4,5,6,7,8,9,10,11,12
RTU - 11	TRANE	YSD120	5250	230	0.80	10	105	80	67	120	96	NG	150.0	122.0	480	3	60	3	26.9	35	1500	NOTE 1,2,3,4,5,6,7,8,9,10,11,12
RTU - 12	TRANE	YSD210	5895	560	1.00	17.5	105	80	67	210	153	NG	250.0	203.0	480	3	60	5	44	60	2700	NOTE 1,2,3,4,5,6,7,8,9,10,11,12
RTU - 13	TRANE	YSD060	1860	160	0.75	5	105	80	67	63.1	46.8	NG	80.0	48.6	480	3	60	1	16	25	1400	NOTE 1,2,3,4,5,6,7,8,9,10,11,12
RTU - 14	TRANE	YSD090	2700	550	0.80	7.5	105	80	67	95	72.9	NG	120.0	97.2	480	3	60	2	22.6	35	1500	NOTE 1,2,3,4,5,6,7,8,9,10,11,12
RTU - 15	TRANE	YSC060	2000	120	0.80	5	105	80	67	63.1	46.9	NG	80.0	48.0	480	3	60	1	16	25	1400	NOTE 1,2,3,4,5,6,7,8,9,10,11,12
RTU - 16	TRANE	YSC060	2000	750	0.80	5	105	80	67	63.1	46.5	NG	80.0	48.0	480	3	60	1	16	25	1400	NOTE 1,2,3,4,5,6,7,8,9,10,11,12

NOTES:
1.) PROVIDE 14" HIGH FACTORY FABRICATED INSULATED SOUND-ATTENUATING ROOF CURB.
2.) SET MINIMUM OUTSIDE AIR AS SPECIFIED ABOVE. OUTSIDE AIR DAMPER SHALL FULLY CLOSE ON UNIT SHUTDOWN.
3.) PROVIDE 5-MINUTE TIME DELAY ON COMPRESSOR RESTART.
4.) PROVIDE INTEGRATED ENTHALPY ECONOMIZER.
5.) PROVIDE FACTORY MOUNTED AND WIRED DISCONNECT SWITCH. UNIT SHALL HAVE SINGLE POINT WIRING CONNECTION.
6.) MODEL NUMBERS ARE GENERAL MODEL NUMBERS FOR BASIS OF DESIGN. MODEL NUMBER MAY NOT INCLUDE ALL ACCESSORIES REQUIRED.
7.) PROVIDE FACTORY MOUNTED 120 VOLT DUPLEX SERVICE RECEPTACLE. RECEPTACLE SHALL BE INTERCONNECTED UPSTREAM OF FACTORY WIRED UNIT DISCONNECT SUCH THAT RECEPTACLE REMAINS ENERGIZED WHEN DISCONNECT SWITCH IS OPENED.
8.) PROVIDE RELAY CONTACTOR TO SHUTDOWN ROOFTOP UNIT ON DETECTION OF SMOKE.
9.) PROVIDE AUDITORIUM UNITS WITH HOT GAS REHEAT OPTION.
10.) FURNISH WITH CO2 SENSOR FOR DEMAND CONTROL VENTILATION.
11.) FURNISH WITH MERV 13 FILTERS.
12.) UNIT SHALL HAVE A MINIMUM SHORT CIRCUIT CURRENT RATING (SCCR) OF 5 KAIC.
13.) UNIT SHALL HAVE A MINIMUM SHORT CIRCUIT CURRENT RATING (SCCR) OF 65 KAIC.

EXHAUST AND VENTILATION FAN SCHEDULE

MARK	MANUFACTURER	MODEL	FAN TYPE	DRIVE TYPE	PERFORMANCE FLOW (CFM)	PERFORMANCE E.S.P. (IN.W.C.)	PERFORMANCE SPEED (RPM)	PERFORMANCE SONES	ELECTRICAL FAN (HP)	ELECTRICAL VOLTS	ELECTRICAL Ø	ELECTRICAL HZ	ACCESSORIES	WEIGHT (LBS)	REMARKS
EF - 2	GREENHECK	G-121-B	CENTRIFUGAL ROOF MTD. DOWNBLAST	DIRECT	750	0.375	1140	8.1	0.17	120	1	60	BS, BD, RC, WP	80	
EF - 3	GREENHECK	G-121-B	CENTRIFUGAL ROOF MTD. DOWNBLAST	DIRECT	750	0.375	1140	8.1	0.17	120	1	60	BS, BD, RC, WP	80	
EF - 4	GREENHECK	G-121-B	CENTRIFUGAL ROOF MTD. DOWNBLAST	DIRECT	750	0.375	1140	8.1	0.17	120	1	60	BS, BD, RC, WP	80	
EF - 5	GREENHECK	G-121-B	CENTRIFUGAL ROOF MTD. DOWNBLAST	DIRECT	750	0.375	1140	8.1	0.17	120	1	60	BS, BD, RC, WP	80	
EF - 6	GREENHECK	G-121-B	CENTRIFUGAL ROOF MTD. DOWNBLAST	DIRECT	750	0.375	1140	8.1	0.17	120	1	60	BS, BD, RC, WP	80	
EF - 7	GREENHECK	G-121-B	CENTRIFUGAL ROOF MTD. DOWNBLAST	DIRECT	750	0.375	1140	8.1	0.17	120	1	60	BS, BD, RC, WP	80	
EF - 8	GREENHECK	G-121-B	CENTRIFUGAL ROOF MTD. DOWNBLAST	DIRECT	750	0.375	1140	8.1	0.17	120	1	60	BS, BD, RC, WP	80	
EF - 9	GREENHECK	QB-101-4	CENTRIFUGAL ROOF MTD. DOWNBLAST	BELT	700	0.625	1360	6.9	0.25	120	1	60	BS, BD, RC, WP	85	
EF - 10	GREENHECK	QB-101-4	CENTRIFUGAL ROOF MTD. DOWNBLAST	BELT	675	0.625	1449	7.5	0.25	120	1	0	BS, BD, RC, WP	85	
EF - 11	GREENHECK	QB-81-4	CENTRIFUGAL ROOF MTD. DOWNBLAST	BELT	500	0.625	1401	7.8	0.25	120	1	0	BS, BD, RC, WP	80	

ACCESSORIES:
AD - MOTORIZED CONTROL DAMPER, BS - BIRD SCREEN, BD - BACKDRAFT DAMPER, DS - DISCONNECT SWITCH, IG - INLET GUARD, MR - WALL MOUNTING RING, RC - PREFABRICATED INSULATED ROOF CURB, SC - PREFABRICATED SOUND ATTENUATING ROOF CURB, WG - WALL GRILLE, WP - NEMA 3R DISCONNECT SWITCH.

NOTES:
1.) MODEL NUMBERS ARE GENERAL MODEL NUMBERS FOR BASIS OF DESIGN. MODEL NUMBER MAY NOT INCLUDE ALL ACCESSORIES REQUIRED. SEE SPECIFICATIONS.

GRILLE, REGISTER AND DIFFUSER SCHEDULE

MARK	MANUFACTURER	MODEL	TYPE	NECK SIZE (L"xW")	FACE SIZE (L"xW")	FRAME TYPE	FINISH	ACCESSORIES	REMARKS
A	TITUS	TMS	HIGH PERFORMANCE SQUARE CONE DIFFUSER	RE: DWG.	24"x24"	NOTE 1	WHITE	<35	
B	TITUS	TMRA	ADJUSTABLE ROUND CEILING DIFFUSER	RE: DWG.	RE: DWG.	DUCT	ALUM.	<35	
C	TITUS	50F	EGGCRATE RETURN GRILLE	22"x22"	24"x24"	NOTE 1	WHITE	<30	NOTE 4
D	TITUS	TBDI	ADJ. GASKET TIPPED BLADE PLENUM SLOT DIFFUSER	RE: DWG.	RE: DWG.	SURFACE	WHITE	<30	
E	TITUS	TMS	HIGH PERFORMANCE SQUARE CONE DIFFUSER	RE: DWG.	12"x12"	NOTE 1	WHITE	<30	
F	TITUS	350FL	EXHAUST GRILLE WITH 35° DEFLECTION	22"x22"	24"x24"	NOTE 1	WHITE	<30	
G	TITUS	50F	EGGCRATE RETURN GRILLE	22"x10"	24"x12"	NOTE 1	WHITE	<30	NOTE 5
H	TITUS	350RL	ADJ. SUPPLY GRILLE WITH DOUBLE DEFLECTION	RE: DWG.	RE: DWG.	SURFACE	WHITE	<30	

ACCESSORIES:
OBD - OPPOSED BLADE DAMPER, LSP - LINEAR SLOT PLENUM

NOTES:
1.) LAY-IN FRAME FOR LAY-IN CEILINGS. PLASTER FRAME FOR GYPSUM BOARD CEILINGS. SEE ARCHITECTURAL DRAWINGS FOR CEILING TYPES.
2.) PAINT TO MATCH CEILINGS. NC FOR AUDITORIUMS TO BE <20.
3.

UNIT HEATER SCHEDULE

MARK	MANUFACTURER	MODEL	TYPE	AIRFLOW SUPPLY (CFM)	HEATING COIL INPUT (MBH)	HEATING COIL OUTPUT (MBH)	ELECTRICAL VOLTS	ELECTRICAL Ø	ELECTRICAL HZ	ELECTRICAL MCA (A)	ELECTRICAL MOP (A)	REMARKS
UH - 1	TRANE	UHEC	SPOT HEATER	400	20.0	17.060	208	1	60	30.1	35	NOTE 1,2,3,4

NOTES:
1.) PROVIDE UNIT MOUNTED THERMOSTAT.
2.) PROVIDE DISCONNECT SWITCH.
3.) PROVIDE WALL MOUNTING BRACKET.

BASEBOARD HEATER SCHEDULE

MARK	MANUFACTURER	MODEL	TYPE	LENGTH (FT.)	ELECTRIC HEAT WATT DENSITY (WATT.)	ELECTRIC HEAT TOTAL POWER (KW)	ELECTRICAL VOLTS	ELECTRICAL Ø	ELECTRICAL HZ	ELECTRICAL MCA (A)	ELECTRICAL MOP (A)	FINISH	REMARKS
BH - 1	TRANE	RDBT-PD	ELECTRIC BASEBOARD	6	125	0.75	208	1	60	3.6	5	BLACK ANODIZED	NOTE 1,2,3,4,5
BH - 2	TRANE	RDBT-PD	ELECTRIC BASEBOARD	8	125	1.00	208	1	60	4.8	6	BLACK ANODIZED	NOTE 1,2,3,4,5
BH - 3	TRANE	RDBT-PD	ELECTRIC BASEBOARD	8	125	1.00	208	1	60	4.8	6	BLACK ANODIZED	NOTE 1,2,3,4,5
BH - 4	TRANE	RDBT-PD	ELECTRIC BASEBOARD	8	125	1.00	208	1	60	4.8	6	BLACK ANODIZED	NOTE 1,2,3,4,5
BH - 5	TRANE	RDBT-PD	ELECTRIC BASEBOARD	8	125	1.00	208	1	60	4.8	6	BLACK ANODIZED	NOTE 1,2,3,4,5
BH - 6	TRANE	RDBT-PD	ELECTRIC BASEBOARD	8	125	1.00	208	1	60	4.8	6	BLACK ANODIZED	NOTE 1,2,3,4,5
BH - 7	TRANE	RDBT-PD	ELECTRIC BASEBOARD	8	125	1.00	208	1	60	4.8	6	BLACK ANODIZED	NOTE 1,2,3,4,5
BH - 8	TRANE	RDBT-PD	ELECTRIC BASEBOARD	8	125	1.00	208	1	60	4.8	6	BLACK ANODIZED	NOTE 1,2,3,4,5

NOTES:
1.) PROVIDE WITH UNIT MOUNTED THERMOSTAT.
2.) PROVIDE WITH DISCONNECT SWITCH.
3.) PROVIDE WITH PEDISTAL KIT.
4.) PROVIDE SPLICE PLATES, WALL TRIM, AND BLANK SECTIONS AS REQUIRED FOR CONTINUOUS APPEARANCE.
5.) FIELD VERIFY EXACT LENGTHS.

MECHANICAL SYMBOLS

- EXISTING DUCT/PIPE TO REMAIN
- EXISTING PIPE TO REMAIN
- EXISTING DUCT/PIPE TO BE REMOVED
- NEW SHEET METAL DUCTWORK
- SUPPLY OR OUTSIDE AIR DUCT
- RETURN AIR DUCT
- EXHAUST AIR DUCT
- DUCTWORK TRANSITION
- DUCTWORK TRANSITION - RECTANGULAR TO ROUND
- SUPPLY DUCT ELBOW UP OR DOWN
- RETURN DUCT ELBOW UP OR DOWN
- EXHAUST DUCT ELBOW UP OR DOWN
- DUCT ELBOW WITH FIXED TURNING VANES
- DUCT BRANCH TAKE-OFF
- ROUND SPIN-IN WITH DAMPER
- SQUARE TO ROUND TAP WITH DAMPER
- FLEXIBLE CONNECTION
- FIRE DAMPER
- VOLUME DAMPER
- FLEXIBLE DUCTWORK

- SUPPLY DIFFUSER
- SUPPLY DIFFUSER WITH 3-WAY THROW
- RETURN GRILLE
- EXHAUST GRILLE
- ROOF MOUNTED EXHAUST FAN
- UNIT HEATER
- THERMOSTAT - ELECTRIC
- TEMPERATURE SENSOR
- CONNECT TO EXISTING
- DIFFUSER DESIGNATION, CFM AND NECK SIZE
- HVAC NOTE DESIGNATION
- DEMOLITION NOTE DESIGNATION
- NOTE DESIGNATION
- MECHANICAL EQUIPMENT DESIGNATION
- BDD BACKDRAFT DAMPER
- CFM CUBIC FEET PER MINUTE
- ESP EXTERNAL STATIC PRESSURE
- FD FIRE DAMPER
- RTU ROOFTOP UNIT
- TSP TOTAL STATIC PRESSURE
- TYP TYPICAL

NOTE: TYPICAL OBJECT MAY NOT BE IN KEY SYMBOL OR DEVICE APPEARING ON THIS LEGEND.

Order Plans @ WWW.LDLine.com

THIS DRAWING IS A SINGLE PART OF AN INTEGRATED SET OF CONSTRUCTION CONTRACT DOCUMENTS. BOTH TO CREATING AND PREPARATION AND THE CONTRACT ARE NOT LIMITED TO: ALL "GENERAL CONDITIONS", "SUMMARY OF WORK", AND APPLICABLE SPECIFICATION SECTIONS WHICH NOTE TO THIS DRAWING. APPLY TO ALL DISCIPLINES FOR THE COMPLETE CONTRACT. THE CONTRACTOR WILL BE RESPONSIBLE FOR ALL MATERIALS WITH CONFLICTS IN THE "SET" OF CONTRACT DOCUMENTS. THE CONTRACTOR IS RESPONSIBLE TO NOTIFY THE ARCHITECT IN WRITING OF ANY CONFLICTS OR DISCREPANCIES BEFORE PROCEEDING WITH THE WORK. THE CONTRACTOR SHALL NOT TAKE ADVANTAGE OF ANY APPARENT ERROR OR OMISSION IN THE CONTRACT DOCUMENTS. IN THE EVENT OF SUCH DISCREPANCY, THE CONTRACTOR SHALL BRING IT TO THE ATTENTION OF THE ARCHITECT BEFORE PROCEEDING WITH THE WORK. THE CONTRACTOR SHALL NOT TAKE ADVANTAGE OF ANY APPARENT ERROR OR OMISSION IN THE CONTRACT DOCUMENTS. IN THE EVENT OF SUCH DISCREPANCY, THE CONTRACTOR SHALL BRING IT TO THE ATTENTION OF THE ARCHITECT BEFORE PROCEEDING WITH THE WORK. THE CONTRACTOR SHALL NOT TAKE ADVANTAGE OF ANY APPARENT ERROR OR OMISSION IN THE CONTRACT DOCUMENTS. IN THE EVENT OF SUCH DISCREPANCY, THE CONTRACTOR SHALL BRING IT TO THE ATTENTION OF THE ARCHITECT BEFORE PROCEEDING WITH THE WORK.

THIS DOCUMENT SHALL NOT BE USED FOR ANY OTHER PROJECTS, FOR ADDITIONS TO THIS PROJECT, OR FOR COMPLETION OF THIS PROJECT BY OTHERS WITHOUT THE PRIOR WRITTEN CONSENT OF GIBBONS DRAKE SCOTT. ANY UNAUTHORIZED, AND/OR CONSENT THAT DOES NOT INCLUDE THE INDEMNITY AND RELEASE OF GIBBONS DRAKE SCOTT, INC. ITS OFFICERS, EMPLOYEES AND AGENTS FROM ANY AND ALL LIABILITY, WILL BE AT THE RECIPIENT'S SOLE RISK AND WITHOUT LIABILITY TO GIBBONS DRAKE SCOTT, AND USER OF DOCUMENT AGREES TO INDEMNIFY AND HOLD HARMLESS GIBBONS DRAKE SCOTT, INC. ITS OFFICERS, EMPLOYEES AND AGENTS FROM ANY AND ALL CLAIMS, LOSSES, OR DAMAGES ARISING OUT OF THE MODIFICATION OR UNAUTHORIZED USE OF THESE DOCUMENTS.

THIS DRAWING AND DESIGN IS COPYRIGHT 2014 ©

GEORGIA REGISTERED No. PE013496 PROFESSIONAL ENGINEER TIM L. SCOTT
SIGNATURE: DATE:

GDS ENGINEERING
Gibbons, Drake, Scott, Inc.
1003 E. 62nd Street, Suite 100
Raytown, Missouri 64133
Phone: (816) 358-1700
Fax: (816) 358-2367
www.gdsengr.com
GEORGIA COA #PEF000363

SHEET LEGEND

G000x	GENERAL INFORMATION & SCOPE OF WORK
A100x	FLOOR PLANS & DETAILS
A200x	FLOOR PLANS & CEILING PLANS
A300x	EXTERIOR & INTERIOR ELEVATIONS
A350x	BUILDING SECTIONS
A400x	ENLARGED PLANS
A450x	EXTERIOR & INTERIOR DETAILS
A500x	DOOR SCHEDULE, DOOR DETAILS, FINISH SCHEDULE, FINISH PLANS
G160x	SIGNAGE, LIGHT AND ELECTRICAL
G430x	AUDITORIUM SEATING PLAN
S1x	STRUCTURAL
M1x	MECHANICAL
P1x	PLUMBING
E1x	ELECTRICAL
W1x	WAYFINDING DETAILS
F1x	CASEWORK & EQUIPMENT

MADISON YARDS 8
AMC NEW BUILD
905 MEMORIAL DRIVE SE
ATLANTA, GA 30316

American Multi-Cinema, Inc.
One AMC Way
11500 Ash Street
Leawood, KS 66211

No.	Date	Description

Project Issue Date:

KEY PLAN:

SHEET TITLE:
MECHANICAL SCHEDULES

SHEET NUMBER:
M000