


# Order Plans



1. THE MURPHY STATION WILL NOT DROP THE WAL-MART GREEN SPACE BELOW CITY REQUIREMENTS.
2. ALL PERMANENT TURF AREAS MUST BE SOODED.
3. GC TO ENSURE THAT TRAFFIC THROUGH MAIN WAL-MART DRIVES IS NOT INTERRUPTED AT ANY TIME DUE TO CONSTRUCTION ACTIVITIES. ENSURE A MINIMUM TEMPORARY LANE WIDTH OF 10' (EACH DIRECTION) IS AVAILABLE AT ALL TIMES, FREE OF OBSTRUCTIONS TO VEHICLES. AT NO TIME SHALL THE CONSTRUCTION FENCE EXTEND INTO THE DRIVE MORE THAN 2' FROM THE FACE OF THE CURB OR DRIVE.
4. IF DEMOLITION OR CONSTRUCTION ON SITE WILL INTERFERE WITH THE WAL-MART TRAFFIC FLOW OR ADJACENT PROPERTY OWNER'S TRAFFIC FLOW, THE CONTRACTOR SHALL COORDINATE WITH THE WAL-MART CONSTRUCTION/STORE MANAGER AND/OR ADJACENT PROPERTY OWNER, TO MINIMIZE THE IMPACT ON TRAFFIC FLOW. TEMPORARY RE-ROUTING OF TRAFFIC IS TO BE ACCOMPLISHED BY USING DOT APPROVED TRAFFIC BARRICADES, BARRELS, AND/OR CONES. TEMPORARY SIGNAGE AND FLAGMEN MAY BE ALSO NECESSARY.
5. ALL WAL-MART PROPERTY DAMAGED DUE TO CONSTRUCTION ACTIVITIES MUST BE REPLACED/RESTORED TO MATCH THE EXISTING TYPE AND QUALITY OF WORK AND MATERIALS, AND IS SUBJECT TO WAL-MART APPROVAL.
6. UTILITY WORK DONE ON WAL-MART PARCEL, WHETHER BY THE GC, CITY OR THE UTILITY COMPANIES, SHALL BE REPAIRED BACK TO EXISTING CONDITIONS.
7. EROSION CONTROL MEASURES IMPLEMENTED INSIDE THE WAL-MART DRIVE ISLES AND PARKING LOT SHALL INCLUDE ONLY SILT BASINS (OR WAL-MART PRE-APPROVED EQUAL) TO ENSURE TRAFFIC CIRCULATION IS NOT IMPEDED. GRAVEL INLET PROTECTION DEVICES SHALL NOT BE ALLOWED INSIDE THE WAL-MART DRIVE ISLES OR PARKING LOT.
8. GC SHALL UTILIZE DIRECTIONAL DRILLING AND BORE METHODS TO INSTALL SERVICE LINES THROUGH THE WAL-MART PARKING LOT, DRIVE AREAS OR DRIVE DRIVE.



### LEGEND

EXISTING	
[Symbol]	EXISTING BUILDING
[Symbol]	LAND LOT LINE (LLL)
[Symbol]	PROPERTY LINE
[Symbol]	UTILITY (GAS, OVERHEAD LINES)
[Symbol]	FIBER OPTIC CABLE
[Symbol]	PIPE LINE
[Symbol]	SEWER MANHOLE
[Symbol]	SANITARY CLEAN-OUT (SCO)
[Symbol]	TELEPHONE MANHOLE/PEDESTAL
[Symbol]	STORAGE TANK WITH HEADWALL
[Symbol]	DOUBLE-WHOLE-ENDED BASIN
[Symbol]	DOUBLE-WHOLE-CATCH BASIN
[Symbol]	MANHOLE BOX (MB)
[Symbol]	TRAP OR CURB INLET (DI OR CI)
[Symbol]	FENCE
[Symbol]	DRAINAGE DITCH OR SWALE
[Symbol]	EXISTING 10 FOOT CONTOUR
[Symbol]	EXISTING 2 FOOT CONTOUR
[Symbol]	EXISTING GRADE SPOT ELEVATION
[Symbol]	DIRECTION OF SURFACE FLOW
[Symbol]	RECORDED DATA
[Symbol]	PARKING SPACE COUNT
[Symbol]	LIGHT POLE (LP)
[Symbol]	ELECTRICAL TRANSFORMER BOX
[Symbol]	ELECTRICAL METER
[Symbol]	ELECTRICAL STUB OUT
[Symbol]	WATER VALVE
[Symbol]	GAS VALVE
[Symbol]	WATER METER
[Symbol]	GAS METER
[Symbol]	WELL
[Symbol]	MONITORING WELL
[Symbol]	POST INDICATOR VALVE
[Symbol]	MAILBOX
[Symbol]	STREET SIGN
[Symbol]	TRAFFIC SIGNAL POLE
[Symbol]	TRAFFIC SIGNAL BOX
[Symbol]	BACKFLOW PREVENTER
[Symbol]	FIRE DEPT. CONNECTION
[Symbol]	FIBER OPTIC BOX
[Symbol]	IRRIGATION CONTROL VALVE
[Symbol]	DRAINAGE MANHOLE
[Symbol]	RIGHT-OF-WAY
[Symbol]	REBAR PIN FOUND
[Symbol]	OPEN TOP PIPE FOUND
[Symbol]	CRIMP TOP PIPE FOUND
[Symbol]	CONCRETE MONUMENT FOUND
[Symbol]	ALIAS FOUND
[Symbol]	BRASS DISK FOUND
[Symbol]	ALIAS FOUND
[Symbol]	REBAR PIN SET

### UTILITY CONTACT INFORMATION

**ELECTRIC**  
 SCANA ENERGY  
 19 MONTAGUE AVE  
 GREENWOOD, SC 29646  
 CONTACT: NEAL ANDERSON  
 PHONE: (864) 227-5433  
 FAX: (864) 993-8772

**TELEPHONE**  
 AT&T  
 SEWER  
 GREENWOOD METROPOLITAN DISTRICT  
 110 METRO DRIVE  
 GREENWOOD, SC 29646  
 CONTACT: BRIAN WALKER  
 PHONE: (864) 942-8901

### UTILITY INSTALLATION RESPONSIBILITIES

ELECTRIC RESPONSIBILITY	GENERAL CONTRACTOR			UTILITY PROVIDER			N/A		
	CONDUIT / TRENCH	TRANSFORMER PAD	CT CABINET	EASEMENTS (TRANSFORMER)	EASEMENTS (SECONDARY LINE)				
	X		X						X

TELEPHONE RESPONSIBILITY	GENERAL CONTRACTOR			UTILITY PROVIDER			N/A		
	CONDUIT / TRENCH	PULL STRINGS							
	X	X							

WATER RESPONSIBILITY	GENERAL CONTRACTOR			UTILITY PROVIDER			N/A		
	TAP	DOMESTIC METER	DOMESTIC BFP	IRRIGATION METER	IRRIGATION BFP	HYDRANT	EASEMENTS		
	X	X	X	X	X				X

SEWER RESPONSIBILITY	GENERAL CONTRACTOR			UTILITY PROVIDER			N/A		
	TAP	EASEMENTS							
	X								X

### UTILITY FEE SCHEDULE

WATER & SANITARY SEWER FEES TO BE PAID BY MURPHY:  
 WATER:  
 \$265.00 DOMESTIC METER, TAP & RPZ  
 \$265.00 IRRIGATION METER, TAP & RPZ  
 \$1,330.00 TOTAL

SANITARY SEWER:  
 \$1,000.00 TAP FEE

### METER SIZES

DOMESTIC: 1" (EXISTING)  
 IRRIGATION: 1"

### PROPOSED LEGEND

[Symbol]	BOUNDARY LINE
[Symbol]	SANITARY SEWER SERVICE
[Symbol]	UNDERGROUND ELECTRIC SERVICE
[Symbol]	UNDERGROUND TELEPHONE SERVICE
[Symbol]	WATER SERVICE
[Symbol]	CONSTRUCTION FENCE (SEE CIVIL DETAILS)
[Symbol]	CONSTRUCTION FENCE ON PAVEMENT (SEE CIVIL DETAILS)

### GENERAL UTILITY NOTES

1. ALL BUILDING WATER LINES FROM METER TOWARDS BUILDING SHALL BE SCHEDULE 40 PVC MEETING ASTM D1785 & D2685 SPECIFICATIONS, AND SHALL BE RATED FOR USE WITH POISSON RATIO PER NSF STD. 61 & STD.14, WITH 36" MIN. COVER.
2. ALL SANITARY SEWER LINES SHALL BE SCHEDULE 40 PVC UNLESS OTHERWISE SPECIFIED BY THE UTILITY COMPANY, PROVIDE 36" MINIMUM COVER.
3. CONTRACTOR SHALL COORDINATE ANY DISRUPTIONS TO EXISTING UTILITY SERVICES WITH ADJACENT PROPERTY OWNERS.
4. ALL ELECTRIC AND TELEPHONE EXTENSIONS INCLUDING SERVICE LINES SHALL BE CONSTRUCTED TO THE APPROPRIATE UTILITY COMPANY SPECIFICATIONS. ALL UTILITY DISCONNECTIONS SHALL BE COORDINATED WITH THE DESIGNATED UTILITY COMPANIES.
5. CONSTRUCTION SHALL NOT START ON ANY PUBLIC UTILITY SYSTEM UNLESS WRITTEN APPROVAL HAS BEEN RECEIVED BY THE ENGINEER FROM THE APPROPRIATE GOVERNING AUTHORITY AND CONTRACTOR HAS BEEN NOTIFIED BY THE ENGINEER.
6. PRIOR TO THE CONSTRUCTION OF OR CONNECTION TO ANY STORM DRAIN, SANITARY SEWER, WATER MAIN OR ANY OTHER UTILITIES, THE CONTRACTOR SHALL EXAMINE, VERIFY AND CALCULATE ALL POINTS OF CONNECTION AND ALL UTILITY CROSSINGS AND INFORM GREENBERGFARROW ENGINEERS AND THE OWNER/DEVELOPER OF ANY CONFLICT OR REQUIRED DEVIATIONS FROM THE PLAN. NOTIFICATION SHALL BE MADE A MINIMUM OF (72) HOURS PRIOR TO CONSTRUCTION AND ITS CLIENTS SHALL BE HELD HARMLESS IN THE EVENT THAT THE CONTRACTOR FAILS TO MAKE SUCH NOTIFICATION.
7. CONTRACTOR SHALL COMPLY COMPLETELY WITH THE LATEST STANDARDS OF OSHA DIRECTIVES OR ANY OTHER AGENCY HAVING JURISDICTION FOR EXCAVATION AND TRENCHING PROCEDURES. THE CONTRACTOR SHALL USE SUPPORT SYSTEMS, SLOPING, BENCHING AND OTHER MEANS OF PROTECTION. THIS IS TO INCLUDE, BUT NOT LIMITED TO ACCESS AND EGRESS FROM ALL EXCAVATION AND TRENCHING. CONTRACTOR IS RESPONSIBLE FOR COMPLYING WITH PERFORMANCE CRITERIA AS REQUIRED BY OSHA.

### UTILITY NOTES

- 22A POINT OF CONNECTION - WATER SERVICE (PER LOCAL CODES)
  - 22L METERED DOMESTIC WATER SERVICE ENTRY
  - 22M PROPOSED WATER METER (SEE THIS SHEET)
  - 23E SANITARY SEWER SERVICE ENTRY (PER ARCH. PLANS)
  - 23L CONNECT GREASE TRAP VENT TO BUILDING VENT SYSTEM. GREASE TRAP VENT INVERT MUST BE HIGHER THAN INLET INVERT.
  - 24A POINT OF CONNECTION FOR UNDERGROUND ELECTRIC SERVICE
  - 24E PROPOSED POLE MOUNTED TRANSFORMER
  - 28A POINT OF CONNECTION FOR UNDERGROUND TELEPHONE
  - 300 VERIFY LOCATION AND DEPTH OF EXISTING UTILITY BEFORE CONSTRUCTING PROPOSED UTILITY
- UTILITY DETAILS - SEE DETAIL SHEETS
- 39G SANITARY SEWER GREASE TRAP
  - 40B SANITARY SEWER WYE CONNECTION
  - 40C SANITARY SEWER CLEAN-OUT
  - 40E SANITARY SEWER SERVICE CONNECTION TO EXISTING STUB OUT
  - 41G REDUCED PRESSURE ZONE BACKFLOW PREVENTER. CONTRACTOR TO VERIFY TYPE (ABOVE/UNDERGROUND) PRIOR TO COMMENCING CONSTRUCTION. SEE DETAIL THIS SHEET

**GreenbergFarrow**  
 1430 W. PEACHTREE ST., NW SUITE 200  
 ATLANTA, GA 30309  
 PHONE: (404) 601-8000  
 FAX: (404) 601-8000  
 DWG. NAME: GREENWOOD, SOUTH CAROLINA  
 JOB NO.: 20107840

**MURPHY OIL USA, INC.**  
 200 PEACH STREET  
 P.O. BOX 7000  
 EL DORADO, AR 71730-7000

**MURPHY SUPERCENTER #1382**  
 508 SC -72  
 GREENWOOD SOUTH CAROLINA

**GreenbergFarrow**  
 1430 W. PEACHTREE ST., NW SUITE 200  
 ATLANTA, GA 30309  
 PHONE: (404) 601-8000  
 FAX: (404) 601-8000  
 DWG. NAME: GREENWOOD, SOUTH CAROLINA  
 JOB NO.: 20107840

**MURPHY OIL USA, INC.**  
 200 PEACH STREET  
 P.O. BOX 7000  
 EL DORADO, AR 71730-7000

**MURPHY SUPERCENTER #1382**  
 508 SC -72  
 GREENWOOD SOUTH CAROLINA