TYPICAL GENERAL NOTES

1. ALL WORK SHALL CONFORM TO THE REQUIREMENTS OF LOCAL STATE BUILDING CODE, FIRE DEPARTMENT RULES AND REGULATIONS, UTILITY COMPANY REQUIREMENTS, AND THE BEST TRADE PRACTICES.
2. BEFORE COMMENCING WORK, THE CONTRACTOR SHALL FILE ALL REQUIRED INSURANCE CERTIFICATES WITH THE DEPARTMENT OF BUILDINGS, OBTAIN ALL REQUIRED PERMITS, AND PAY ALL FEES REQUIRED BY THE GOVERNING LOCAL STATE AGENCIES.
3. MINOR DETAILS NOT USUALLY SHOWN OR SPECIFIED, BUT REQUIRED FOR PROPER CONSTRUCTION OF ANY PART OF THE WORK SHALL BE INCLUDED AS IF THEY WERE INDICATED IN THE DRAWINGS.
4. THE CONTRACTOR SHALL COORDINATE ALL WORK PROCEDURES WITH THE STIPULATIONS OF THE LOCAL AUTHORITIES.
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING & NEW CONDITIONS AND MATERIALS WITHIN THE PROPOSED CONSTRUCTION AREA. THE CONTRACTOR SHALL DESIGN AND INSTALL ADEQUATE SHORING AND BRACING FOR ALL STRUCTURAL OR REMOVAL TASKS. THE CONTRACTOR SHALL HAVE SOLE RESPONSIBILITY FOR ANY DAMAGE OR INJURIES CAUSED BY OR DURING THE EXECUTION OF THE WORK.
6. THE CONTRACTOR SHALL LAY OUT HIS OWN WORK, AND SHALL PROVIDE ALL DIMENSIONS REQUIRED FOR OTHER TRADES: PLUMBING, ELECTRICALS, ETC.
7. PLUMBING WORK SHALL BE PERFORMED BY PERSONS LICENSED IN THEIR TRADES, WHO SHALL ARRANGE FOR AND OBTAIN THROUGH THE DEPARTMENT OF BUILDINGS ALL REQUIRED PERMITS, INSPECTIONS AND REQUIRED SIGN OFFS.
8. ELECTRICAL WORK SHALL BE PERFORMED BY PERSONS LICENSED IN THEIR TRADES, WHO SHALL ARRANGE FOR AND OBTAIN THROUGH THE BUREAU OF ELECTRICAL CONTROL ALL REQUIRED PERMITS, INSPECTIONS AND REQUIRED SIGN OFFS.
9. THE CONTRACTOR SHALL DO ALL CUTTING, PATCHING, REPARING AS REQUIRED TO PERFORM ALL OF THE WORK INDICATED ON THE DRAWINGS, AND ALL OTHER WORK THAT MAY BE REQUIRED TO COMPLETE THE JOB..
10. ALL PIPING AND WIRING SHALL BE REMOVED TO A POINT OF CONCEALMENT AND SHALL BE PROPERLY CAPPED OR PLUGGED.

TYPICAL PROTECTION NOTES

TENANT PROTECTION PLAN

CONSTRUCTION DOCUMENTS FOR ALTERATIONS OF BUILDINGS IN WHICH ANY SPACE WILL BE OCCUPIED DURING CONSTRUCTION SHALL INCLUDE A TENANT PROTECTION PLAN. SUCH PLAN SHALL CONTAIN A STATEMENT THAT THE BUILDING CONTAINS DWELLING UNITS THAT WILL BE OCCUPIED DURING CONSTRUCTION AND SHALL INDICATE IN SUFFICIENT DETAIL THE SPECIFIC UNITS THAT ARE OR MAY BE OCCUPIED DURING CONSTRUCTION, THE MEANS AND METHODS TO BE EMPLOYED TO SAFEGUARD THE SAFETY AND HEALTH OF THE OCCUPANTS, INCLUDING, WHERE APPLICABLE, DETAILS SUCH AS TEMPORARY FIRE-RATED ASSEMBLIES, OPENING PROTECTIVES, OR DUST CONTAINMENT PROCEDURES. THE ELEMENTS OF THE TENANT PROTECTION PLAN MAY VARY DEPENDING ON THE NATURE AND SCOPE OF THE WORK BUT AT A MINIMUM SHALL MAKE DETAILED AND SPECIFIC PROVISIONS FOR:

1. EGRESS. AT ALL TIMES IN THE COURSE OF CONSTRUCTION PROVISION SHALL BE MADE FOR ADEQUATE EGRESS AS REQUIRED BY THIS CODE AND THE TENANT PROTECTION PLAN SHALL IDENTIFY THE EGRESS THAT WILL BE PROVIDED. REQUIRED EGRESS SHALL NOT BE OBSTRUCTED AT ANY TIME EXCEPT WHERE APPROVED BY THE COMMISSIONER.
2. FIRE SAFETY. ALL NECESSARY LAWS AND CONTROLS, INCLUDING THOSE WITH RESPECT TO OCCUPIED DWELLINGS, AS WELL AS ADDITIONAL SAFETY MEASURES NECESSITATED BY THE CONSTRUCTION SHALL BE STRICTLY OBSERVED.
3. HEALTH REQUIREMENTS. SPECIFICATION OF METHODS TO BE USED FOR CONTROL OF DUST, DISPOSAL OF CONSTRUCTION DEBRIS, PEST CONTROL AND MAINTENANCE OF SANITARY FACILITIES, AND LIMITATION OF NOISE TO ACCEPTABLE LEVELS SHALL BE INCLUDED.
4. THERE SHALL BE INCLUDED A STATEMENT OF COMPLIANCE WITH APPLICABLE PROVISIONS OF LAW RELATING TO LEAD AND ASBESTOS.
5. COMPLIANCE WITH HOUSING STANDARDS. THE REQUIREMENTS OF THE LOCAL HOUSING MAINTENANCE CODE, AND, WHERE APPLICABLE, THE LOCAL STATE MULTIPLE DWELLING LAW SHALL BE STRICTLY OBSERVED.
6. STRUCTURAL SAFETY. NO STRUCTURAL WORK SHALL BE DONE THAT MAY ENDANGER THE OCCUPANTS.
7. NOISE RESTRICTIONS. WHERE HOURS OF THE DAY OR THE DAYS OF THE WEEK IN WHICH CONSTRUCTION WORK MAY BE UNDERTAKEN ARE LIMITED TO THE LOCAL STATE NOISE CONTROL CODE, SUCH LIMITATIONS SHALL BE STATED.

TYPICAL SAFETY NOTES

1. GENERAL: ALL WORK TO BE COMPLETED IN ACCORDANCE WITH STATE BUILDING CODE, AND REGULATIONS OF ALL OTHER AGENCIES HAVING JURISDICTION.
2. MEANS OF EGRESS: ALL EXISTING MEANS OF EGRESS FOR TENANTS OF THE BUILDING TO BE MAINTAINED CLEAR AND FREE OF ALL OBSTRUCTIONS, SUCH AS BUILDING MATERIALS, TOOLS, ETC,
3. FIRE SAFETY: A. ALL BUILDING MATERIALS WHICH ARE STORED AT THE SITE OR ANY AREA OF BUILDING ARE TO BE STORED IN A LOCKED AREA. ACCESS TO THE AREA TO BE CONTROLLED BY THE OWNER, OR THE GENERAL CONTRACTOR. B. ALL MATERIALS TO BE STORED IN A ORDERLY FASHION. C. ALL FLAMMABLE MATERIALS TO BE KEPT TIGHTLY SEALED IN THEIR RESPECTIVE MANUFACTURER'S CONTAINERS. SUCH MATERIALS ARE TO BE KEPT AWAY FROM HEAT. D. ALL FLAMMABLE MATERIALS TO BE USED AND STORED IN AN ADEQUATELY VENTILATED SPACE. E. ALL ELECTRICAL POWER TO BE SHUT OFF WHERE THERE ARE EXPOSED CONDUITS. F. ALL ELECTRICAL POWER IN THE CONSTRUCTION AREA TO BE SHUT OFF AFTER WORKING HOURS. G. CONTRACTOR, AT ALL TIMES, TO ENSURE THERE IS NO NATURAL GAS LEAKAGE IN THE BUILDINGS, OR ANY FLAMMABLE GAS TO BE USED DURING CONSTRUCTION.
4. DUST CONTROL: A. DEBRIS, DIRT AND DUST TO BE KEPT TO A MINIMUM AND CONFINED TO THE IMMEDIATE CONSTRUCTION AREA. B. CONTRACTOR TO ISOLATE CONSTRUCTION AREA FORM OCCUPIED BUILDING AREA BY MEANS OF TEMPORARY PARTITIONS OR HEAVY HEIGHT DROP CLOTHS. C. DEBITS, DIRT, AND DUST TO BE CLEANED UP AND CLEARED FROM THE BUILDING SITE PERIODICALLY TO AVOID EXCESSIVE ACCUMULATION.
5. CONTRACTOR MUST OBTAIN WRITTEN PERMISSION FROM ALL AFFECTED PARTIES TO WORK OTHER THEN REGULAR HOURS.
6. CONSTRUCTION OPERATIONS WILL NOT INVOLVE INTERRUPTION OF HEATING, WATER, OR ELECTRICAL SERVICES TO OTHER TENANTS.
7. THERE WILL BE NO ONE OCCUPYING THE PREMISES TO BE RENOVATED DURING THE COURSE OF CONSTRUCTION WORK.

DISCLAIMER

ALL WORK SHOWN ON THESE DRAWINGS IS THE RESPONSIBILITY OF THE GENERAL CONTRACTOR UNLESS OTHERWISE NOTED ON THE DRAWINGS. THE GENERAL CONTRACTOR IS RESPONSIBLE TO COORDINATE ALL ASPECTS OF CONSTRUCTION AND BUILDING TRADES INCLUDING MILLWORK ITEMS. WORK DENOTED BY M.W.C. (MILLWORK CONTRACTOR) OR BY OWNER WILL BE FURNISHED BY OTHERS.

RESPONSIBILITY MATRIX

DESCRIPTION	SUPPLIED BY								INSTALLED BY					REMARKS
	OWNER - BOWLMOR|AMF	LANDLORD	PROJECT MANAGEMENT	ARCHITECT OF RECORD - CALLISONRTKL	M.E.P. ENGINEERS	STRUCTURAL ENGINEER	GENERAL CONTRACTOR	OWNER SPECIALTY CONTRACTOR	OWNER - BOWLMOR|AMF	LANDLORD	PROJECT MANAGEMENT	GENERAL CONTRACTOR	OWNER SPECIALTY CONTRACTOR	
GENERAL REQUIREMENTS														
ARCHITECTURAL DESIGN & STAMP FOR PERMIT				●										
MEP DESIGN & STAMP FOR PERMIT					●									
STRUCTURAL DESIGN & STAMP FOR PERMIT						●								
PERMITS & FEES							●					●		EXPEDITING BY OWNER'S EXPEDITOR. GC TO PAY ALL ASSOCIATED PERMITS & FEES.
PRELIMINARY WALL / CEILING / MILLWORK LAYOUT							●					●		MILLWORKER TO BE SUBCONTRACTED BY GC.
REVIEW / APPROVAL OF LAYOUT				●										
INSURANCE							●							LIST OWNER AND LANDLORD AS ADDITIONAL INSURED.
INSPECTIONS							●							GC TO HIRE ALL INDEPENDENT SPECIAL INSPECTORS
FINAL CLEANING							●							
PUNCH LIST	●			●	●	●								GC TO PROVIDE PUNCHLIST COMPLETION REPORT.
SITE WORK														
CONSTRUCTION BARRICADES							●					●		GC TO PROVIDE PHASING PLAN AND CONSTRUCTION BARRICADES FOR OPEN RENOVATION.
DEMOLITION							●					●		
SAW CUT SLAB / CORE DRILL							●					●		AS REQ'D, VIF.
TEMPORARY UTILITIES							●					●		COORDINATE TEMPORARY UTILITY REQUIREMENTS WITH OWNER'S CONSTRUCTION PROJECT MANAGER
DUMPSTERS / TRASH DISPOSAL							●					●		
SHORING, RETAINAGE, DRAINAGE, & UNDERPINNING														N/A
SIDEWALKS, PAVERS, & ACCESSORIES														N/A
FENCE & GATES														N/A
LANDSCAPING / PLANTERS														N/A
AWNINGS, CANOPIES, GUTTERS, LEADERS														N/A
CONCRETE														
CONCRETE FLOOR SLAB & REINFORCEMENT							●					●		GC TO PATCH AND REPAIR TO MEET REQUIREMENTS OF NEW FLOOR PLAN.
EXPANSION JOINTS (WALL, CEILING, FLOOR)							●					●		
CEMENTITIOUS UNDERLAYMENT FOR FLOOR DRAINAGE							●					●		
CEMENTITIOUS OVERLAYMENT AND CONCRETE STAIN							●					●		
NEW SUBSTRUCTURE FOR ELEVATED FLOOR AREAS							●					●		
MASONRY														
CONCRETE CMU CONSTRUCTION & REINFORCEMENT														N/A
BRINK VENEER CONSTRUCTION & REINFORCEMENT														N/A
MASONRY CLEANING														N/A
METALS														
STRUCTURAL METAL FRAMING / MISC. SUPPORTS							●					●		
METAL DECKING / STRUCTURAL STEEL							●					●		
INTERIOR METAL FOOTRAILS & HANDRAILS							●					●		
STEEL STAIRS														N/A
WOOD & PLASTICS														
ROUGH CARPENTRY							●					●		
ARCHITECTURAL WOODWORK & MILLWORK							●					●		
FIRE RATED WOOD BLOCKING, TYP.							●					●		
SOLID SURFACE MILLWORK TOPS							●					●		
WOOD VENEER & PLAM MILLWORK TOPS							●					●		
PLYWOOD BACKING FOR AV, SECURITY, UTILITY PANELS							●					●		
MOISTURE & THERMAL CONTROL														
THERMAL & SOUND INSULATION							●					●		
CAULKING, SEALANTS AT JOINTS / BASE IN KITCHEN							●					●		
WATER REPELLENT SHEATHING & COATINGS							●					●		
ROOFING, SHEATHING, FLASHING, MEMBRANES							●					●		GC TO FLASH/SEAL ALL NEW ROOF PENETRATIONS AS REQUIRED.
WATERPROOFING MEMBRANE AT WET LOCATIONS							●					●		GC TO PROVIDE WATERPROOFING MEMBRANE AT FLOOR AND WALLS OF NEW KITCHEN, BATHROOMS AND BAR.
DOORS / OPENINGS														
HOLLOW METAL DOORS, FRAMES & HARDWARE							●					●		
WOOD DOORS, FRAMES & HARDWARE							●					●		
INTERIOR WINDOWS & GLAZING							●					●		
ENTRANCES, STOREFRONTS, EXTERIOR GLAZING												●		EXISTING TO REMAIN, REMOVE/REINSTALL DOO... AS REQUIRED FOR INST...
ACCESS PANELS							●					●		GC TO PROVIDE STEALTH ACCESS PANELS, AS REQ...
FINISHES														
ACCOUSTICAL TILE CEILING SYSTEM							●					●		
GYPSUM BOARD SHEATHING & FRAMING							●					●		
STONE, CERAMIC, QUARRY TILE, & ACCESSORIES							●					●		EPOXY GR... TO BE USED WITH ALL Q...RRY TILE. PROVIDE LATICRETE S... CRACK SUPPRESSION MEMBRANE AS REQUIRED FOR MENUFACTURERS RECOMMENDED INSTALL.
EXTERIOR / INTERIOR PAINT							●					●		
WALLCOVERINGS, SPECIAL FINISHES, & WALL PREP							●					●		
CARPETING & LVT	●						●					●		WALK OFF CAR... FURNISHED ... INSTALLED BY G.C. ALL OTHER CARPET AND HERRINGBONE LVT FURNISHED BY OWNER, INSTALLED BY GC. PROVIDE FLOOR LEVELING AS REQUIRED FOR INSTALL OF NEW FLOORING.
WOOD FLOORING														N/A
SPECIAL CEILING TREATMENTS							●					●		
FLOORING SUBSTRATES, UNDERLAYMENTS, PADDING							●					●		...IDE SUBSTRA... UNDERL... ...UIRED PER MANUFACTURER'S RECOMMENDED INSTALL.
COOLER FLOORING							●					●		...NTINUE QU...RY TILE FINIS... ...ALK-IN COOLERS/FREEZERS.
WALL BASE							●					●		
TRANSITION STRIPS							●					●		PROVIDE ... ...SITIONS AT ALL FLOOR...G MATERIAL CHANGES.
SUBFLOOR PATCHING, FLASHPATCHING & LEVELING							●					●		AS REQ'D
STAINLESS STEEL/FRP PANELS							●	●				●		OSC TO PROVIDE SS... AT KITCHEN, GC TO INSTALL. GC TO PROVIDE AND INSTALL FRP PANELS.
VINYL WALL GRAPHICS (INC OVERHEAD & DOOR GLAZING)	●											●	●	GC TO COORDINATE AND ...EP WALL AS REQUIRED, PROVIDE LEVEL 5 FINISH AT ALL APPLIED SIGNAGE/GRAPHIC LOCATIONS.
STENCILS FOR GRAPHIC PAINTING	●											●		STENCILS SUPPLIED BY OWNER, PAINTING BY GC.
CORREGATED METAL DECK FACING							●					●		
SPECIALTIES														
INTERIOR SIGNAGE & GRAPHICS	●											●	●	GC TO PROVIDE (IF APPLICABLE) ELECTRICAL, BLOCKING, WALL PREP, AND COORDINATE INSTALLATION WITH OWNER'S SIGN CONTRACTOR
EXTERIOR SIGNAGE & GRAPHICS	●											●	●	GC TO PROVIDE (IF APPLICABLE) ELECTRICAL AND BLOCKING, AND COORDINATE INSTALLATION WITH OWNER'S SIGN CONTRACTOR. G.C. TO DEMO EXTERIOR SIGNAGE AND PATCH AND REPAIR AS NECESSARY.
EXTERIOR SITE PYLON / SIGNAGE	●											●	●	GC TO PROVIDE (IF APPLICABLE) ELECTRICAL AND BLOCKING, AND COORDINATE INSTALLATION WITH OWNER'S SIGN CONTRACTOR
EXTERIOR SITE ADA ... DEMARCATION														N/A
EXTERIOR BOLLARDS														N/A
EMPLOYEE LOCKERS & ACCESSORIES														N/A
TOILET COMPARTMENTS & LAVATORY ACCESSORIES							●					●		
WAYFINDING / ADA SIGNAGE							●					●		SUBMIT SIGNAGE PACKAGE SHOP DRAWING FOR AOR APPROVAL PRIOR TO FABRICATION.
PUBLIC ASSEMBLY CAPACITY SIGNAGE							●					●		SUBMIT SIGNAGE PACKAGE SHOP DRAWING FOR AOR APPROVAL PRIOR TO FABRICATION.
AIRSTREAM TRAILER														N/A
VIDEOMASKING SYSTEMS	●								●					
BOWLING SCORING SYSTEM	●												●	GC TO PATCH WOOD FLOORING AT APPROACH.
BALL RETURNS / ...ING EQUIPMENT	●												●	GC TO PATCH WOOD FLOORING AT APPROACH.
BOWLING LANES														N/A
...SETTERS														EXISTING TO REMAIN
SA...	●											●	●	GC TO COORDINATE AND PROVIDE ELECTRICAL CONDUIT (IF REQUIRED).
FURNISHINGS														
FURNITURE & FURNISHINGS	●											●		STORAGE AND FINAL MOVE INTO SPACE BY GC. GC TO COORDINATE AND PROVIDE BLOCKING AS REQUIRED FOR INSTALLATION, TYP.
RECEIPT & ASSEMBLY OF FURNITURE & FURNISHINGS												●		
INTERIOR ARTWORK	●											●		GC TO COORDINATE WITH OWNER/AOR AND PROVIDE BLOCKING + INSTALL OWNER FURNISHED ARTWORK.
WINDOW TREATMENTS & DRAPERY TREATMENTS														N/A
DECORATIVE MIRRORS							●					●		GC TO SUPPLY AND INSTALL AT BAR
LOUNGERS	●											●		STORAGE, ASSEMBLE AND FINAL MOVE INTO SPACE BY GC.
GAMES (FOOSBALL, POOL, ETC.)	●								●					
ARCADE GAMES	●								●					GC TO PROVIDE ALL WIRING AND CONNECTION TO KILL SWITCH
BANQUETTE SEATING														N/A
BUILT-IN WORKSTATIONS							●					●		GC TO PROVIDE 2" DIAMETER GROMMETS AT 4' O.C. AT WORKSURFACES.
OFFICE FURNITURE	●											●		
EQUIPMENT / MECHANICAL														
KITCHEN EQUIPMENT	●											●	●	ALL ELEC., MECH., PLUMB., BLOCKING & PLYWOOD SUBSTRATES BY GC. EQUIPMENT & INSTALL BY KITCHEN VENDOR. FINAL CONNECTION BY GC.
KITCHEN EQUIPMENT DISCONNECTION							●					●		
WALK-IN COOLER & REFRIGERATION	●											●	●	ALL ELECTRICAL, MECHANICAL, PLUMBING, BLOCKING, AND PLYWOOD SUBSTRATES BY GC. EQUIPMENT AND INSTALL BY KITCHEN VENDOR.
WASTE COMPACTORS														N/A
KITCHEN ROUGH-INS							●					●		
TYPE 1 HOOD / COOKING HOOD EXHAUST / TRIM	●											●	●	ALL ELECTRICAL, MECHANICAL, PLUMBING, BLOCKING, AND PLYWOOD SUBSTRATES BY GC. EQUIPMENT AND INSTALL BY KITCHEN VENDOR.
PALCEMENT OF ON-SITE MECH EQUIPMENT / DUNNAGE														N/A
PLACEMENT OF KITCHEN ROOFTOP EQUIPMENT / DUNNAGE							●	●				●		BY OSC, SLEEPERS FOR CONDENSERS / COMPRESSORS ARE FURNISHED AND INSTALLED BY GC.
SPRINKLER SYSTEM DESIGN, INSTALLATION & PERMITING							●					●		GC RESPONSIBLE FOR SUBMITAL AND APPROVAL TO FIRE MARSHALL.
PLUMBING FIXTURES & ACCESSORIES							●					●		
WATER HEATER SYSTEM							●					●		
PLUMBING CONNECTIONS TO KITCHEN EQUIPMENT							●					●		
HEAT, VENTILATION & AIR CONDITIONING	●											●		RTU'S PROVIDED BY OWNER, INSTALLED BY G.C.
DISHWASHING SYSTEM	●											●	●	ALL ELECTRICAL, MECHANICAL, PLUMBING, BLOCKING, AND PLYWOOD SUBSTRATES BY GC. EQUIPMENT AND INSTALL BY KITCHEN VENDOR.
ANSUL FIRE SUPRESSION SYSTEM								●					●	GC TO COORDINATE INSTALL AND INSPECTIONS WITH KEV. 72 HOUR MANDATORY NOTICE FOR BOTH.
AIR CURTAIN UNIT AT EXTERIOR DOOR														N/A
REGISTERS, GRILLES & DIFFUSERS							●					●		
BAR EQUIPMENT								●				●	●	G.C. TO COORDINATE AS REQUIRED, PROVIDE ELECTRICAL AND PLUMBING AS REQ'D. PROVIDE CUT OUT(S) IN MILLWORK/BARTOPS AS REQUIRED. FINAL CONNECTIONS BY G.C.
CAULKING KITCHEN EQUIPMENT							●					●		
BLACK IRON DUCTWORK							●					●		
EXHAUST FANS							●					●		
GENERAL PLUMBING							●					●		
SMALL KITCHEN WARES	●								●					
BEER LINES & TAPS	●											●	●	GC TO PROVIDE ELECTRICAL CONNECTIONS, PROVIDE CONDUIT REFER TO KITCHEN DRAWINGS.
SODA LINES	●											●	●	GC TO PROVIDE ELECTRICAL CONNECTIONS, PROVIDE CONDUIT REFER TO KITCHEN DRAWINGS.
CO2								●					●	C02 LINES BY OWNER SPECIALTY CONTRACTOR.
ELECTRICAL / DATA / AUDIOVISUAL / SECURITY														
LIGHTING	●											●		FINISHES TO BE VERIFIED BY AOR. OWNER TO PROVIDE LIGHT FIXTURES, GC TO INSTALL. OWNER TO PROVIDE EMERGENCY LIGHTS, GC TO INSTALL. GC TO PROVIDE AND INSTALL EXIT SIGNS.
LIGHTING SYSTEM DIMMING PANELS / CONTROLS							●					●		LIGHTING SYSTEM CONTROLS DESIGNED BY ENGINEER OF RECORD. DIMMING PANELS, WHERE APPLICABLE TO BE FURNISHED BY GC, INSTALLED BY ELECTRICAL CONTRACTOR MANUAL CONTROLS (SWITCHES, SLIDING DIMMERS) WHERE APPLICABLE TO BE PROVIDED AND INSTALLED BY ELECTRICAL CONTRACTOR.
ELECTRICAL CONNECTION KICHEN / BAR EQUIPMENT							●					●		
FLOOR BOXES, STUB UPS, POKE-THRUS							●					●		
AV EQUIPMENT / CABLE TV / SATELLITE TV SYSTEMS	●							●				●	●	SPEAKERS, AMPs, RACKS, VIDEO PROJECTORS, TELEVISIONS/CABLE TV/SATELLITE TV BY OWNER/OSC. GC TO PROVIDE ELECTRICAL, CONDUITS, AND BLOCKING. COORDINATE INSTALLATION WITH OWNER/VENDOR. GC. TO PULL ALL AV AND LOW VOLTAGE CABLE, FINAL TERMINATIONS BY VENDOR.
SECURITY SYSTEMS								●				●	●	COORDINATE WITH SECURITY VENDOR. OWNER'S VENDOR TO PULL SECURITY CABLE AND PROVIDE TERMINATIONS. GC TO PROVIDE BACK BOX AND CONDUITS.
POS SYSTEMS	●											●	●	GC. TO COORDINATE AND PULL ELECTRICAL + LOW VOLTAGE CABLE.
POWER & LIGHTING CONDUIT & JUNCTION BOXES							●					●		ELECTRICAL TERMINATIONS BY GC.
AV/TEL/DATA/SECURITY CONDUIT & JUNCTION BOXES							●					●		GC TO PROVIDE CONDUITS AND BOXES. CABLES AND WIRING BY GC.
PIPING/CONDUIT FOR ALL EXPOSED CEILING AREAS							●					●		
AUDIOVISUAL / SECURITY WIRING & CABLING							●	●				●	●	GC. TO PROVIDE CONDUITS AND BOXES. GC TO PROVIDE AV CABLING. OWNER'S VENDOR TO PROVIDE SECURITY CABLING.
TEL / DATA WIRING & CABLING							●					●		GC. TO PULL CABLE, FINAL TERMINATIONS BY GC.
MISC LOW VOLTAGE WIRING & CABLING							●					●		GC. TO PULL CABLE, FINAL TERMINATIONS BY VENDOR.
FIRE ALARM DESIGN, WIRING & CONNECTION							●					●		G.C. MUST USE EXISTING MONITORING COMPANY FOR REVISIONS AND RE-CERTIFICATION TO FIRE MARSHALL.

CALLISONRTKL™
A DESIGN CONSULTANCY OF ARCADIS

CallisonRTKL, Inc.
1420 Fifth Ave., Suite 2400
Seattle, WA 98101
Tel: 206.623.4646

CallisonRTKL Project No: 003-180034.00

Consultant
HENDERSON ENGINEERS
Henderson Engineers, Inc.
83... Suite 300
...exa, KS 662...
...: 913.742.5483

Consultant
GMS
...29 West 27th Street, 5th Floor
New York, NY 10001
Tel: 212.254.0030

BOWLERO - AUGUSTA

ISSUE FOR PERMIT / BID

Client/Owner/Project Address

Bowlmor | AMF
Client Address
222 W44th Street
New York, NY 10036

Project Address
3067 Washington Rd.
Augusta, GA 30907

Bowlero

Issue Drawing Log

	Date	Description
	2018.05.29	ISSUE FOR PERMIT
	2018.05.29	ISSUE FOR BID

Seal

Sheet Identification

SYMBOLS AND RESPONSIBLITIES MATRIX

G-001

©2017 CallisonRTKL Inc.

Order Plans @ WWW.LDILine.com