



PLUMBING ROUGH-IN PLAN
1/2" = 1'-0"

PLUMBING ROUGH-IN SCHEDULE

ITEM	DESCRIPTION	WATER			WASTE			NOTES
		HW	CW	AFF	CONNECTION TYPE	SIZE	AFF	
P16A	COKE FOUNTAIN		1/2"	36"				NIKEC; VERIFY REQUIREMENTS AND MOUNTING HEIGHT
P16B					INDIRECT	1"	FD	
P20A	ICE CUBER		3/8"	56"				THRU WATER FILTER
P20B					INDIRECT	1"	FD	
P25	WALK-IN COOLER				INDIRECT	1"	FD	
P102	DRAINBOARD				INDIRECT	1/2"	FS	
P103A	BLENDER STATION	1/2"	1/2"	20"				
P103B					INDIRECT	1/2"	FS	
P105	ICE BIN				INDIRECT		FS	
P108A	HAND SINK	1/2"	1/2"	20"				
P108B					INDIRECT	1/2"	12"	
P112A	UNDERBAR SINK UNIT	1/2"	1/2"	20"				MANIFOLD DRAINS
P112B					INDIRECT	1/2"	FS	

GENERAL PLUMBING NOTES

PLUMBING CONTRACTOR TO PERFORM ALL WORK ACCORDING TO PREVAILING HEALTH AND BUILDING CODES. ALL FOOD SERVICE PLUMBING COMPONENTS AND EQUIPMENT SHALL BE IN STRICT ACCORDANCE WITH THE NATIONAL SANITATION FOUNDATION (N.S.F.) AND IN COMPLIANCE WITH STATE & LOCAL CODES.

ALL DIMENSIONS ARE FROM FINISHED SURFACES OR CENTER LINE OF COLUMNS TO CENTER LINES OF PLUMBING ROUGH-IN SERVICE LOCATIONS. ALL WRITTEN DIMENSIONS ARE TO BE CONSIDERED CORRECT AND DRAWINGS ARE NOT TO BE SCALED.

PLUMBING CONTRACTOR SHALL PROVIDE AND INSTALL ALL NECESSARY CONTROLS, VALVES, REGULATORS, TRIM, TRAPS, TAILPIECES, STRAINERS, BACK-FLOW PREVENTION DEVICES AND ANY OTHER DEVICES REQUIRED FOR A PROPER INSTALLATION. P.C. SHALL COORDINATE AND MAKE ALLOWANCES SO NOT TO INTERFERE WITH THE OPERATION OF THE FOOD SERVICE EQUIPMENT PROVIDED.

PLUMBING CONTRACTOR SHALL INSTALL AND INTERCONNECT ALL PLUMBING COMPONENTS, ACCESSORIES AND SYSTEMS PROVIDED BY THE FOOD SERVICE EQUIPMENT CONTRACTOR. P.C. TO FLUSH OUT ALL FOREIGN MATTER FROM LINE STRAINERS, FAUCET AERATORS, ETC. PRIOR TO FINAL CONNECTIONS.

PLUMBING CONTRACTOR TO CONCEAL WATER LINES WHENEVER POSSIBLE. EXTERNAL WALLS WATER LINES SHALL BE STUBBED UP ALONG THE INTERIOR FACE OF THE WALL TO AVOID POTENTIAL FREEZING UNLESS OTHERWISE NOTED.

PLUMBING CONTRACTOR TO VERIFY ALL WATER PRESSURE REQUIREMENTS FOR EACH EQUIPMENT AND PROVIDE CONTROL DEVICES FOR PROPER WATER PRESSURE AND OPERATION OF EQUIPMENT AS SPECIFIED BY THE MANUFACTURER.

PLUMBING CONTRACTOR TO VERIFY ALL REQUIREMENTS FOR ITEMS THAT ARE EXISTING, BY OWNER, BY VENDOR, N.L.C., AND BY OTHERS. P.C. TO PROVIDE ALL P.V.C. LINES WITH SWEEP ELS FOR BEVERAGE LINES AND TO VERIFY SIZE AND LOCATIONS WITH THE GENERAL CONTRACTOR.

PLUMBING CONTRACTOR TO PROVIDE AND INSTALL GREASE INTERCEPTORS, FLOOR DRAINS, FLOOR SINKS, TAILPIECES, TRAPS, SHUT-OFFS, LOOP VENTS AS REQUIRED AND TO COORDINATE ALL OF THESE ITEMS WITH THE FOOD SERVICE EQUIPMENT CONTRACTOR.

FLOOR DRAINS SHOWN ARE FOR THE FOOD SERVICE EQUIPMENT ONLY. FLOOR DRAINS REQUIRED FOR GENERAL CLEANING AND CODE REQUIREMENTS TO BE ADDITIONAL. P.C. TO VERIFY LOCATIONS OF ADDITIONAL FLOOR DRAINS WITH THE GENERAL CONTRACTOR. TO VERIFY LOCATIONS OF ADDITIONAL FLOOR DRAINS WITH THE GENERAL CONTRACTOR.

FLOORS IN KITCHEN AND SERVING AREAS TO BE "TRANSIT LEVEL". DO NOT SLOPE FLOOR TO FLOOR DRAINS IN KITCHEN AND SERVING AREAS.

ALL FLOOR SINKS TO BE MOUNTED IN FLOOR SUCH THAT THE TOP OF THE RIM WILL BE FLUSH WITH FINISHED FLOOR ELEVATION. FLOOR SINKS ALSO TO SERVE AS AREA FLOOR DRAINS IF NEED BE.

PLUMBING CONTRACTOR TO INSTALL F.S.E.C. FURNISHED MECHANICAL GAS SHUT-OFF VALVE IN ACCESSIBLE LOCATION PRIOR TO BRANCHING GAS SUPPLY TO COOKING EQUIPMENT.

THIS DRAWING HAS BEEN PREPARED FROM THE ACTUAL ARCHITECTURAL WALL LAYOUT DRAWINGS. PLUMBING CONTRACTOR SHALL ALERT THE GENERAL CONTRACTOR ON SITE OF ANY DISCREPANCIES FOUND BETWEEN THIS DRAWING AND THE ACTUAL FIELD CONDITIONS.

SYMBOL LEGEND

▲	ELECTRICAL CONNECTION
●	PLUMBING SUPPLY
●	PLUMBING DRAIN
●	GAS SUPPLY
⊙	FLOOR DRAIN
⊙	FLOOR SINK

GAS ROUGH-IN SCHEDULE

ITEM	DESCRIPTION	GAS			NOTES
		SIZE	BTU	AFF	
G5	GRIDDLE	3/4"	122,000	16"	
G6	GRIDDLE	3/4"	108,000	36"	
G8	HOTPLATE	3/7"	50,000	36"	

CENTRAL RESTAURANT PRODUCTS

7750 GEORGETOWN ROAD
INDIANAPOLIS, INDIANA 46268

DATE: 04.09.2018
SCALE: AS NOTED
DRAWN BY: LMJ

REVISIONS

BY: DATE:

SHEET

K3

PROJECT NO: 9558

CONTACT: JEFF CHAPMAN

AUGUSTA NATIONAL LANES