1 MECHANICAL DEMO ROOF PLAN
1/8" = 1'-0"

MECHANICAL DEMOLITION PLAN NOTES

1. EXISTING ROOF MOUNTED EXHAUST FAN TO REMAIN.
2. REMOVE EXISTING EXHAUST FAN SHOWN IN HEAVY DASHED LINE ON PLANS. PATCH AND SEAL EXISTING ROOF OPENINGS.
3. EXISTING ROOFTOP EQUIPMENT SHALL BE RE-USED. FIELD VERIFY THE EQUIPMENT, INCLUDING ALL ACCESSORIES, IS IN GOOD WORKING CONDITION. REPORT ANY DEFICIENCIES TO THE OWNER. PROVIDE NEW FILTERS AT CONSTRUCTION. NEW FILTERS SHALL BE COMPATIBLE WITH THE EXISTING EQUIPMENT AND EQUAL IN PERFORMANCE TO THE EXISTING FILTERS AT NEW CONDITION UNLESS OTHERWISE NOTED.

NOTE:
EXISTING CONDITIONS WERE TAKEN FROM ORIGINAL DRAWINGS & SITE VISITS AND MAY NOT REFLECT EXACT "AS-BUILT" CONDITIONS. FIELD VERIFY ALL EXISTING CONDITIONS PRIOR TO SUBMITTING FINAL BIDS. CAREFULLY COORDINATE NEW WORK AND DEMOLITION WITH ALL OTHER DISCIPLINES AND EXISTING CONDITIONS.

CALLISONRTKL
A DESIGN CONSULTANCY OF ARCADIS

Callison RTKL, Inc
1420 Fifth Ave., Suite 2400
Seattle, WA 98101
Tel: 206 623 4646

Callison RTKL Project No: 003-180034.00

Consultant
HENDERSON ENGINEERS
Henderson Engineers, Inc.
9900 Lenexa Drive, Suite 300
Lenexa, KS 66219
Tel: 913 742 5000

Consultant
GMS
GMS Engineers
29 West 27th Street, 5th Floor
New York, NY 10001
Tel: 212 254 0030

BOWLERO - AUGUSTA

ISSUE FOR PERMIT / BID

Client/Owner/Project Address

Bowlmor | AMF
Client Address
222 W 44th Street
New York, NY 10036

Project Address
3067 Washington Rd
Augusta, GA 30907

Issue Drawing Log

	2018.05.29	ISSUE FOR PERMIT
	2018.05.29	ISSUE FOR BID

Seal

THIS DOCUMENT IS RELEASED FOR THE PURPOSE OF PRELIMINARY SUBMITTAL
LICENSE # PE034924

IT IS NOT TO BE USED FOR CONSTRUCTION PURPOSES

Sheet Identification

MECHANICAL DEMO ROOF PLAN

M-011

ANDREW S. KNIGHT

Order Plans @ WWW.LDILine.com