

LIGHTING PLAN GENERAL NOTES

- REFER TO SHEET E-000 FOR ADDITIONAL GENERAL NOTES.
- REFER TO ARCHITECT'S LIGHT FIXTURE PACKAGE FOR LIGHT FIXTURE INFORMATION. LIGHT FIXTURE SCHEDULE SHOWN ON SHEET E-200 IS FOR REFERENCE ONLY.
- REFER TO ARCHITECTURAL SHEETS FOR LIGHT FIXTURES INSTALLED IN M.I. WORK. REFER TO ELECTRICAL POWER PLANS FOR HARD WIRING CONNECTIONS.
- EMERGENCY EGRESS LIGHTING WITHIN THE TENANT SPACE HAS BEEN CALCULATED BY THE DESIGN PROFESSIONAL TO MEET 1.0 FOOT-CANDLE AVERAGE, 0.1 FOOT-CANDLE MINIMUM AND A 40:1 MAXIMUM RATIO ALONG THE ARCHITECT'S PATH OF EGRESS.
- PROVIDE NEUTRAL CONDUCTOR TO EACH WALL SWITCH LOCATION IF NEUTRAL TERMINATION IS NOT REQUIRED. OCP CONDUCTOR AND TAG AS NEUTRAL FOR FUTURE USE.
- LOW VOLTAGE SPECIFICATIONS AND LOCATIONS SHOWN ON THIS SHEET WERE PROVIDED TO HENDERSON ENGINEERS, INC. (HEI) BY OWNERS LIGHTING DESIGNER. HESCOPE OF WORK FOR THE LIGHTING SYSTEM IS STRICTLY LIMITED TO CIRCUITING AND CONTROL DESIGN. THE ENGINEER SEAL AND SIGNATURE ON THIS SHEET APPLIES ONLY TO HESCOPE OF WORK.

LIGHT FIXTURE TAG LEGEND


L#	=	LIGHT FIXTURE TYPE
PNL #.#.#	=	PANELBOARD AND CIRCUIT NUMBER
RFP#.#.#	=	RELAY PANEL AND RELAY NUMBER

OWNER'S LIGHTING DESIGNER HAS RESPONSIBILITY FOR THE LIGHTING DESIGN MEETS MINIMUM LEVELS. DESIGNER'S LIGHTING DESIGN DOES NOT GUARANTEE THE SCHEMATIC DESIGN AND CONSUMER IS RESPONSIBLE FOR LIGHTING FIXTURE LOCATION AND COORDINATION.

COORDINATE LOCATION, MOUNTING HEIGHTS AND FINISHES WITH ARCHITECTURAL PLANS. RESOLVE ALL CONFLICTS PRIOR TO RUSH IN.

ELECTRICAL PLAN NOTES

- ALL EXISTING LIGHT FIXTURES, CONTROLS, AND CIRCUITING IN ROOM AND DESIGNATED EXF ARE EXISTING TO REMAIN. FIELD VERIFY EXISTING CIRCUITS AND MAINTAIN CONTINUITY THROUGHOUT PROJECT.
- RELAY PANEL (RFP#), REFER TO SHEETS E-200 FOR REQUIREMENTS, SCHEDULES, AND ADDITIONAL INFORMATION.
- FAN WITH LIGHT KIT: THE TAG ASSOCIATED WITH THE LIGHT FIXTURE TYPE 'L' INDICATES CIRCUITING AND CONTROL REQUIREMENTS FOR THE LIGHT. THE TAG WITHOUT A LIGHT FIXTURE TYPE INDICATES CIRCUITING AND CONTROLS FOR THE FAN MOTOR.
- THE TAG ASSOCIATED WITH 'Y' FIXTURES ARRANGED IN AN 'X' FORMATION SHALL BE TYPICAL OF ALL (4) FIXTURES WITHIN THE 'X' FORMATION.
- LOCATION OF NEW MASTER LIGHTING CONTROL SWITCHES AND SALES FLOOR DIMMING SWITCHES REFER TO LIGHTING CONTROL SCHEDULES AND SWITCHBANK DETAIL ON SHEET E-200 FOR ADDITIONAL INFORMATION.
- CEILING MOUNTED OCCUPANCY SENSOR AND POWER PACK FOR AUTOMATIC CONTROL OF LIGHT FIXTURES IN THIS SPACE. REFER TO LIGHTING CONTROL SCHEDULES AND DETAILS ON SHEET E-200 FOR ADDITIONAL INFORMATION.



① LIGHTING RCP
1/8" = 1'-0"

16

Order Plans @ WWW.LDILLINE.COM

BOWLERO - AUGUSTA

ISSUE FOR PERMIT / BID

Client/Owner/Project Address

Bowlero | AMP
Client Address:
222 WATER STREET
New York, NY 10008



Issue Drawing Log

DATE	ISSUE FOR PERMIT
2018 05 29	ISSUE FOR PERMIT

Seal

THIS DOCUMENT IS RELEASED FOR THE PROJECT ONLY. IT IS NOT TO BE USED FOR CONSTRUCTION PURPOSES.

Sheet Identification
LIGHTING RCP

E-100

NOTE: EXISTING CONDITIONS WERE TAKEN FROM ORIGINAL DRAWINGS & SITE VISITS AND MAY NOT REFLECT EXACT "AS-BUILT" CONDITIONS. FIELD VERIFY ALL EXISTING CONDITIONS PRIOR TO SUBMITTING FINAL BIDS. CAREFULLY COORDINATE NEW WORK AND DEMOLITION WITH ALL OTHER DISCIPLINES AND EXISTING CONDITIONS.