




Order Plans @


WWW.LDLINE.COM

REVISIONS/ISSUANCES		
NO.	DATE	DESCRIPTION









Manley Spangler Smith Architects
A Professional Corporation

505 East Taylor St.
P.O. Box 590
Gwin, Georgia 30224
Office 770.227.5473
Fax 770.228.3442

PROJECT:
RENOVATIONS, MODIFICATIONS, & ADDITIONS TO HENRY COUNTY SCHOOLS - GROUP 10 WOODLAND HIGH SCHOOL (ITEM C)
CLIENT:
HENRY COUNTY BOARD OF EDUCATION

SHEET TITLE:
SITE GRADING AND DRAINAGE PLAN

1:1 - 85
F.T.E. - 1982
FACILITY CODE - 0408

© 2018 Manley Spangler Smith Architects, PC
PROJECT NUMBER: 201731C
DATE: 08/07/18
SCALE: 1"=20'
DRAWN BY: AGM/MAR/AMH
CHECKED BY: DLC
SHEET NO.: C4.1

- CONSTRUCTION NOTES:**
- CONTRACTOR SHALL VERIFY LOCATIONS AND DEPTHS OF ALL EXISTING UTILITIES PRIOR TO BEGINNING EXCAVATION (1-800-282-7461).
 - ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH HENRY COUNTY SPECIFICATIONS AND REQUIREMENTS.
 - MAXIMUM CUT AND FILL SLOPES ARE 3:1 UNLESS SHOWN OTHERWISE.
 - NOTIFY COUNTY INSPECTOR 48 HOURS PRIOR TO BEGINNING CONSTRUCTION.
 - TEMPORARY SEDIMENT STORAGE AREAS TO BE CONSTRUCTED AND FULLY OPERATIONAL PRIOR TO ANY OTHER CONSTRUCTION OR GRADING. REFER TO EROSION AND SEDIMENT CONTROL PLAN.
 - CONTRACTOR SHALL BE RESPONSIBLE FOR FINISH GRADING OF ALL AREAS INDICATED BY PROPOSED SPOTS AND PROPOSED GRADES.
 - CONTRACTOR SHALL LOCATE PIPE AND DETERMINE INVERT PRIOR TO STARTING STORM SEWER INSTALLATION. NOTIFY ARCHITECT & ENGINEER IF INVERT VARIES FROM PLANNED INVERT ELEVATIONS.