

ROOM FINISH SCHEDULE										
ROOM	ROOM NAME	FLOOR MATERIAL	FLOOR COLOR	BASE MATERIAL	BASE COLOR	WALL MATERIAL	WALL COLOR	CEILING MATERIAL	CEILING COLOR	REMARKS
101	EXIST. OFFICE	CARPET TILE	CPT-2	RUBBER BASE	B-1	PAINT	PT-2	EXISTING TO REMAIN		
102	EXIST. MECH.	EXISTING TO REMAIN				PAINT	PT-2	EXISTING TO REMAIN		
103	EXIST. OFFICE	CARPET TILE	CPT-2	RUBBER BASE	B-1	PAINT	PT-2	EXISTING TO REMAIN		
104	EXIST. OFFICE	CARPET TILE	CPT-2	RUBBER BASE	B-1	PAINT	PT-2	EXISTING TO REMAIN		
105	EXIST. LOBBY	EXISTING TO REMAIN				PAINT	PT-2	EXISTING TO REMAIN		
106	EXIST. CONFERENCE	CARPET TILE	CPT-2	RUBBER BASE	B-1	PAINT	PT-2	EXISTING TO REMAIN		
107	EXIST. OFFICE	CARPET TILE	CPT-2	RUBBER BASE	B-1	PAINT	PT-2	EXISTING TO REMAIN		
108	EXIST. STOR.	EXISTING TO REMAIN				PAINT	PT-2	EXISTING TO REMAIN		
109	EXIST. BREAK ROOM	EXISTING TO REMAIN				PAINT	PT-2	EXISTING TO REMAIN		
111	EXIST. WOMEN'S	EXISTING TO REMAIN				PAINT	PT-2	EXISTING TO REMAIN		
112	EXIST. VEST.	EXISTING TO REMAIN				PAINT	PT-2	EXISTING TO REMAIN		
113	EXIST. MEN'S	EXISTING TO REMAIN				PAINT	PT-2	EXISTING TO REMAIN		
114	EXISTING	EXISTING TO REMAIN				PAINT	PT-2	EXISTING TO REMAIN		
115	EXIST. MECH.	EXISTING TO REMAIN				PAINT	PT-2	EXISTING TO REMAIN		
116	EXIST. LAB	CARPET TILE	CPT-1	RUBBER BASE	B-1	PAINT	PT-2/PT-3	EXISTING TO REMAIN		SEE WALL FINISH PLAN FOR ACCENT WALL LOCATION
117	EXIST. LAB	CARPET TILE	CPT-1	RUBBER BASE	B-1	PAINT	PT-2/PT-3	EXISTING TO REMAIN		SEE WALL FINISH PLAN FOR ACCENT WALL LOCATION
118	EXIST. CLASSROOM	CARPET TILE	CPT-1	RUBBER BASE	B-1	PAINT	PT-2	EXISTING TO REMAIN		
119	EXIST. ELEC.	EXISTING TO REMAIN				PAINT	PT-2	EXISTING TO REMAIN		
120	EXIST. CLASSROOM	CARPET TILE	CPT-1	RUBBER BASE	B-1	PAINT	PT-2/PT-3	EXISTING TO REMAIN		SEE WALL FINISH PLAN FOR ACCENT WALL LOCATION
121	EXIST. CLASSROOM	CARPET TILE	CPT-1	RUBBER BASE	B-1	PAINT	PT-2/PT-3	EXISTING TO REMAIN		SEE WALL FINISH PLAN FOR ACCENT WALL LOCATION
122	EXIST. HANGAR SPACE	REPAINT EXISTING EPOXY FLOOR	SC-1			PAINT	PT-2	EXISTING TO REMAIN		
201	EXIST. OFFICE	CARPET TILE	CPT-2	RUBBER BASE	B-1	PAINT	PT-2	EXISTING TO REMAIN		
202	CORRIDOR	CARPET TILE	CPT-1	RUBBER BASE	B-1	PAINT	PT-2	ACOUSTIC CEILING TILE	ACT-1	
203	CLASSROOM	CARPET TILE	CPT-1	RUBBER BASE	B-1	PAINT	PT-2/PT-3	ACOUSTIC CEILING TILE	ACT-1	SEE WALL FINISH PLAN FOR ACCENT WALL LOCATION
204	CLASSROOM	CARPET TILE	CPT-1	RUBBER BASE	B-1	PAINT	PT-2/PT-3	ACOUSTIC CEILING TILE	ACT-1	SEE WALL FINISH PLAN FOR ACCENT WALL LOCATION
205	CLASSROOM	CARPET TILE	CPT-1	RUBBER BASE	B-1	PAINT	PT-2/PT-3	ACOUSTIC CEILING TILE	ACT-1	SEE WALL FINISH PLAN FOR ACCENT WALL LOCATION
206	CLASSROOM	CARPET TILE	CPT-1	RUBBER BASE	B-1	PAINT	PT-2/PT-3	ACOUSTIC CEILING TILE	ACT-1	SEE WALL FINISH PLAN FOR ACCENT WALL LOCATION
207	LAB	CARPET TILE	CPT-1	RUBBER BASE	B-1	PAINT	PT-2/PT-3	ACOUSTIC CEILING TILE	ACT-1	SEE WALL FINISH PLAN FOR ACCENT WALL LOCATION
208	ELEC.	SEALED CONCRETE				PAINT	PT-2			
211	STAIRS	SEALED CONCRETE				PAINT	PT-2			
212	STAIRS	SEALED CONCRETE				PAINT	PT-2			
213	CLOSET	CARPET TILE	CPT-1	RUBBER BASE	B-1	PAINT	PT-2	ACOUSTIC CEILING TILE	ACT-1	

CARPET

CPT-1: MANUFG: INTERFACE
COLLECTION: PALINDROME & ALLITERATION
PATTERN: ALLITERATION
NUMBER: 1391202500
COLOR: #9720 STORM/RED
SIZE: 20' X 20' MODULAR CARPET TILE (50CM X 50CM)
WEIGHT: 24 OZ./YD.
PILE DENSITY: 8,640.
PILE: TUFTED SHEARED TEXTURED PATTERNED LOOP
BACKING: GLASBAC® TILE BACKING SYSTEM
INSTALL: BRICK
ADHESIVE: TACTILES® INSTALLATION SYSTEM
DETAILS: 100% SOLUTION DYED 100% RECYCLED CONTENT TYPE 6 NYLON WITH PROTEKT® SOIL AND STAIN PROTECTION AND INTERCEPT® PRESERVATIVE FOR MOLD PROTECTION 73% TOTAL RECYCLED CONTENT, GREEN LABEL PLUS #GLP0820 LESS THAN 3.0 KV RATING BRICK INSTALLATION
INSTALL: INSTALL APPROPRIATE BLACK VINYL ADAPTER TRANSITION STRIPS AT ALL DOORS WHERE CARPET MEETS EXISTING PORCELAIN TILE. VCT, PAINTED CONCRETE OR OTHER FINISH CLASSROOMS, LABS - SEE INTERIOR FINISH SCHEDULE AND FINISH PLAN FOR DETAILS AND EXACT LOCATIONS
LOCATION: OFFICES - SEE INTERIOR FINISH SCHEDULE AND FINISH PLANS FOR DETAILS AND EXACT LOCATIONS

CPT-2: MANUFG: INTERFACE
COLLECTION: PALINDROME AND ALLITERATION
PATTERN: PALINDROME
NUMBER: 1391202500
COLOR: #102539 STORM
SIZE: 20' X 20' MODULAR CARPET TILE (50CM X 50CM)
WEIGHT: 24 OZ.
PILE DENSITY: 8,640.
PILE: TUFTED SHEARED TEXTURED PATTERNED LOOP
BACKING: GLASBAC® TILE BACKING SYSTEM
INSTALL: BRICK INSTALLATION.
NOTE: INSTALL APPROPRIATE BLACK VINYL ADAPTER TRANSITION STRIPS AT ALL DOORS WHERE CARPET MEETS EXISTING PORCELAIN TILE. VCT, PAINTED CONCRETE OR OTHER FINISH TACTILES® INSTALLATION SYSTEM
ADHESIVE: 100% SOLUTION DYED 100% RECYCLED CONTENT TYPE 6 NYLON WITH PROTEKT® SOIL AND STAIN PROTECTION AND INTERCEPT® PRESERVATIVE FOR MOLD PROTECTION 73% TOTAL RECYCLED CONTENT, GREEN LABEL PLUS #GLP0820, LESS THAN 3.0 KV RATING
LOCATION: OFFICES - SEE INTERIOR FINISH SCHEDULE AND FINISH PLANS FOR DETAILS AND EXACT LOCATIONS

RESOURCE CONTACT:
INTERFACE
CONTACT: ROODY JONES
PHONE: (404) 398-8287

TRIM

TRM-1: MANUFG: ROPPE
STYLE: VINYL ADAPTER/TRANSITION
NUMBER: #177
SIZE: 1/8" TO 1/4"
FINISH: #100 BLACK
INSTALL: VCT TO CARPET TILE TRANSITION
NOTE: INSTALL APPROPRIATE BLACK VINYL ADAPTER TRANSITION STRIPS AT ALL DOORS WHERE CARPET MEETS EXISTING TILE. VCT, PAINTED CONCRETE OR OTHER FINISH
LOCATION: SEE INTERIOR FINISH SCHEDULE FOR DETAILS AND EXACT LOCATIONS

SPECIALTY COATING

SC-1: MANUFG: PLEXI-CHEMIE, INC.
PRODUCT: PLEXI CREST UL-600 FURNITURE URETHANE
NOTE: FOLLOW MANUFACTURER'S INSTRUCTIONS
SERIES: PLEXICREST
COLOR: DUNK GREEN, SMOKE GRAY, CHARCOAL & SAFETY YELLOW STRIPING
FINISH: POLYURETHANE POLYURETHANE COATING SYSTEM
INSTALL: GLOSS PER MANUFACTURERS INSTRUCTIONS
LOCATION: DOORS ONLY - MATCH EXISTING STRIPING / PATTERN
SEE INTERIOR FINISH SCHEDULE AND FINISH PLAN FOR DETAILS AND EXACT LOCATIONS

RESOURCE CONTACT:
PLEXI-CHEMIE, INC.
CONTACT: PAT SICILIA
PHONE: (706) 297-2907

WALL BASE

B-1: MANUFG: ROPPE
TYPE: PINK/CLC, 4" TYPE TS VULCANIZED RUBBER STANDARD COVE BASE
NUMBER: TS-123
COLOR: #174 SMOKE
PROFILE: STANDARD COVE
SIZE: 4" H X 1/8" THICKNESS
LOCATION: ALL BASE FOR CARPETED AND VCT AREAS UNLESS OTHERWISE NOTED
SEE INTERIOR FINISH SCHEDULE FOR EXACT LOCATIONS

RESOURCE CONTACT:
WILLIAM M BIRD CO.
CONTACT: MICHELE MUSGROVE
PHONE: (404) 640-0241

WALLS

PAINT FINISHES

PT-1: MANUFG: BENJAMIN MOORE
PRODUCT: ULTRA SPEC 500 FLAT INTERIOR LATEX PAINT
SERIES: ULTRA SPEC 500
COLOR: OC-151 WHITE
FINISH: FLAT
LOCATION: ALL GYPSUM BOARD CEILINGS, SOFFITS
NOTE: INSTALL 2 COATS PER MANUFACTURER'S INSTRUCTIONS

PT-2: MANUFG: BENJAMIN MOORE
PRODUCT: ULTRA SPEC 500 LOW SHEEN #537 INTERIOR LATEX
NOTE: INSTALL 2 COATS PER MANUFACTURER'S INSTRUCTIONS
SERIES: ULTRA SPEC 500
COLOR: AC-HARBOR GRAY
FINISH: LOW SHEEN
LOCATION: ALL WALLS UNLESS OTHERWISE NOTED
NOTE: PRIME ALL NEW WALLS WITH ULTRA SPEC 500 - PRIMER #534. TEST EXISTING CMU WALLS TO MAKE SURE THEY ARE PAINTED WITH LATEX PAINT
SEE INTERIOR FINISH SCHEDULE FOR EXACT LOCATIONS

PT-3: MANUFG: BENJAMIN MOORE
PRODUCT: ULTRA SPEC 500 LOW SHEEN #537 INTERIOR LATEX
NOTE: INSTALL 2 COATS PER MANUFACTURER'S INSTRUCTIONS
SERIES: ULTRA SPEC 500
COLOR: 2127 PIKE'S PEAK GRAY
FINISH: LOW SHEEN
LOCATION: ACCENT WALLS AS NOTED
NOTE: PRIME ALL NEW WALLS WITH ULTRA SPEC 500 - PRIMER #534. TEST EXISTING CMU WALLS TO MAKE SURE THEY ARE PAINTED WITH LATEX PAINT
SEE INTERIOR FINISH SCHEDULE FOR EXACT LOCATIONS

PT-4: MANUFG: BENJAMIN MOORE
PRODUCT: ULTRA SPEC HP D.T.M. ACRYLIC SEMI-GLOSS #HP29
SERIES: ULTRA SPEC
COLOR: AC-26 OZARK SHADOWS
FINISH: SEMI-GLOSS
LOCATION: ALL METAL DOORS, DOOR FRAMES, STAIRS, STAIR HANDRAILS
NOTE: TEST EXISTING METAL DOORS, FRAMES AND HANDRAILS TO MAKE SURE THEY ARE PAINTED WITH LATEX PAINT
PRIME ALL EXISTING AND NEW INTERIOR METAL DOORS, DOOR FRAMES, STAIRS AND HANDRAILS WITH ULTRA SPEC HP ACRYLIC METAL PRIMER #HP04 SEE INTERIOR FINISH SCHEDULE FOR EXACT LOCATIONS

RESOURCE CONTACT:
BENJAMIN MOORE
CONTACT: SHAWNE TOWNSLEY
PHONE: (214) 862-6156

FINISH MATERIAL ABBREVIATIONS

ACT ACOUSTICAL CEILING TILE
B RUBBER BASE
CPT CARPET MODULAR
EXP EXPOSED
GWB GYPSUM WALL BOARD
PT PAINT
TRM VINYL ADAPTER TRANSITION
SC SPECIALTY COATING

ACOUSTICAL CEILING TILE

ACT-1: MANUFG: USG CORPORATION
SERIES: MARS CLIMA PLUS
NUMBER: B-895
TEXTURE: NON-DIRECTIONAL PATTERN
TYPE: NON-MOLD MILDEN
PROFILE: 2" X 2" X 3/4"
GRID: 24" X 24" X 3/4"
COLOR: WHITE
NOTE: DOWN CENTRICITEE ACOUSTICAL SUSPENSION SYSTEM
DXT/DXLT T BAR GRID, 9/16"
FLAT WHITE
LOCATION: WITH SEISMIC CLIPS ASSEMBLY
ALL CEILINGS UNLESS OTHERWISE NOTED
SEE INTERIOR FINISH SCHEDULE, AND RCP FOR DETAILS AND EXACT LOCATIONS

RESOURCE CONTACT:
USG
CONTACT: PACE PICKEL
PHONE: (678) 942-1212

GENERAL FINISH NOTES:


- REFER TO INTERIOR FINISH SPECIFICATIONS FOR SUBMITTAL AND/OR MOCK UP GUIDELINES AND REQUIREMENTS.
- CONTACT COR FOR DIRECTION IN THE EVENT OF CONTRADICTION INFORMATION BETWEEN DRAWINGS, LEGEND AND/OR SPECIFICATIONS.
- REFER TO FINISH SCHEDULE AND FINISH PLANS FOR GENERAL FINISHES. REFER TO ALL INTERIOR FINISH NOTES AND INTERIOR DRAWINGS (INCLUDING PLANS, ELEVATIONS AND DETAILS) FOR ADDITIONAL INTERIOR INFORMATION.
- IF COLOR OR FINISH IS NOT SPECIFIED, CONTACT COR FOR DIRECTION.
- SUBMIT FOUR SAMPLES FOR APPROVAL PER MATERIAL SPECIFIED IN PLAN. SAMPLES TO MATCH THE FINISH LEGEND DESIGNATION. INCLUDE PRODUCT DATA SHEETS, SEAMING DIAGRAMS AND SHOP DRAWINGS PRIOR TO FABRICATION.
- PROVIDE REPRESENTATIVE SAMPLES FROM ALL DYE LOTS REQUIRED TO COMPLETE INSTALLATION. PROVIDE MINIMUM ONE BOX FOR ATTIC STOCK ON ALL TILE PRODUCTS OF EACH SIZE, STYLE AND COLOR.
- PROVIDE A SUBMITTAL SCHEDULE DEMONSTRATING LEAD TIME MILESTONES FOR ITEMS TO PREVENT NEED FOR SUBSTITUTIONS.
- PROVIDE SHOP DRAWINGS FOR TILE LAYOUT APPROVAL PRIOR TO INSTALLATION.
- CLEAN JOB SITE REMOVING SCRAPS, DEBRIS AND WASTE MATERIALS DAILY.
- PROVIDE BLOCKING AS REQUIRED IN ALL WALLS TO RECEIVE WALL HUNG EQUIPMENT. ITEMS FURNITURE, FLIP DOWN CHARTING, LARGE MARKER AND TACK BOARDS.
- ALL NEW FURNITURE IS COR FURNISHED AND COR INSTALLED U.N.O. DIFFUSERS IN COLORED WALLS, CEILINGS AND SOFFITS TO BE PAINTED THE COLOR OF ADJACENT SURFACE.
- SURFACES TO RECEIVE NEW FINISHES SHALL BE CLEAN, TRUE AND FREE OF IRREGULARITIES. WORK SHALL NOT PROCEED UNTIL UNSATISFACTORY CONDITIONS HAVE BEEN CORRECTED. STARTING OF WORK SHALL INDICATE INSTALLER'S ACCEPTANCE OF SUBSTRATE.
- PROVIDE A SMOOTH, LEVEL 4 DRYWALL FINISH ON ALL GYPSUM BOARD CEILINGS AND SOFFITS, U.N.O.
- ALL DRYWALL OR EXPOSED STRUCTURE CEILINGS ARE TO BE PAINTED FLAT SHEEN U.N.O.
- ALL INTERIOR FRAMES, BOTH NEW AND EXISTING WITHIN PROJECT SCOPE SHALL BE PAINTED COLOR OF ADJACENT WALL, SEMI-GLOSS SHEEN U.N.O.
- PAINT ALL EXPOSED SURFACES INCLUDING GRILLES, ETC. DO NOT PAINT FACTORY FINISHED ITEMS (I.E. EXTRUDED ALUMINUM FRAMES OR STOREFRONTS).
- PROVIDE MINIMUM THREE-COAT PAINT SYSTEM FOR EACH SUBSTRATE U.N.O.
- THE GENERAL CONTRACTOR IS RESPONSIBLE FOR USING TEMPORARY FLOOR PROTECTION THROUGHOUT THE PROJECT TO SAFEGUARD THE SURFACE QUALITY OF CONCRETE SLABS THAT WILL BE EXPOSED AS FINAL FLOOR FINISH.
- CLEAN JOB SITE REMOVING SCRAPS, DEBRIS AND WASTE MATERIALS DAILY.
- PATCH AND PREP ALL EXISTING WALLS TO REMAIN. CONFIRM EQUIPMENT MOUNTING HEIGHTS AND BLOCKING REQUIREMENTS WITH COR PRIOR TO RE-INSTALLATION.
- ANY ITEM DEMOLISHED OR DAMAGED BY DEMOLITION AND NOT SPECIFIED FOR DEMOLITION SHALL BE REPLACED WITH AN EQUAL ITEM AS APPROVED BY COR AT NO COST TO COR.
- PROTECT ALL EXISTING FLOOR, WALL, DOOR AND CEILING FINISHES AND/OR FIXTURES TO REMAIN. REPAIR ANY DAMAGE AS A RESULT OF DEMOLITION OR CONSTRUCTION.
- CONTRACTOR IS RESPONSIBLE FOR MOVING ALL EXISTING FURNITURE TO ACCOMMODATE SCOPE OF WORK. CONTRACTOR IS RESPONSIBLE FOR STORING ANY FURNITURE NOT USED DURING CONSTRUCTION. ONCE WORK IS COMPLETED, CONTRACTOR MUST PUT FURNITURE BACK IN RESPECTIVE SPACES IN SAME ARRANGEMENT AS IT WAS BEFORE IT WAS MOVED.
- DOBBINS IS RESPONSIBLE FOR MOVING AND REPLACING COMPUTER WORKSTATIONS, PRINTERS, AND PERSONAL EFFECTS TO ACCOMMODATE SCOPE OF WORK.

CONSTRUCTION DOCS.


REV.	DATE	DESCRIPTION
A	2017-11-03	10% CONCEPT DESIGN
B	2017-12-22	65% SUBMITTAL
C	2018-02-23	95% SUBMITTAL
D	2018-04-13	FOR CONSTRUCTION
E	2018-06-01	FOR CONSTRUCTION



CIVIL ENGINEERING
94th AIRLIFT WING
DOBBINS AIR RESERVE BASE, GEORGIA



CROFT & ASSOCIATES
3400 Blue Springs Road,
Suite 200
Kennesaw, GA 30144
770.529.7144 (o)
770.529.7168 (f)
www.croftga.com



REPAIR FACILITY & ADDITION
BUILDING 747
FGWB 08-0027
DOBBINS AIR RESERVE BASE, GEORGIA
ROOM FINISH SCHEDULE & FINISH MATERIAL
SECS
PROJECT CONTRACT:
ROBIELENS1@us.af.mil

PROJECT	LOCATION	DRAWING	CONTACT
PROJECT No:	2017-238		
PROJ. OFFICER:	J. MORGAN		
DESIGNED:	M. GUNN		
CHECKED:	J. MORGAN		
DATE:	2018-06-01		
DRAWING	28	OF	45

IF001