

STRUCTURAL NOTES

(REFER TO PROJECT MANUAL FOR ADDITIONAL INFORMATION)

1. FOOTINGS & FOUNDATION EXCAVATION:

- A. A GEOTECHNICAL ANALYSIS HAS BEEN PERFORMED ON THIS SITE. SEE PROJECT MANUAL FOR GEOTECHNICAL INFORMATION. APPROPRIATE RECOMMENDATIONS STATED IN THE GEOTECHNICAL REPORT ISSUED BY TERRACON CONSULTANTS, INC DATED JANUARY 17, 2018 SHALL BE FOLLOWED.
- B. THESE FOUNDATIONS HAVE BEEN DESIGNED FOR A SOIL BEARING OF 2000 PSF FOR CONTINUOUS AND ISOLATED FOOTINGS.
- C. FOUNDATIONS AND SLAB SHOULD BEAR ON PROPERLY PLACED AND COMPACTED ENGINEERED FILL OR STIFF OR BETTER NATIVE SOILS. SEE GEOTECHNICAL REPORT FOR SPECIFIC REQUIREMENTS REGARDING EXCAVATION AND PREPARATION OF SUBGRADE. A GEOTECHNICAL ENGINEER SHOULD BE PRESENT TO DIRECT THE REMOVAL OF UNSUITABLE SOILS AND TO DETERMINE THE ADEQUACY OF THE BEARING SURFACE PRIOR TO PLACEMENT OF THE REINFORCEMENT AND CONCRETE.
- D. FOOTING WIDTHS TO BE AS SHOWN ON PLANS AND DETAILS. BOTTOM OF FOOTING IS TO BE EXCAVATED SQUARE AND TRUE.
- E. WHERE ANY OPEN TRENCH HAS BEEN EXPOSED TO RAIN, SNOW OR ICE PRIOR TO POURING CONCRETE, ALL REINFORCING IN THAT TRENCH SHALL BE REMOVED AND THE BOTTOM OF THE TRENCH SHALL BE DRAINED OF ALL WATER AND CLEANED OF MUD, SNOW OR ICE. A GEOTECHNICAL ENGINEER OR HIS TECHNICAL REPRESENTATIVE SHALL INSPECT THE BOTTOM OF THE TRENCH AND OBSERVE THE RE-COMPACTING OF SOILS PRIOR TO PLACING REINFORCEMENT AND POURING OF CONCRETE.
- F. ALL STRIP FOOTINGS SHALL BE CENTERED UNDER WALLS BEING SUPPORTED AND ALL ISOLATED FOOTINGS SHALL BE CENTERED UNDER COLUMNS, UNLESS NOTED OTHERWISE.
- G. MINIMUM EXTERIOR FOOTING DEPTH SHALL BE AS INDICATED ON THE FOUNDATION PLAN SHEET S2.
- H. IN THE EVENT THAT ORGANIC SOIL OR UNCOMPACTED FILL IS FOUND BELOW FOOTINGS OR FLOOR SLABS, IT SHALL BE REMOVED AND REPLACED WITH SELECT FILL, PLACED AND COMPACTED AS DESCRIBED IN THE GEOTECHNICAL REPORT.
- I. STRUCTURAL FILL SHOULD BE PLACED AND COMPACTED AS INDICATED IN THE GEOTECHNICAL REPORT. ADEQUATE DENSITY AND MOISTURE CONTENT TESTS SHOULD BE PERFORMED TO INSURE COMPLIANCE WITH PROJECT SPECIFICATIONS. SUBGRADE INSPECTION AND FILL TESTING UNDER CONTROLLED CONDITIONS IS CONSIDERED ESSENTIAL IF THE FOOTINGS ARE TO BE FOUND IN FILL. A TESTING FREQUENCY OF AT LEAST ONE FIELD DENSITY TEST FOR EACH 2500 SQUARE FEET OF LIFT, BUT NOT LESS THAN 3 TESTS PER LIFT IS RECOMMENDED WITHIN THE BUILDING AREAS.

2. CONCRETE:

- A. ALL READY MIX CONCRETE SHALL BE 4000 PSI FOR ALL CONCRETE PLACEMENT. DO NOT ADD WATER TO THE MIX DESIGN AFTER DELIVERY TO THE PROJECT SITE.
- B. EXPOSED EXTERIOR CONCRETE SHALL BE AIR-ENTRAINED (TOTAL AIR CONTENT = 5%). INTERIOR CONCRETE SHALL NOT BE AIR-ENTRAINED.
- C. UNLESS NOTED OTHERWISE, CONCRETE COVER OVER STEEL REINFORCEMENT SHALL CONFORM TO THE MINIMUM REQUIREMENTS OF ACI 318. REINFORCEMENT DETAILING AND PLACEMENT SHALL CONFORM TO ACI 318 AND ACI 315, EXCEPT WHERE OTHERS' REQUIREMENTS ARE SHOWN.
- D. HOT OR COLD WEATHER CONCRETING SHALL BE IN ACCORDANCE WITH ACI 305-89 AND ACI 306-1-90, RESPECTIVELY.
- E. ANY CONCRETE PLACED BY MEANS OF PUMPING SHALL BE DONE IN ACCORDANCE WITH ACI 304.2R (82).
- F. CEMENT SHALL CONFORM TO A.S.T.M. C-150 TYPE I.
- G. AGGREGATES SHALL CONFORM TO A.S.T.M. C-33 FOR NORMAL WEIGHT CONCRETE & A.S.T.M. C-330 FOR LIGHTWEIGHT CONCRETE.
- H. READY MIX CONCRETE SHALL BE MIXED AND DELIVERED IN ACCORDANCE WITH A.S.T.M. C-94.
- I. ADMIXTURES MAY BE USED WITH THE APPROVAL OF THE STRUCTURAL ENGINEER. ADMIXTURES THAT IMPAIR DURABILITY OR THE CONCRETE SHALL NOT BE CONSIDERED TO REDUCE THE CEMENT CONTENT. HOLDING TIME CHLORIDES SHALL BE LIMITED.

3. SLABS ON GRADE:

- A. FLOOR SLABS ARE TO BE PLACED AND FINISHED IN ACCORDANCE WITH ACI 302.1R (92) PROJECT MANUAL FOR ADDITIONAL INFORMATION.
- B. THICKNESS TOLERANCE FOR ALL SLABS IS TO BE PER ACI 117 AND IS TO BE NO MORE THAN +3/8" (THICKER) AND NO MORE THAN -1/4" (THINNER) FROM THE DESIGN THICKNESS.
- C. CONCRETE USED FOR FLOOR SLABS SHALL INCLUDE SUPERPLASTICIZER. SEE PROJECT MANUAL FOR ADDITIONAL INFORMATION.

4. REINFORCING:

- A. REINFORCING BARS SHALL BE BILLET STEEL, ASTM A 601, GRADE 60. PROVIDE CONTINUOUS BENT BARS AT FOOTING STEPS AND 90 DEGREE BENT TIES AT CORNERS. UNLESS OTHERWISE NOTED, LAP SPLICES OR EMBEDMENT LENGTHS SHALL CONFORM TO CLASS B SPLICE (SEE SPLICE TABLE). ADJACENT BAR SPLICES IN WALLS AND FOOTINGS TO BE ALTERNATED. FOOTINGS SHALL REQUIRED HOOKED REINFORCING PROJECTED INTO WALLS. PLASTERS OR COLUMNS WHERE THE SIZE AND SPACING OF JOINTS ARE TO MATCH VERTICAL REINFORCING.
- B. WELDED WIRE FABRIC (WFF) SHALL CONFORM TO THE CURRENT AISC SPECIFICATION FOR COLD DRAWN STEEL REINFORCEMENT WIRE. LAP END AND EDGES MINIMUM 6".
- C. REINFORCING DETAILING, BENDING, AND PLACING SHALL CONFORM TO ACI 318.
- D. MINIMUM CONCRETE COVER: THE MINIMUM CLEAR DISTANCES BETWEEN REINFORCING STEEL AND FACE OF CONCRETE SHALL BE MAINTAINED UNLESS NOTED OTHERWISE.

5. LUMBER:

- A. TREATED LUMBER: IN AREAS WHERE TREATED LUMBER IS SHOWN ON DRAWINGS, THE APPROVED PRESSURE TREATED WOODS ARE C-D(CARBONATE) OR C-D(TREATED WOODS WITHOUT AMMONIA CARRIERS). THE CHEMICAL RETENTION LEVELS ARE TO BE NO GREATER THAN 0.4 PCF FOR C-D-2, 0.21 PCF FOR CA-B. ALL METAL CONNECTORS ARE TO HAVE A GALVANIZED COATING OF NO LESS THAN 1.85 OUNCES OF ZINC PER SQUARE FOOT PER ASTM A653. ALL BOLTS, SCREWS NAILS AND OTHER FASTENERS ARE TO BE GALVANIZED PER ASTM A153. WHERE TREATED LUMBER IS SHOWN IN EXTERIOR INSTALLATIONS WITH NO ROOF COVERINGS TO PREVENT EXPOSURE TO RAIN, USE HOT DIP GALVANIZED CONNECTORS PER ASTM A123.

6. STRUCTURAL STEEL:

- A. FABRICATOR QUALIFICATIONS: FABRICATOR MUST PARTICIPATE IN THE AISC QUALITY CONTROL PROGRAM AND BE DESIGNATED AN AISC-CERTIFIED PLANT.
- B. MATERIALS:
 - STRUCTURAL STEEL ASTM A992, GRADE 50 UNLESS NOTED
 - PLATES, ANGLES, CHANNELS, AND MISCELLANEOUS STEEL ASTM A36
 - ANCHOR RODS ASTM F1554, GRADE 36
 - HIGH STRENGTH BOLTS ASTM A325 (3/4") UNLESS NOTED (OF NORTH AMERICAN MANUFACTURE)
 - WELDING ELECTRODES AWS A5.1 (E70XX)
 - PIPE ASTM A53, GRADE B
 - SQUARE AND RECTANGULAR HOLLOW STRUCTURAL SECTIONS (HSS) ASTM A500, GRADE B

7. LIGHT GAUGE STEEL: SHALL CONFORM TO AISC (LATEST EDITION) AND THE FOLLOWING:

- A. ALL LIGHT GAUGE METAL STUDS, JOISTS AND HEADERS ARE TO MEET OR EXCEED INDUSTRY STANDARDS AS SET FORTH BY THE STEEL STUDS MANUFACTURER'S ASSOCIATION (SSMA).
- B. LIGHT GAUGE STEEL MEMBER DESIGNATIONS SHOWN ON THE CONSTRUCTION DOCUMENTS ARE SSMA STANDARD DESIGNATIONS.
- C. ALL LIGHT GAUGE STEEL WALLS SHALL BE Laterally BRIDGED AT 48" O.C. (VERTICALLY) USING 2"x20ga STRAP BRACING ATTACHED TO EACH STUD FLANGE. SOLID BLOCKING WITHIN THE PLANE OF THE STRAP BRACING MUST BE PROVIDED AT EACH END OF WALL, ADJACENT TO WALL OPENINGS, AND AT 8' O.C. MAXIMUM. ALL BRIDGING AND BRACING IS TO BE POSITIVELY CONNECTED TO STUDS.
- D. MINIMUM TRACK GAUGE TO MEET OR EXCEED GAUGE OF SUPPORTED STUDS.
- E. BOTTOM TRACK FASTENERS TO BE SPACED AT EACH END OF WALL, ADJACENT TO WALL OPENINGS, AND AT 48" O.C. MAXIMUM.
- F. POWDER ACTUATED FASTENERS SHALL BE OS HEAVY DUTY 0.1779x1/2" LONG MANUFACTURED FROM MODIFIED AISI 1051 STEEL. AUSTEMPERED TO A HARDNESS OF 52-56 HRC AND ZINC PLATED IN ACCORDANCE WITH ASTM B633.S01, TYPE II. FASTENERS SHALL BE INSTALLED BY A QUALIFIED OPERATOR IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS. POWDER ACTUATED FASTENERS SHALL BE AS MANUFACTURED BY "MULTI FASTENING SYSTEMS" OR EQUIVALENT.
- G. ALL LOAD BEARING STUDS TO BE SEATED SQUARELY INTO TOP AND BOTTOM WALL TRACKS WITH NO MORE THAN A 1/8" GAP.
- H. THE DESIGN OF SLIP TRACKS SHALL CONFORM TO THE GUIDELINES ESTABLISHED IN SSMA TECHNICAL NOTE NO. 1 PUBLISHED JANUARY, 2001.

8. GENERAL:

- A. CONTRACTOR HAS SOLE RESPONSIBILITY TO COMPLY WITH ALL OSHA REGULATIONS.
- B. THE STRUCTURAL DESIGN OF THE BUILDING IS BASED UPON THE FULL INTERACTION OF ALL ITS COMPONENT PARTS, WITH NO PROVISION MADE FOR CONDITIONS OCCURRING DURING CONSTRUCTION. THE STRUCTURE IS STABLE ONLY IN ITS COMPLETED FORM. THE CONTRACTOR SHALL PROVIDE ADEQUATE BRACING DURING CONSTRUCTION. TEMPORARY SUPPORTS REQUIRED FOR STABILITY DURING ALL INTERMEDIATE STAGES OF CONSTRUCTION SHALL BE DESIGNED, FURNISHED AND INSTALLED BY THE CONTRACTOR. THE CONTRACTOR IS RESPONSIBLE FOR CONSTRUCTIBILITY ANALYSIS AND ERECTION PROCEDURES, INCLUDING DESIGN AND ERECTION OF FALSEWORK, TEMPORARY BRACING, ETC. THE STRUCTURAL ENGINEER ASSUMES NO LIABILITY FOR THE STRUCTURE DURING CONSTRUCTION.
- C. CORRECTIONS DUE TO UNFORESEEN FIELD CONDITIONS OR DIMENSIONAL DISCREPANCIES ON CONSTRUCTION DOCUMENTS MUST BE BROUGHT TO THE ATTENTION OF THE PROJECT ARCHITECT FOR REVIEW AND AUTHORIZATION PRIOR TO CORRECTIVE MEASURES BEING IMPLEMENTED.
- D. STRUCTURAL DRAWINGS ARE TO BE USED IN CONJUNCTION WITH ARCHITECTURAL, MECHANICAL, AND ELECTRICAL DRAWINGS.
- E. NOTES AND DETAILS TAKE PRECEDENCE OVER THESE GENERAL NOTES.
- F. ALL SHOP DRAWINGS SHALL BE REVIEWED AND APPROVED BY THE PROJECT ARCHITECT/ENGINEER PRIOR TO SUBMITTING TO THE BUILDING DEPARTMENT FOR REVIEW AND APPROVAL.

9. SIMPSON "AT-XP" ADHESIVE SYSTEM INTO CONCRETE (APMO LIES ER-283):

- A. CONTRACTOR TO FOLLOW ALL REQUIREMENTS, INSTRUCTIONS, AND RECOMMENDATIONS FOR ADHESIVE APPLICATION.
- B. SUBSTITUTIONS FOR SIMPSON "AT-XP" ANCHORING ADHESIVE SHALL BE ONLY UPON THE APPROVAL OF THE PROJECT ENGINEER OF RECORD.

10. SPECIAL INSPECTIONS REQUIREMENTS:

- A. OWNER SHALL ENGAGE ONE OR MORE QUALIFIED SPECIAL INSPECTORS AND/OR TESTING AGENCIES TO CONDUCT STRUCTURAL TESTS, CONSTRUCTION MATERIAL TESTING, AND SPECIAL INSPECTIONS SPECIFIED IN THE "STATEMENT OF SPECIAL INSPECTIONS".
- B. FOR THE SPECIFIC RESPONSIBILITY OF THE OWNER, CONTRACTOR, AND SPECIAL INSPECTOR REFER TO SECTION 01 45 16 OF THE PROJECT MANUAL.

DESIGN CRITERIA

BUILDING CODE: 2012 INTERNATIONAL BUILDING CODE

DESIGN LOADS:

- ROOF DEAD LOAD.....5.0 psf
- ROOF COLLATERAL LOAD.....2.5 psf
- ADDITIONAL CEILING SYSTEM COLLATERAL AT PARTS AREA "A".....2.0 psf
- ROOF LIVE LOAD.....20.0 psf
- SPRINKLER LOADS
- UNIFORM BRANCH PIPE LOAD.....0.0 psf
- LINEAL LOOP/TEE MAIN PIPE LOAD.....0.0

SNOW LOAD:

- P_g = 10 psf
- P_f = 12 psf
- C_e = 1.0
- C_t = 1.0
- I_s = 1.0

WIND CALCULATION METHOD: ENVELOPE

- V_{ult} = 115 mph V_{base} = 39.1 mph
- EXPOSURE = "C"
- RISK CATEGORY =
- BUILDING COEFFICIENT C_d = ±0.1

MAIN FLOOR RESISTING SYSTEM:

- WALL AND ROOF 14.7 psf
- PARAPETS 18.4 psf

WIND COMPONENTS & CLADDING: All Wind Pressures & Forces in "ASD"

(Wind Pressures tabulated based by JS Smith Consulting Engineers, P.C. for design. Components designed by others for use in this project will require wind pressures derived by that designer.)

- WALL AREAS 10 SQUARE FEET OR LESS = 21.1 psf
- WALL INTERIOR ZONES = 12.9 psf & -14.5 psf
- WALL END ZONES = 12.9 psf & -15.1 psf
- PARAPETS AT INTERIOR ZONES = 11.6 psf & -18.5 psf
- PARAPETS AT END ZONES = 11.6 psf & -20.9 psf
- ROOF INTERIOR ZONES = 5.6 psf & -15.8 psf
- ROOF EDGE ZONES = 5.6 psf & -18.8 psf
- ROOF CORNER ZONES = 5.6 psf & -18.8 psf

BASE SHEAR:

- V_w WIND = 20.2 k
- SEISMIC = 14.7 k
- V_w WIND = 18.5 k
- SEISMIC = 14.7 k

SEISMIC DESIGN: EQUIVALENT FORCE PROCEDURE

- S_s = 0.248
- S_i = 0.119
- S_{ps} = 0.265
- S_{ps} = 0.184
- SITE CLASS = D
- SEISMIC DESIGN CATEGORY = C
- I_e = 1.0


SEISMIC FORCE RESISTING SYSTEM:

- STEEL NOT DETAILED FOR SEISMIC
- R = 3.00
- C_s = 0.088
- R_o = 3.00
- C_t = 3.00
- p = 1.00

SPLICE TABLE¹
(UNLESS NOTED OTHERWISE)

BAR SIZE	LAP SPLICES (in.) ²		EMBED LENGTH (in.)		
	TOP BARS ³ Class B	OTHERS Class B	TOP BARS ³ ld	OTHERS ld	HOOKS ⁵ ldh
#3	25	19	19	15	8
#4	33	25	25	19	10
#5	41	31	31	24	12
#6	49	37	37	29	15
#7	71	54	54	42	17

- 1. SPLICE TABLE IS BASED ON THE FOLLOWING:
 - A. CONCRETE f_c = 4000 psi
 - B. GRADE 60 REBAR
 - C. BAR SPACING NOT LESS THAN 2 BAR DIAMETERS OR 1"
 - D. CONCRETE COVER NOT LESS THAN ONE BAR DIAMETER
- 2. LAP LENGTHS SHOWN ARE FOR CLASS "B" TENSION SPLICES PER ACI 318-11 CHAPTER 12.
- 3. TOP BARS ARE DEFINED AS HORIZONTAL REINFORCEMENT PLACED SO THAT MORE THAN 12" OF CONCRETE IS CAST BELOW THE REINFORCEMENT IN THAT MEMBER.
- 4. STANDARD 90° HOOKS:
 - A. RADIUS = 4 BAR DIAMETERS FOR #3 THRU #6
 - RADIUS = 5 BAR DIAMETERS FOR #9 THRU #11
 - B. LENGTH = 12 BAR DIAMETERS
- 5. HOOK LENGTH MAY BE REDUCED IN ACCORDANCE WITH ACI 318-11 CHAPTER 12.5



CRAIG A. SCHNEIDER, AIA
 ARCHITECT
 1736 East Sunshine, Suite 417
 Springfield, Missouri 65804
 417.862.0556
 Fax: 417.862.3265
 e-mail: architect@esterlyschneider.com

PROJECT: NEW O'REILLY AUTO PARTS STORE
 PRICEVILLE, AL
 HWY 67
 STRUCTURAL NOTES

O'Reilly AUTO PARTS
 CORPORATE OFFICES
 1000 N. WASHINGTON
 SPRINGFIELD, MISSOURI 65802
 (417) 862-2674 TELEPHONE

COMM #	4160
DATE:	4-6-18
REVISION	
DATE:	

JS Smith Consulting Engineers
 Alabama State Certificate of Authorization CA-2283-E
 Aaron D. Smith P.E. 24301
 P.O. Box 8102 * JOPLIN, MISSOURI 64802
 PHONE: 417-624-0444 * FAX: 417-624-0430

Order Plans @



WWW

APR 14 2018
 ARCHITECTURE
 1736 EAST SUNSHINE ST. SUITE 417
 SPRINGFIELD, MISSOURI 65804