



GENERAL NOTES:  
FOR PARAPET DIMENSION & DETAILS SEE A400 & A401

- KEYNOTES:
- 1 AT UPPER ROOF MIN INSULATION THICKNESS SHALL BE 2" AT THE LOCATIONS SHOWN AS 0". THICKNESS SHALL BE OBTAINED WITH A MIN OF 2 LAYERS RIGID INSULATION TO BE MECHANICALLY ATTACHED.
  - 2 AT LOWER ROOF THIS AREA ONLY ELEVATION OF ROOF. NOTE MIN THICKNESS OF INSULATION IS 5"(R-20) AT 0" ELEVATION.
  - 3 PARAPET WITH PRECAST CONCRETE COPING.
  - 4 ROOF DRAIN SEE PLUMBING.
  - 5 OVERFLOW DRAIN SEE PLUMBING.
  - 6 BOILER FLUE SEE MECHANICAL.
  - 7 FUTURE FLUE WITH CAP ROOF PENETRATION.
  - 8 INTENSIFIER VENT SEE MECHANICAL.
  - 9 BENTHOUSE RELIEF HOOD SEE MECHANICAL.
  - 10 FOUR 1/2" VENTS FROM NATURAL GAS TRAIN.
  - 11 24"x24"x2" PRECAST SPLASH BLOCK.
  - 12 ROOF ACCESS HATCH.
  - 13 HVAC FRESH AIR UNIT, SEE MECHANICAL.
  - 14 EXHAUST FAN SEE MECHANICAL.
  - 15 4" UNIT HEATER FLUE.
  - 16 8" VENT.
  - 17 DEAERATOR SAFETY VENT.
  - 18 2" CONDENSATE RETURN UNIT VENT.
  - 19 BOILER SAFETY VENT.
  - 20 4" CANT STRIP.
  - 21 TREATED WOOD NAILER, DEPTH AS REQD.
  - 22 EPDM CAP SHEET.
  - 23 EPDM BASE SHEET.
  - 24 EPDM FLASHING STRIP.
  - 25 POLYISOCYENURATE BOARD, DEPTH VARIES W/ SLOPE.
  - 26 ROOF DRAIN UNIT SEE MECHANICAL.
  - 27 EPDM COMPATIBLE SEALANT.
  - 28 TERMINATION BAR CONTINUOUS ANCHORS @ 24" O.C.
  - 29 PRECAST COPING.
  - 30 NOMINAL 8" CMU PARAPET.
  - 31 8" BLOWDOWN SEPARATOR VENT W/ EXH. HEAD.
  - 32 3" VENT (HOT).
  - 33 CONTINUOUS POURED U BLOCK - SEE STRUCTURAL.

A three inches = one foot  
 B one and one half inches = one foot  
 C one inch = one foot  
 D three quarters inch = one foot  
 E one half inch = one foot  
 F three eighths inch = one foot  
 G one quarter inch = one foot  
 H one eighth inch = one foot

Order Plans @ WWW.A101DILINE.COM

FINAL DESIGN  
APPROVED FOR CONSTRUCTION

CONSULTANTS:		ARCHITECT-OF-RECORD THOMAS R. GHELLERSON ARCHITECT/ENGINEERS: <b>AKEA INC.</b> 3803 NW 95th Street, Suite B Gainesville, FL 32606 Phone: (352) 474-6124 Fax: (352) 553-4437 OJA: FL #26693 AKEA Project No. 083-14		Drawing Title <b>ROOF PLAN AND DETAILS</b>		Project Title <b>REPLACE BOILERS - FCA D. ENERGY AT THE MALCOM RANDALL VAMC</b>		Project Number <b>573-14-600</b>		Office of Construction and Facilities Management	
Approved: Project Director		Location <b>GAINESVILLE, FLORIDA</b>		Building Number		Drawing Number <b>A102</b>		Date <b>MARCH 9, 2016</b>		Department of Veterans Affairs	
Revisions:		ARCHITECT/ENGINEERS: THOMAS R. GHELLERSON ARCHITECT/ENGINEERS: <b>AKEA INC.</b> 3803 NW 95th Street, Suite B Gainesville, FL 32606 Phone: (352) 474-6124 Fax: (352) 553-4437 OJA: FL #26693 AKEA Project No. 083-14		Checked <b>THG</b>		Drawn <b>JG</b>		29 OF 127		VA FORM 08-6231	