

DEMOLITION NOTES

- 1. THE CONTRACTOR SHALL NOT CONSIDER DEMOLITION AND ALTERATION NOTES TO BE ALL-INCLUSIVE... 2. REMOVE ALL EXISTING CONSTRUCTIONS AND FINISHES NECESSARY FOR THE COMPLETION OF THE WORK... 3. THE CONTRACTOR SHALL VERIFY ALL CONDITIONS AND DIMENSIONS WITHIN THE CONTRACT LIMITS... 4. ALL REMOVALS AND SALVAGE, UNLESS SPECIFICALLY NOTED OR REQUESTED BY THE VA MEDICAL CENTER... 5. ANY FLOOR OPENINGS SHALL BE PROTECTED AND SECURED DURING DEMOLITION AND CONSTRUCTION... 6. ANY EXTERIOR WALL OPENINGS SHALL BE CLOSED IMMEDIATELY OR BE PROVIDED WITH TEMPORARY WEATHER AND SECURITY PROTECTION... 7. PATCH ALL FINISHES TO MATCH EXISTING... 8. MAINTAIN ACCESS TO EXITS AND EXIT STAIRS AT ALL TIMES... 9. ALL DEMOLITION SHALL BE PERFORMED IN A SAFE AND ACCEPTABLE MANNER... 10. ALL WORK SHALL BE DONE IN PROTECTED SPACE... 11. PROVIDE TEMPORARY PARTITIONS/DUST PROTECTION... 12. IF HAZARDOUS MATERIAL IS ENCOUNTERED... 13. ITEMS INDICATED AS TO-BE-DEMOLISHED...

ELECTRICAL NOTES

- APPLICABLE TO ALL ELECTRICAL SHEETS: 1. ALL WORK SHALL COMPLY WITH NEC, NFPA, AND ALL APPLICABLE FEDERAL CODES. 2. ALL RECEPTACLES SHALL HAVE THE NEMA 5-20R CONFIGURATION... 3. ALL BRANCH CIRCUITS SHALL BE RUN WITH DEDICATED NEUTRALS... 4. IT IS ANTICIPATED THAT ANY CRITICAL WORK (SHUTDOWNS, HOLDUPS, ETC.) AFFECTING OTHER AREAS... 5. IT IS ANTICIPATED THIS PROJECT WILL INVOLVE WORK ON OR VERY NEAR LIVE CIRCUITS... 6. PRIOR TO FINAL INSPECTION, PROVIDE NEW PANEL SCHEDULES... 7. ALL CONDUITS SHALL BE CLEAN AND FREE OF DEBRIS... 8. CONDUCTORS FROM DIFFERENT VOLTAGE SYSTEMS... 9. IN ACCORDANCE WITH NEC 300.7, PROVIDE DUCT SEAL MATERIAL... 10. WORK SHALL BE PLANNED SUCH THAT THERE IS NO CLIMBING OR STANDING... 11. ANY WORK ABOVE OR AT THE TOP OF EQUIPMENT... 12. TO CONSERVE USEABLE WALL SPACE, JUNCTION AND PULL BOXES... 13. PROVISIONS IN ACCORDANCE WITH THE SPECIFICATIONS... 14. PRIOR TO FINAL INSPECTION, PROVIDE LABELS FOR ALL NEW EQUIPMENT... 15. RACEWAY ROUTING DEPICTED ON PLANS IS PROPOSED ROUTING... 16. CONTRACTOR SHALL PROVIDE COORDINATION STUDY... 17. A PORTION OF THIS PROJECT MAY REQUIRE THE CONTRACTOR... 18. UNLESS NOTED OTHERWISE, 20A ELECTRICAL DEVICES... 19. THE CONTRACTOR SHALL NOT OPERATE ANY EXISTING EQUIPMENT... 20. IF OBSTRUCTIONS ARE ENCOUNTERED... 21. PRINTED DIMENSIONS SHALL TAKE PRECEDENCE... 22. CONFLICTS IN AND CONFLICTS BETWEEN THE VARIOUS ELEMENTS... 23. THE CONTRACTOR SHALL BECOME FAMILIAR WITH ALL PORTIONS... 24. UNDERGROUND BENDS, TURNUPS, NIPPLES THROUGH CONCRETE...

SYMBOLS

SYMBOLS table with columns for LIGHTING, POWER, and SYSTEMS. Includes symbols for 2' x 4' light fixture, transformer, disconnect switch, motor, duplex receptacle, etc.

ABBREVIATIONS

Table of abbreviations including AFC (Available Fault Current), BRK (Breaker), CFL (Compact Fluorescent Lamp), etc.

INVESTIGATIVE SERVICES

THIS PROJECT REQUIRES NEW PENETRATIONS THROUGH EXISTING CONCRETE FLOORS. PRIOR TO LAYOUT AND INSTALLATION OF NEW CONDUIT REQUIRING NEW PENETRATIONS OF EXISTING CONCRETE FLOOR SLABS...

DEDUCTIVE ALTERNATES

THIS PROJECT INCLUDES MULTIPLE DEDUCTIVE ALTERNATES. CONTRACTOR SHALL REFER TO SPEC SECTION 01 00 00 FOR DETAILED DESCRIPTIONS. IN SUMMARY: BASE BID - ALL WORK SHOWN. DEDUCT ALTERNATE #1 - DEDUCT NOTED ARCHITECTURAL COMPONENTS...

FINAL DESIGN APPROVED FOR CONSTRUCTION

Vertical scale on the left side of the page with markings from 0 to 72 inches.

Order Plans

CONSULTANTS:

Table for listing consultants with columns for Name, Title, and Date.

ARCHITECT/ENGINEERS:

Logo and contact information for AKEA INC., 3803 NW 98th Street, Suite B, Gainesville, FL 32606.

Drawing Title

ELECTRICAL LEGEND, ABBREVIATIONS, AND NOTES

Project Title

REPLACE BOILERS - FCA D, ENERGY AT THE MALCOM RANDALL VAMC

Project Number

573-14-600

Building Number

Building Number

Drawing Number

E001

101 OF 127

Office of Construction and Facilities Management

