



FIXTURE SCHEDULE NOTES:

1. ALL LIGHTING FIXTURES AND LAMPS SHALL BE SUPPLIED & INSTALLED BY GENERAL CONTRACTOR. FIXTURES AVAILABLE AT SPECIALTY LIGHTING (CONTACT INFO: MIKE BODIGIANO (866) 787-0110 EXT. 227. NO EXCEPTIONS.
2. NOT USED.
3. COVER PLATES ON ALL OUTLETS TO MATCH COLOR OF WALL.
4. CONTRACTOR SHALL INSTALL OWNER SUPPLIED COVERS & TRIM ACCESSORIES TO ALL NEW AND EXISTING TRACKS HEADS.
5. NOT USED.
6. CONTRACTOR SHALL REPLACE ALL RECESSED DOWN LIGHT FIXTURES.
7. ALL HANGING FIXTURES SHALL BE PROVIDED WITH SUFFICIENT CHAIN LENGTH TO ACCOMMODATE REQUIRED MOUNTING HEIGHTS.
8. ALL HANGING FIXTURES AT CEILING SHALL BE INSTALLED WITH DECORATIVE COVER PLATES. FIXTURES SHALL BE INSTALLED IN PANGACE BOXES, NOT HANG FROM TRACK STRIPS.
9. ALL NEW TRACK LIGHT LAMPS SHALL BE SPOTS AND RODS IN ANY FIXTURES.
10. CONTRACTOR SHALL DIRECT WALL WASHER LIGHT FIXTURES IN FRONT OF THE WINE CABINET TO THE WINE DISPLAY SECTION OF THE CABINET.
11. CONTRACTOR SHALL ADJUST TRACK HEADS TO ILLUMINATE THE CENTER OF TABLES AND DECOR PIECES.
12. CONTRACTOR SHALL COUNT EXISTING TRACK HEADS THE FIRST DAY OF WORK AND SHALL VERIFY IF THE RESTAURANT HAS ENOUGH FIXTURES TO COMPLETE THE PROJECT. FOLLOWING THE REFLECTED CEILING PLAN TO DETERMINE IF ADDITIONAL FIXTURES ARE NEEDED. CONTACT GARDEN PROJECT MANAGER IF NEW FIXTURES ARE REQUIRED.
13. ALL PENDANT AND CHANDELLER FIXTURES ABOVE TABLE TOPS SHALL BE CENTERED ON THE TABLE.
14. ALL PENDANT LIGHT FIXTURES AND CHANDELLERS SHALL BE CONNECTED TO THE DIMMER SYSTEM.

TRACK LIGHT FIXTURE NOTES:

EXISTING TRACK LIGHT FIXTURE TO REMAIN. IF RESTAURANT PRESENTLY HAS "LIGHTS UP" TRACK HEADS AND TRACKS, ALL NEW TRACK HEADS TO SUPPLEMENT EXISTING LIGHTCOVER FIXTURES WILL BE JUNG. THE TRACK HEAD WILL BE LIGHTER. AN ADAPTER WILL BE PROVIDED TO CONNECT THE TRACK HEAD AND THE TRACK. FIXTURES SHOULD BE CONSOLIDATED BY BRAND TO DIFFERENT AREAS IF POSSIBLE TO MINIMIZE ANY CONFLICT IN LOOK BETWEEN THE TWO. FIXTURES SHALL HAVE BLACK FINISH IN DARK CEILING AND WHITE FINISH IN WHITE CEILING.

IF RESTAURANT HAS "CAPRI" TRACK HEADS AND TRACKS, ALL NEW TRACK HEADS AND TRACKS TO SUPPLEMENT EXISTING CAPRI FIXTURES WILL BE JUNG. THE CAPRI (COORDINATE AT PRE-BID MEETING) MAY OPT TO RELOCATE STILL FUNCTIONING CAPRI FIXTURES TO A PORTION OF THE RESTAURANT. FIXTURES SHOULD BE CONSOLIDATED BY BRAND TO DIFFERENT AREAS IF POSSIBLE TO MINIMIZE ANY CONFLICT IN LOOK BETWEEN THE TWO. FIXTURES SHALL HAVE BLACK FINISH IN DARK CEILING AND WHITE FINISH IN WHITE CEILING.

COORDINATE WITH OWNER REPOSITIONING OF HEADS. EACH TABLE SHALL BE ILLUMINATED BY ONE HEAD. OTHER HEADS TO BE DIRECTED TO ILLUMINATE DECOR & PATH OF TRAVEL.

- CEILING PLAN NOTES:**
- 1.4 NOT USED.
 - 1.3 NOT USED.
 - 1.2 EXISTING SPLIT OR HEADER TO BE PAINTED P-1.
 - 1.1 REPLACE EXISTING ACoustICAL CEILING TILES. USE ITEM (20). EXISTING CEILING GRID & CROWN MOLDING IF EXISTING TO BE PAINTED TO MATCH TILE COLOR. REFER TO FINISH SCHEDULE SHEET A-1. ALL ACoustICAL CEILING GRILLES AND EMERGENCY LIGHT HOUSINGS SHALL BE PAINTED TO MATCH CEILING TILE COLOR.
 - 1.1a EXISTING GYP. BOARD CEILING AND CROWN MOLDING (IF EXISTING) TO BE PAINTED P-1. REFER TO FINISH SCHEDULE SHEET A-1. REPLACE MONOCHROMS TO BLACK COLORE. MATCH EXISTING ROOM DRAIN ROOMS. ALL A/C DIFFUSERS & RETURN GRILLES SHALL BE PAINTED P-1. REPLACE ALL DOWN LIGHT FIXTURES (IF APPLICABLE).
 - 1.17 NOT USED.
 - 1.18 EXISTING EXCESSIVE SPACERS SHALL BE PAINTED TO MATCH THE COLOR OF THE ADJACENT ACoustICAL CEILING TILES OR GYP. BOARD CEILING.
 - 1.22 EXISTING A/C GRILLE TO BE PAINTED TO MATCH EXISTING ACoustICAL CEILING TILES.
 - 1.23 EXISTING SPLIT TO REMAIN.
 - 1.24 NOT USED.
 - 1.25 NOT USED.
 - 1.26 EXISTING WOOD CEILING JOIST SYSTEM. REFER TO DETAILS 1 & 2/ A.B.3.
 - 1.27 NOT USED.
 - 1.28 NOT USED.
 - 1.29 PROVIDE ADDITIONAL CEILING GRID IN ORDER TO OBTAIN A 2'x2' GRID SYSTEM.
 - 1.30 AFTER REMOVAL OF WALL BELOW, PROVIDE HEADER BOTTOM TO MATCH ADJACENT HEADERS. SECURED TO STRUCTURE ABOVE. PROVIDE 1/2" GYP. BOARD AND PLASTER FINISH TO MATCH EXISTING FINISH. COORDINATE WITH OWNER.
 - 1.31 REWORK PORTION OF EXISTING ACoustICAL CEILING AS REQUIRED TO ALLOW FOR NEW HEADER OR SOFFIT.
 - 1.32 NOT USED.
 - 1.33 NOT USED.
 - 1.34 REMOVE VAULTED SOFFIT AS REQUIRED. REPAIR DAMAGED AREAS. MATCH EXISTING FINISHES. PROVIDE ACoustICAL CEILING TILES AND GRID EXTENSION FROM ADJACENT CEILING AREAS.
 - 1.35 EXISTING ACoustICAL CEILING TILES AND GRID TO REMAIN. REPLACE ANY DAMAGED CEILING TILES. COORDINATE WITH OWNER.
 - 1.36 REMOVE LOWER PORTION OF HEADERS. SECTION OF NEW HEADERS AT 4" O.C. PROVIDE FRAMING AS REQUIRED WITH 1/2" GYP. BOARD AND PLASTER FINISH TO MATCH EXISTING. ALL SURFACES SHALL BE PAINTED P-1.
 - 1.37 NOT USED.
 - 1.38 NOT USED.
 - 1.39 NOT USED.
 - 1.40 NOT USED.
 - 1.41 AFTER REMOVAL OF WALL BELOW, PROVIDE HEADER BOTTOM AT 2" O.C. SECTION OF NEW HEADERS AT 4" O.C. PROVIDE FRAMING AS REQUIRED WITH 1/2" GYP. BOARD AND PLASTER FINISH TO MATCH EXISTING FINISHES. COORDINATE WITH OWNER.
 - 1.42 INSTALL OWNER PROVIDED LATTICE / PENDANT / PORT UNIT. REFER TO A.B.3.
 - 1.43 NOT USED.
 - 1.44 INSTALL OWNER PROVIDED MESH CURTAIN. NO EXIST. HEADER, CONTAINING ALL WIRING (IF APPLICABLE). COORDINATE WITH OWNER. REPAIR DAMAGED AREAS. MATCH EXISTING FINISHES.
 - 1.45 PROVIDE 2x4 WOOD MEMBER BETWEEN EXISTING 2x4 WOOD MEMBER TO SUPPORT STANDING AREA.
 - 1.46 NOT USED.
 - 1.47 EXISTING TRACKING CEILING TILES & GRID TO BE PAINTED P-1. ALL A/C DIFFUSERS & RETURN GRILLES SHALL BE PAINTED TO MATCH CEILING TILE COLOR. REFER TO FINISH SCHEDULE SHEET A-1.
 - 1.48 NOT USED.
 - 1.49 PROVIDE NEW WOOD JOIST SYSTEM AT 19" O.C. MATCH EXISTING HEADERS. USE 2x4 WOOD STUDS AT 19" O.C. SECURED TO STRUCTURE ABOVE. PROVIDE 1/2" GYP. BOARD AND PLASTER FINISH TO MATCH EXISTING.
 - 1.50 EXISTING OVERHEAD LIGHTING TO BE REMOVED. PROVIDE NEW 1/2" GYP. BOARD SOFFIT FINISHED P-1. REFER TO A.B.3.
 - 1.51 EXISTING LIGHT FIXTURE TO BE REMOVED AS REQUIRED. CONNECTION TO PATCH & REPAIR EXISTING GYP. BOARD CEILING (IF NECESSARY).
 - 1.52 CONTRACTOR SHALL PROVIDE ELECTRICAL AND COMM. CABLE CONNECTIONS FOR CABLE BOXES. COORDINATE FINAL LOCATION WITH CONSTRUCTION PROJECT MANAGER.
 - 1.53 CONTRACTOR TO INSTALL OWNER PROVIDED FLATSCREEN TV. PROVIDE ELECTRICAL & COMM. CABLE CONNECTIONS. COORDINATE WITH OWNER.
 - 1.54 CONTRACTOR SHALL PROVIDE CAT 6 CABLE TO RUN FROM THE LOCATION TO MANAGERS OFFICE. COORDINATE WITH OWNER.

GENERAL NOTES:

1. CEILING HEIGHT AT FINISH SURFACE SHALL BE MEASURED TO BOTTOM OF GYP. BD. CEILING HEIGHT AT LATHING SHALL BE MEASURED TO BOTTOM OF FINISHED MATERIAL. FINISH ALL A.C. WALLS AND CEILING GRILLES & SPACERS TO MATCH ADJACENT SURFACE.
2. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE LATEST EDITION OF THE INTERNATIONAL CODE BOOKS AND SPECIFICATIONS. REFER TO THE LATEST EDITION OF THE INTERNATIONAL CODE BOOKS AND SPECIFICATIONS.
3. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING MECHANICAL AND ELECTRICAL TIME WHERE SHOWING. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING MECHANICAL AND ELECTRICAL TIME WHERE SHOWING. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING MECHANICAL AND ELECTRICAL TIME WHERE SHOWING.
4. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING MECHANICAL AND ELECTRICAL TIME WHERE SHOWING. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING MECHANICAL AND ELECTRICAL TIME WHERE SHOWING.
5. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING MECHANICAL AND ELECTRICAL TIME WHERE SHOWING. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING MECHANICAL AND ELECTRICAL TIME WHERE SHOWING.
6. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING MECHANICAL AND ELECTRICAL TIME WHERE SHOWING. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING MECHANICAL AND ELECTRICAL TIME WHERE SHOWING.
7. ALL MATERIAL AND EQUIPMENT SHALL BE PROVIDED BY THE ELECTRICAL CONTRACTOR. ALL WIRING SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE (NEC) AND ALL LOCAL CODES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING MECHANICAL AND ELECTRICAL TIME WHERE SHOWING.
8. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING MECHANICAL AND ELECTRICAL TIME WHERE SHOWING. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING MECHANICAL AND ELECTRICAL TIME WHERE SHOWING.
9. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING MECHANICAL AND ELECTRICAL TIME WHERE SHOWING. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING MECHANICAL AND ELECTRICAL TIME WHERE SHOWING.
10. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING MECHANICAL AND ELECTRICAL TIME WHERE SHOWING. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING MECHANICAL AND ELECTRICAL TIME WHERE SHOWING.
11. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING MECHANICAL AND ELECTRICAL TIME WHERE SHOWING. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING MECHANICAL AND ELECTRICAL TIME WHERE SHOWING.
12. IN ALL PAINTED CEILING AND NEW ACoustICAL CEILING AREAS, THE CONTRACTOR SHALL REMOVE, PAINT AND REINSTALL ALL A/C DIFFUSERS, RETURN GRILLES, AND RETURN GRILLES. CLEAN AND ABLE OF GREASE, GRIME AND OIL, AS WELL AS PROCESS OILS AND CONTAMINANTS. PROVIDE FINISH AND PART FINISH FRAME BARS TO MATCH NEW CEILING PANEL COLOR.
13. ALL BASE BOARD HEADERS AND/OR WALL OF CEILING UNIT HEADERS IF APPLICABLE SHALL BE CLEANED AS REQUIRED.
14. CONTRACTOR SHALL REPAIR ALL SEE A/C WALL DIFFUSERS TO MATCH NEW PAINT OF ADJACENT WALL.
15. FINISH-MOUNTED DOOR CONTACTS TO BE REINSTALLED BY OWNER'S SECURITY SYSTEM VENDOR (ADD).

LIGHTING FIXTURE SCHEDULE

SYMBOL	DESCRIPTION	LAMP QTY. & TYPE	FIXTURE WATTAGE	VOLTS	REMARKS
[Symbol]	PENDANT FIXTURE KICHLER LIGHTING S1842S2 (OLD BRONZE FINISH) SHADE: HONEY OPALESCENT	1CP-2400K (2) LEDT19D0024K	14	120	PENDANT FIXTURE AT DINING ROOM (6'-4" A.F.F.)
[Symbol]	PENDANT FIXTURE KICHLER LIGHTING S1842S2 (OLD BRONZE FINISH) SHADE: HONEY OPALESCENT	1CP-2400K (2) LEDT19D0024K	14	120	PENDANT FIXTURE AT BAR COUNTER TO GO BOTTOM AT 7'-0" A.F.F.
[Symbol]	RECESSED LIGHT FIXTURE CON-TECH TRIM: CHROME SL-E HOUSING: 4R, 20	1CP-LED8P02002726NRL	8	120	NEW BAR SOFFIT LIGHT FIXTURE AND GENERAL-HAT REPLACEMENT
[Symbol]	CHANDELLER FIXTURE KICHLER LIGHTING 2M407 (OLDE BRONZE FINISH) GLASS: CLEAR W/LIGHT UMBER ETCH	(1) 2CP-LED4E2681124K7	96	120	CHANDELLER FIXTURE AT FAMILY ROOM (6'-4" A.F.F.)
[Symbol]	CHANDELLER FIXTURE KICHLER LIGHTING 4251CE (OLDE BRONZE FINISH) GLASS: CLEAR W/LIGHT UMBER ETCH	(8) 3CP-LED4E2681124K7	64	120	CHANDELLER FIXTURE EXISTING FAMILY ROOM TABLE (6'-4" A.F.F.) FIXTURE HAS TO BE MODIFIED - STEMS REMOVED AND CHAINS USED IN PLACE.
[Symbol]	PENDANT FIXTURE KICHLER LIGHTING S18279 (OLDE BRONZE FINISH) SHADE: LIGHT UMBER TRANSLUCENT ORGANZA	(4) BULBRITE NCS2376/3Q/12	100	120	CHANDELLER FIXTURE AT ROUND TABLE (5'-6" A.F.F.)
[Symbol]	PENDANT FIXTURE KICHLER LIGHTING S18214B (OLDE BRONZE FINISH), HONEY OPALESCENT GLASS	1CP-2400K (1) LEDT19D0024K	7	120	PENDANT FIXTURE AT LOUNGE. REFER TO DETAIL 1/ A.B.4
[Symbol]	PENDANT FIXTURE KICHLER LIGHTING 4251CE (OLDE BRONZE FINISH) GLASS: SATIN ETCHED	(1) 1CP-LED4E2681124K7	8	120	PENDANT FIXTURE AT DINING ROOM BOTTOM OF FIXTURE AT 30" FROM TABLE
[Symbol]	PENDANT FIXTURE KICHLER LIGHTING 4251CE (OLDE BRONZE FINISH) GLASS: SATIN ETCHED	(1) BULBRITE NCS40-1910	40	120	PENDANT FIXTURE AT LOBBY OVER HOSTESS STAND. REFER TO DETAIL 10/ A.B.3 AT SIDE DINING AREAS. REFER TO DETAIL 12/ A.B.3
[Symbol]	PENDANT FIXTURE KICHLER LIGHTING 4251CE (OLDE BRONZE FINISH) GLASS: SATIN ETCHED	(1) BULBRITE NCS40-1910	40	120	PENDANT FIXTURE AT LOBBY OVER HOSTESS STAND. REFER TO DETAIL 10/ A.B.3 AT SIDE DINING AREAS. REFER TO DETAIL 12/ A.B.3
[Symbol]	PENDANT FIXTURE KICHLER LIGHTING 4251CE (OLDE BRONZE FINISH) GLASS: SATIN ETCHED	(1) BULBRITE NCS40-1910	40	120	PENDANT FIXTURE AT LOBBY OVER HOSTESS STAND. REFER TO DETAIL 10/ A.B.3 AT SIDE DINING AREAS. REFER TO DETAIL 12/ A.B.3
[Symbol]	WALL SCONCE FIXTURE KICHLER LIGHTING J-HACE (OLDE BRONZE FINISH), CLEAR/SATIN ETCH GLASS	(1) 1CP-LED4E2681124K7	8	120	DECORATIVE WALL SCONCE AT DINING 7 CENTER OF ELECTRICAL BOX AT 6'-4" A.F.F.
[Symbol]	STEP LIGHTING INNOVATIVE LIGHTING COLD LED STRIP MODEL: 24V SD 2700 K LED 888CN	GOLD LED 888CN	1.35 W/FT	24	BACK BAR CABINET FIXTURES ARE PART OF CABINET (OWNER'S VENDOR PROVIDED) AND SHALL BE CONNECTED TO ADJACENT NEW SWITCH BY CONTRACTOR.
[Symbol]	EXISTING PENDANT FIXTURES TO BE REMOVED.		VARIABLES	120	
[Symbol]	EXISTING LIGHT FIXTURE (RELANPED)		75	120	
[Symbol]	EXISTING LIGHT FIXTURE (RELANPED)		75	120	
[Symbol]	RELOCATED DOWNLIGHT	PHILIPS ENDURA LED PAR20 8W/2700K 20" MEDIUM BASE ORDER CODE: 8PAR20/END/P25/2700DAM	8	120	
[Symbol]	EXISTING TRACK LIGHT AND MONO POINT TO REMAIN R = RELOCATED	PHILIPS ENDURA LED PAR20 8W/2700K 20" MEDIUM BASE ORDER CODE: 8PAR20/END/P25/2700DAM	8	120	1+ DIRECTED TO CENTER OF TABLE 2+ DIRECTED TO DECOR ITEM 3+ DIRECTED TO POS
[Symbol]	JUNG TRACK-LITES SPECIALTY SERIES LITES TRACK (BL - BLACK, CR - WHITE) REFER TO CEILING PLAN NOTES	10W INTEGRAL LED	10	120	1+ DIRECTED TO CENTER OF TABLE 2+ DIRECTED TO DECOR ITEM 3+ DIRECTED TO POS
[Symbol]	EXISTING BATTERY PACK EMERGENCY LIGHT TO REMAIN R = RELOCATED			120	
[Symbol]	N = NEW : BEGHELLI MODEL # 2XR31	(2) 7W MR16 (NEW FIXTURE ONLY)		120	NEW FIXTURES SHALL BE PROVIDED AND INSTALLED BY THE GENERAL CONTRACTOR
[Symbol]	EXISTING EMERGENCY SIGN TO REMAIN R = RELOCATED			120	NEW MATCH EXISTING PROVIDED AND INSTALLED BY CONTRACTOR.
[Symbol]	EXISTING WALL MOUNTED EMERGENCY SIGN TO REMAIN R = RELOCATED			120	NEW MATCH EXISTING PROVIDED AND INSTALLED BY CONTRACTOR.
[Symbol]	EXISTING EMERGENCY LIGHT TO REMAIN R = RELOCATED			120	NEW MATCH EXISTING PROVIDED AND INSTALLED BY CONTRACTOR.

CEILING LEGEND

SYMBOL	DESCRIPTION	REMARKS	SYMBOL	DESCRIPTION
[Symbol]	EXISTING SPEAKER TO REMAIN R = RELOCATED N = NEW, PROVIDED AND INSTALLED BY CONTRACTOR	NEW SPEAKERS SHALL BE PAINTED TO MATCH THE COLOR OF THE ADJACENT CEILING. SPECIFICATION: IN-CENTRA 24C MICRO7	[Symbol]	EXISTING RETURN AIR GRILLE TO REMAIN R = RELOCATED
[Symbol]	EXISTING SPEAKER TO BE REMOVED		[Symbol]	EXISTING SPRINKLER HEAD TO REMAIN R = RELOCATED
[Symbol]	EXISTING AIR SUPPLIED & RETURN GRILLES TO REMAIN R = RELOCATED N = NEW, PROVIDED AND INSTALLED BY CONTRACTOR		[Symbol]	N = NEW, PROVIDED AND INSTALLED BY CONTRACTOR

REFLECTED CEILING PLAN 1/4"

Oliver Garden
ARCHITECTS
1711 GALLATIN RD NORTH
MADISON, TN 37117
TEL: 615.261.1177
WWW.OLIVERGARDENARCHITECTS.COM

DATE: 11-10-2017

Issue Date: 04-26-2018

REVISION INFORMATION

1	
2	
3	
4	
5	
6	
7	
8	

Restaurant #: 1173

P1B (HIGH)

1711 GALLATIN RD NORTH

MADISON, TN

Drawing REFLECTED CEILING PLAN A2.1

Order Plans

FOR REVIEW ONLY

THESE DRAWINGS AND SPECIFICATIONS REMAIN THE PROPERTY OF THE DESIGN PROFESSIONAL. AUTHORIZED COPIES OF THESE DRAWINGS AND SPECIFICATIONS MAY BE MADE BY THE CLIENT FOR USE AND FOR OCCUPYING THE PROJECT FOR WHICH THEY WERE PREPARED, AND NOT FOR THE CONSTRUCTION OF ANY OTHER PROJECT. UNAUTHORIZED COPIES OF THESE DRAWINGS ARE STRICTLY PROHIBITED.