



BOHLER ENGINEERING
 CIVIL AND CONSTRUCTION ENGINEERING
 LAND SURVEYING DESIGN PERMITTING SERVICES
 CONSULTATION SERVICES
 NORTHERN VIRGINIA
 PHILADELPHIA
 PHOENIX
 RICHMOND, VA
 TAMPA, FL
 WASHINGTON, DC
 WASHINGTON STATE
 WISCONSIN

REVISIONS

REV	DATE	COMMENT	BY
2	2017-07-11	PER COUNTY SURVING & FOOT COMMENTS	JDP
3	2017-10-13	PER COUNTY COMMENTS	JDP
4	2017-10-27	PER FOOT COMMENTS	JDP
5	2017-11-30	PER COUNTY UTILITY COMMENTS	JDP
6	2018-01-02	PER COUNTY & FOOT COMMENTS	JDP
7	2018-01-25	PER FOOT COMMENTS	JDP
8	2018-02-06	PER FOOT COMMENTS	JDP
9	2018-04-05	HYDRANT PER FIRE MARSHAL	JDP
10	2018-09-07	WAWA BID SET	JDP
11	2018-10-03	PER ROW COMMENTS	SKK

811 KNOW WHAT'S BELOW
 ALWAYS CALL 811
 BEFORE YOU DIG
 It's fast. It's free. It's the law.
www.callsunshine.com

PERMIT SET

PROJECT NO: FLT160078
 DRAWN BY: JDP
 CHECKED BY: KSM
 DATE: 11/03/2016
 SCALE: 1" = 30'
 CAD LID: DDP

WAWA SR 52 & LITTLE RD
 FOR
RMC PROPERTY GROUP
 LOCATION OF SITE
 9021 STATE ROAD 52
 HUDSON, FLORIDA 34689
 PASCO COUNTY

BOHLER ENGINEERING
 3820 NORTDALE BLVD., SUITE 300B
 TAMPA, FLORIDA 33624
 Phone: (813) 812-4100
 Fax: (813) 812-4101
 FLORIDA BUSINESS CERT. OF AUTH. NO. 37919
 LICENSE NO. 48070707-B-00000101-00000000

- DEMOLITION LEGEND**
- (A) EXISTING ASPHALT PAVEMENT TO BE REMOVED. SEE PAVEMENT PLANS FOR LIMITS OF PROPOSED FULL DEPTH PAVEMENT
 - (B) EXISTING CONCRETE PAVEMENT TO BE REMOVED
 - (C) EXISTING SECTION OF CURBS AND GUTTER TO BE REMOVED
 - (D) EXISTING DRAINAGE STRUCTURES TO BE REMOVED AND / OR RELOCATED SEE GRADING AND DRAINAGE PLAN
 - (E) EXISTING BUILDING AND / OR STANDING STRUCTURES TO BE REMOVED
 - (F) EXISTING TREES TO BE REMOVED, TYP.
- TREE LEGEND**
- (Symbol) OAK TREE
 - (Symbol) PALM TREE
 - (Symbol) MAPLE TREE
 - (Symbol) TREE TO BE REMOVED

NOTES:
 REQUIRED EROSION AND SEDIMENT CONTROL DEVICES SHALL BE IN PLACE AT ALL TIMES DURING CONSTRUCTION AND SHALL BE REMOVED ONLY AFTER STABILIZATION HAS BEEN ESTABLISHED.
 SIDEWALKS WILL BE CONSTRUCTED WITHIN THREE (3) DAYS AFTER REMOVAL AND SAFE PEDESTRIAN TRAFFIC WILL BE MAINTAINED AT ALL TIMES. IF SIDEWALK IS REMOVED IT WILL BE REMOVED TO THE NEAREST EXPANSION JOINT AND REPLACED PER FOOT INDEX 310. ANY SIDEWALK WHICH BECOMES UNDERMINED, MUST BE REMOVED AND REPLACED. ROADWAY/SIDEWALK CONNECTIONS REPLACEMENTS MUST MEET CURRENT A.D.A. STANDARDS AND FOOT INDEX 304.

Order Plans @

10/5/2018

SHEET TITLE:
DEMOLITION PLAN

SHEET NUMBER:
C-4.2