DOOR SCHEDULE - LEVEL 000 & LEVEL 100

DOOR NO.	DOOR ELEV.	DOOR WIDTH	DOOR HEIGHT	DOOR THICK.	DOOR MAT.	DOOR FIN.	FRAME ELEV.	FRAME MAT.	FRAME FIN.	DETAILS HEAD	DETAILS JAMB	DETAILS SILL	LABEL	HDWR SET	SIGNAGE TYPE	SIGNAGE TEXT	NOTES	DOOR NO.
LEVEL 000																		
0004.1	A	3'-0"	7'-0"	1-3/4"	HM	P	HM1	HM	P	H21	J21	S1	---	A05	1 & 2A	RM NM ELECTRICAL	1,2	0004.1
0005.1	A	3'-0"	7'-0"	1-3/4"	HM	P	HM1	HM	P	H21	J21	S1	---	A05	1 & 2A	RM NM ELECTRICAL	1,2	0005.1
0310.1	B	PR 4'-0"	7'-0"	1-3/4"	HM	P	HM11	HM	P	H22	J21	S1	---	A07	---	---	1,2	0310.1
0320.1	D	PR 3'-0"	7'-0"	1-3/4"	HM	P	HM10	HM	P	H22	J21	S1	---	A06	---	---	1,2	0320.1
0320.1.1	C	PR 4'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H1	J1	---	B-90	B04	1 & 3	RM NM STAIR J	1,2,4	0320.1.1
0320.2.1	C	PR 4'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H4	J4	---	B-90	B04	1 & 3	RM NM STAIR L	1,2,4	0320.2.1
0320.2.2	B	PR 4'-0"	7'-0"	1-3/4"	HM	P	HM11	HM	P	H22	J21	S1	---	A07	---	---	1,2	0320.2.2
0321.1	B	3'-0"	7'-0"	1-3/4"	WD	PF	HM5	HM	P	H2	J1	S4	---	G01	1	RM NM	---	0321.1
0322.1	E	PR 3'-0"	7'-0"	1-3/4"	AL	PF	C03	AL	PF	H20	7/A-2.70	S1	---	AL-03	---	---	1,2	0322.1
0322.2	E	PR 3'-0"	7'-0"	1-3/4"	AL	PF	C02	AL	PF	H20	J20.1	S1	---	AL-04	---	---	1,2	0322.2
0322.3	E	PR 3'-0"	7'-0"	1-3/4"	AL	PF	C02	AL	PF	H20	J20.1	S1	---	AL-04	---	---	1,2	0322.3
0322.4	E	PR 3'-0"	7'-0"	1-3/4"	AL	PF	C01	AL	PF	H20	7/A-2.70	S1	---	AL-04	---	---	1,2	0322.4
0322.5	D	PR 4'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H1	J1	---	---	C06	2	RM NM GYMNASIUM	1,2	0322.5
0322.6	D	PR 3'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H1	J1	S5	---	C06	2	RM NM GYMNASIUM	1,2	0322.6
0322.7	D	PR 3'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H1	J1	S5	---	C06	2	RM NM GYMNASIUM	1,2	0322.7
0322.1.1	A	PR 3'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H1	J1	S5	---	H14	1	RM NM	1	0322.1.1
0322.2.1	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S7	---	H08	2	RM NM IDF	1	0322.2.1
0322.3.1	B	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1		---	F04	1	RM NM	1	0322.3.1
0322.3.2	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S6	---	E03	1 & 3	RM NM RESTROOM	1	0322.3.2
0323.1	A	3'-6"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S3	B-90	C11	2	RM NM ELEVATOR MACHINE ROOM	1,2	0323.1
0324	---	---	---	---	---	---	---	---	---	---	---	S6	---	---	1 & 3	RM NM WOMEN	5	0324
0325	---	---	---	---	---	---	---	---	---	---	---	S6	---	---	1 & 3	RM NM BOYS	5	0325
0326	---	---	---	---	---	---	---	---	---	---	---	S6	---	---	1 & 3	RM NM MEN	5	0326
0327	---	---	---	---	---	---	---	---	---	---	---	S6	---	---	1 & 3	RM NM GIRLS	5	0327
0328.1	A	4'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S3	C-45	H06	2	RM NM CUSTODIAN	1	0328.1
0329.1	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S6	---	G05	1	RM NM	1	0329.1
0330.1	B	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	---	---	G01	1	RM NM	---	0330.1
0330.1.1	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S6	---	E03	1 & 3	RM NM RESTROOM	1	0330.1.1
0331.1	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S3	---	H01	1	RM NM	1	0331.1
0331.2	A	PR 3'-0"	7'-0"	1-3/4"	HM	P	HM10	HM	P	H22	J21	S1	---	A08	---	---	1	0331.2
0332.1	A	4'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S6	C-45	H06	1	RM NM	1	0332.1
0340.1.1	C	PR 4'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H4	J4	---	B-90	B05	1 & 3	RM NM STAIR K	1,2,4	0340.1.1
0340.1.2	B	PR 4'-0"	7'-0"	1-3/4"	HM	P	HM11	HM	P	H22	J21	S1	---	A07	---	---	1,2	0340.1.2
0340.1.3	B	PR 4'-0"	7'-0"	1-3/4"	HM	P	HM11	HM	P	H22	J21	S1	---	A07	---	---	1,2	0340.1.3
0341.1	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S6	---	D02	2	RM NM VISITOR GIRLS	1	0341.1
0341.1	---	---	---	---	---	---	---	---	---	---	---	---	---	---	1 & 3	RM NM RESTROOM	5	0341.1
0342.1	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S6	---	C02	2	RM NM BOYS LOCKER ROOM	1,2	0342.1
0342.2	A	3'-0"	7'-0"	1-3/4"	HM	P	HM1	HM	P	H21	J21	S1	---	A01	---	---	1,2	0342.2
0342.1.1	B	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	---	---	C03	1	RM NM	1,2	0342.1.1
0342.1.2	B	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	---	---	G06	1	RM NM	1,16	0342.1.2
0342.1.3	A	3'-0"	7'-0"	1-3/4"	HM	P	HM1	HM	P	H21	J21	S1	---	A02	---	---	1,2	0342.1.3
0342.2.1	---	PR 3'-9"	9'-4"	1-1/2"	---	---	---	---	---	---	---	---	---	J01	1	RM NM	6	0342.2.1
0342.3	---	---	---	---	---	---	---	---	---	---	---	---	---	---	1 & 3	RM NM RESTROOM	5	0342.3
0342.4	---	---	---	---	---	---	---	---	---	---	---	---	---	---	1 & 3	RM NM SHOWERS	5	0342.4
0343.1	B	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	---	---	G01	1	RM NM	---	0343.1
0343.2	B	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S6	---	G03	1	RM NM	1	0343.2
0343.1.1	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	---	---	F05	1	RM NM	1	0343.1.1
0343.1.2	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S6	---	E02	1 & 3	RM NM RESTROOM	1	0343.1.2
0344.1	B	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	---	---	G01	1	RM NM	---	0344.1
0344.2	B	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S6	---	G03	1	RM NM	1	0344.2
0344.1.1	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	---	---	F05	1	RM NM	1	0344.1.1
0344.1.2	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S6	---	E02	1 & 3	RM NM RESTROOM	1	0344.1.2
0345.1	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S6	---	C02	2	RM NM GIRLS LOCKER ROOM	1,2	0345.1
0345.2	A	3'-0"	7'-0"	1-3/4"	HM	P	HM1	HM	P	H21	J21	S1	---	A01	---	---	1,2	0345.2
0345.1.1	---	PR 3'-9"	9'-4"	1-1/2"	---	---	---	---	---	---	---	---	---	J01	1	RM NM	6	0345.1.1
0345.2.1	---	PR 3'-9"	9'-4"	1-1/2"	---	---	---	---	---	---	---	---	---	J01	1	RM NM	6	0345.2.1
0345.3.1	---	PR 3'-9"	9'-4"	1-1/2"	---	---	---	---	---	---	---	---	---	J01	1	RM NM	6	0345.3.1
0345.3.2	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S6	---	C03	1	RM NM	1,2	0345.3.2
0345.4.1	---	PR 3'-9"	9'-4"	1-1/2"	---	---	---	---	---	---	---	---	---	J01	1	RM NM	6	0345.4.1
0345.5	---	---	---	---	---	---	---	---	---	---	---	---	---	---	1 & 3	RM NM RESTROOM	5	0345.5
0345.6	---	---	---	---	---	---	---	---	---	---	---	---	---	---	1 & 3	RM NM SHOWERS	5	0345.6
0346.1	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S6	---	D03	2	RM NM VISITOR BOYS	1	0346.1
0346.2	---	---	---	---	---	---	---	---	---	---	---	---	---	---	1 & 3	RM NM RESTROOM	5	0346.2
0350.1.1	C	PR 4'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H4	J4	---	B-90	B03	1 & 3	RM NM STAIR M	1,2,4	0350.1.1
0351.1	B	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	---	---	G01	1	RM NM	[illegible]	0351.1
0353.1	B	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	---	---	G01	1	RM NM	[illegible]	0353.1
0355.1	B	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S8	---	C05	1	RM NM	1,2	0355.1
0355.2	B	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S8	---	C05	1	RM NM	1,2	0355.2
0357.1	B	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S8	---	G07	1	RM NM	1	0357.1
0357.2	B	PR 3'-0"	7'-0"	1-3/4"	HM	P	HM10	HM	P	H22	J21	S1	---	A03	---	---	[illegible]	0357.2
0359.1	B	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S3	---	G07	[illegible]	[illegible]	[illegible]	0359.1
0359.2	D	PR 3'-0"	7'-0"	1-3/4"	WD	PF	HM6	HM	P	H2	J1	S8	---	[illegible]	[illegible]	---	[illegible]	0359.2
0359.3	B	PR 3'-0"	7'-0"	1-3/4"	HM	P	HM10	HM	P	H22	J21	S1	---	[illegible]	[illegible]	---	1,2	0359.3
0360.1	A	PR 3'-0"	7'-0"	1-3/4"	HM	P	HM10	HM	P	H22	J21	S1	---	[illegible]	[illegible]	RM NM	1	0360.1
0361.1	A	PR 3'-0"	7'-0"	1-3/4"	HM	P	HM10	HM	P	H22	[illegible]	[illegible]	[illegible]	A08	1	RM NM	1	0361.1
LEVEL 100																		
1234.9.1	---	---	---	---	---	---	---	---	---	[illegible]	---	[illegible]	---	J01	[illegible]	---	17	1234.9.1
1310.1	B	PR 4'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H1	[illegible]	[illegible]	---	B06	[illegible]	---	1,2,4	1310.1
1311.1	B	PR 3'-0"	7'-0"	1-3/4"	WD	PF	HM11	HM	P	H2	[illegible]	[illegible]	---	[illegible]	2	RM NM GYMNASIUM	1,2	1311.1
1311.2	B	PR 3'-0"	7'-0"	1-3/4"	WD	PF	HM11	HM	P	H2	J1	S8	---	C09	2	RM NM GYMNASIUM	1,2	1311.2
1311.1.1	C	PR 4'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	[illegible]	H4	J4	S8	B-90	B04	1 & 3	RM NM STAIR H	1,2,4	1311.1.1
1320.1.1	C	PR 3'-6"	7'-0"	1-3/4"	WD	PF	HM2	[illegible]	P	H1	J1	[illegible]	B-90	B03	1 & 3	RM NM STAIR J	1,2,4	1320.1.1
1320.2.1	C	PR 4'-0"	7'-0"	[illegible]	WD	PF	[illegible]	HM	[illegible]	H4	J4	---	B-90	B04	1 & 3	RM NM STAIR L	1,2,4	1320.2.1
1320.4.1	A	3'-0"	7'-0"	[illegible]	WD	PF	[illegible]	HM	[illegible]	H1	J1	S3	C-45	C10	1 & 2A	RM NM ELECTRICAL	1,2	1320.4.1
1321.1	A	3'-0"	7'-0"	[illegible]	WD	PF	HM1	HM	P	H1	J1	S6	---	H05	1	RM NM	1	1321.1
1321.2	G	10'-0"	4'-2"	[illegible]	SS	[illegible]	---	[illegible]	[illegible]	H5	J5	S11	---	J01	---	---	7	1321.2
1321.3	A	3'-0"	7'-0"	1-3/4"	[illegible]	[illegible]	HM1	[illegible]	P	H1	J1	---	---	H11	1	RM NM	1	1321.3
1321.2.1	G	8'-0"	4'-2"	1"	[illegible]	---	[illegible]	[illegible]	---	H5	4/A-2.76	S11	---	J01	---	---	7	1321.2.1
1321.2.2	A	3'-0"	7'-0"	1-3/4"	[illegible]	PF	[illegible]	HM	P	H1	J1	---	---	H09	1	RM NM	1	1321.2.2
1322.1	B	3'-0"	7'-0"	1-3/4"	WD	PF	HM4	HM	P	H2	J1	---	---	G02	1	RM NM	---	1322.1
1323.1	A	[illegible]	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	---	---	H08	2	RM NM IDF	1	1323.1
1324.1	[illegible]	PR [illegible]	7'-0"	[illegible]	WD	PF	HM2	HM	P	H1	J1	S4	---	C18	2	RM NM AUDITORIUM	1,2	1324.1
1324.2	[illegible]	PR 3' [illegible]	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H1	J1	---	---	D05	---	---	1,8	1324.2
1325.1	[illegible]	3'-0"	[illegible]	1-3/4"	WD	PF	HM1	HM	P	H1	J1	---	---	D01	1 & 3	RM NM MEN	1	1325.1
1326.1	B	PR 3'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H1	J1	---	C-45	C17	2	RM NM STAGE	1,2	1326.1
1326.2	[illegible]	PR 3'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H1	J1	---	C-45	C16	2	RM NM STAGE	1,2	1326.2
[illegible]	B	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S4	C-45	G13	2	RM NM GREEN ROOM	1	1326.1.1
1327.1	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	---	---	D01	1 & 3	RM NM WOMEN	1	1327.1

DOOR NO.	DOOR ELEV.	DOOR WIDTH	DOOR HEIGHT	DOOR THICK.	DOOR MAT.	DOOR FIN.	FRAME ELEV.	FRAME MAT.	FRAME FIN.	DETAILS HEAD	DETAILS JAMB	DETAILS SILL	LABEL	HDWR SET	SIGNAGE TYPE	SIGNAGE TEXT	NOTES	DOOR NO.
1328.1	B	PR 3'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H1	J1	S4	AC	C13	1	RM NM	1,2	1328.1
1328.2	B	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S4	AC	C12	1	RM NM	1,2	1328.2
1328.1.1	B	3'-0"	7'-0"	1-3/4"	WD	PF	HM8	HM	P	H2	J1	---	---	F04	1	RM NM	1	1328.1.1
1328.2.1	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	---	---	F03	1	RM NM	1	1328.2.1
1330.1.1	C	PR 4'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H4	J4	S8	B-90	B05	1 & 3	RM NM STAIR K	1,2,4	1330.1.1
1330.1.2	C	PR 4'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H4	J4	---	B-90	B03	1 & 3	RM NM STAIR K	1,2,4	1330.1.2
1330.2.1	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S3	C-45	C10	1 & 2A	RM NM ELECTRICAL	1,2	1330.2.1
1331.1	B	PR 3'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H1	J1	S5	---	C05	2	RM NM AUXILIARY GYMNASIUM	1,2	1331.1
1331.2	B	PR 3'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H1	J1	S5	---	C06	2	RM NM AUXILIARY GYMNASIUM	1,2	1331.2
1331.3	B	PR 3'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H1	J1	S5	---	C07	2	RM NM AUXILIARY GYMNASIUM	1,2	1331.3
1331.1.1	A	PR 3'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H1	J1	S5	---	H13	1	RM NM	1	1331.1.1
1332	---	---	---	---	---	---	---	---	---	---	---	S6	---	---	1 & 3	RM NM BOYS	5	1332
1333	---	---	---	---	---	---	---	---	---	---	---	S6	---	---	1 & 3	RM NM GIRLS	5	1333
1340.1	E	PR 3'-0"	7'-0"	1-3/4"	AL	PF	C04	AL	PF	H23	J23	S1	---	AL-02	---	---	1,2	1340.1
1340.2	E	PR 3'-0"	7'-0"	1-3/4"	AL	PF	C04	AL	PF	H23	J23	S1	---	AL-02	---	---	1,2	1340.2
1340.3	E	PR 3'-0"	7'-0"	1-3/4"	AL	PF	C06	AL	PF	6/A-2.50	12/A-2.77	S1	---	AL-02	---	---	1,2	1340.3
1340.4	E	PR 3'-0"	7'-0"	1-3/4"	AL	PF	C06	AL	PF	6/A-2.50	12/A-2.77	S1	---	AL-01	---	---	1,2,12,13	1340.4
1340.5	E	PR 3'-0"	7'-0"	1-3/4"	AL	PF	C05	AL	PF	H23	S1	S1	---	AL-02	---	---	1,2	1340.5
1340.6	E	PR 3'-0"	7'-0"	1-3/4"	AL	PF	C05	AL	PF	H23	S1	S1	---	AL-02	---	---	1,2	1340.6
1341.1	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S6	---	D01	1 & 3	RM NM BOYS	1	1341.1
1342.1	B	PR 3'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H1	J1	S4	---	C18	2	RM NM AUDITORIUM	1,2	1342.1
1342.2	B	PR 3'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H1	J1	---	---	D05	---	---	1,8	1342.2
1343.1	G	10'-0"	4'-2"	1"	SS	---	---	---	---	H5	J5	S11	---	J01	---	---	7	1343.1
1343.2	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S8	AC	H15	1	RM NM	1	1343.2
1343.3	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	---	---	H11	1	RM NM	1	1343.3
1344.1	B	PR 3'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H1	J1	S4	---	C18	2	RM NM AUDITORIUM	1,2	1344.1
1344.2	B	PR 3'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H1	J1	---	---	D05	---	---	1,8	1344.2
1345.1	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	---	AC	F05	2	RM NM CONTROL ROOM	1	1345.1
1346.1	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S6	---	D01	1 & 3	RM NM GIRLS	1	1346.1
1347.1	A	4'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S3	C-45	H07	2	RM NM CUSTODIAN	1	1347.1
1348.1	A	PR 3'-0"	7'-0"	1-3/4"	HM	P	HM2	HM	P	H21	J21	S1	---	A07	---	---	1,2	1348.1
1348.1.1	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S4	---	H01	1	RM NM	1	1348.1.1
1348.2.1	A	3'-0"	7'-0"	1-3/4"	HM	P	HM1	HM	P	H21	J21	S1	---	A05	---	---	1,2	1348.2.1
1348.2.2	A	4'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S3	B-90	C11	1 & 2A	RM NM ELECTRICAL	[illegible]	1348.2.2
1349.1.1	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	---	C-45	C01	1	RM NM	1	1349.1.1
1349.1.2	H	10'-0"	10'-0"	1"	S	PF	---	---	---	---	---	---	C-45	J01	---	---	9	1349.1.2
1349.2.1	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	---	C-45	G08	1	RM NM	1	1349.2.1
1349.2.2	H	10'-0"	10'-0"	1"	S	PF	---	---	---	---	---	---	C-45	J01	---	---	9	1349.2.2
1349.2.3	A	PR 3'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H1	J1	---	C-45	[illegible]	1	RM NM	1	1349.2.3
1349.2.4	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	---	C-45	[illegible]	1	RM NM	1	1349.2.4
1349.2.5	H	10'-0"	10'-0"	1"	S	PF	---	---	---	---	---	---	[illegible]	[illegible]	---	---	9	1349.2.5
1349.3.1	A	3'-0"	7'-0"	1-3/4"	HM	P	HM1	HM	P	H21	J21	SIM S1	---	[illegible]	---	---	1,2	1349.3.1
1349.3.2	H	10'-0"	10'-0"	1"	GS	PF	---	---	---	---	---	SIM S1	---	[illegible]	---	---	[illegible]	1349.3.2
1349.3.3	B	PR 4'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H1	J1	[illegible]	[illegible]	B03	[illegible]	---	[illegible]	1349.3.3
1349.4.1	A	PR 3'-6"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H1	J1	---	[illegible]	H12	[illegible]	[illegible]	1	1349.4.1
1349.5.1	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	---	C-45	[illegible]	2	RM NM SOUND CONTROL	1	1349.5.1
1350.1.1	C	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	[illegible]	J4	[illegible]	B-90	[illegible]	---	---	1,2,4	1350.1.1
1350.1.2	C	PR 3'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	[illegible]	H4	[illegible]	[illegible]	B-90	B02	1 & 3	RM NM STAIR M	1,2,4	1350.1.2
1350.1.3	E	PR 3'-6"	7'-0"	1-3/4"	AL	PF	C07	AL	[illegible]	H26	[illegible]	[illegible]	---	AL-05	---	---	1,2	1350.1.3
1350.1.4	E	PR 3'-6"	7'-0"	1-3/4"	AL	PF	C07	AL	[illegible]	H26	[illegible]	[illegible]	---	AL-05	---	---	1,2	1350.1.4
1350.2.1	A	3'-0"	7'-0"	1-3/4"	WD	PF	[illegible]	HM	[illegible]	H1	J1	[illegible]	C-45	F07	1	RM NM	1	1350.2.1
1351.1	B	3'-0"	7'-0"	1-3/4"	WD	PF	[illegible]	HM	P	[illegible]	J1	[illegible]	AC	G10	1	RM NM	1	1351.1
1351.2	B	3'-0"	7'-0"	1-3/4"	WD	PF	[illegible]	HM	P	[illegible]	[illegible]	---	AC	F06	1	RM NM	1	1351.2
1352.1	B	3'-0"	7'-0"	1-3/4"	[illegible]	PF	HM1	HM	P	H1	[illegible]	---	C-45	C04	1	RM NM	1,3	1352.1
1352.2	B	PR 3'-0"	7'-0"	1-3/4"	[illegible]	PF	HM2	HM	P	H1	[illegible]	---	C-45	C14	1	RM NM	1,2	1352.2
1352.1.1	B	3'-0"	7'-0"	[illegible]	WD	[illegible]	HM9	HM	P	H2	[illegible]	S4	---	F02	1	RM NM	---	1352.1.1
1352.2.1	A	3'-0"	7'-0"	[illegible]	WD	[illegible]	HM1	HM	P	H1	J1	---	---	H01	1	RM NM	1	1352.2.1
1353.1	B	3'-0"	[illegible]	[illegible]	WD	[illegible]	[illegible]	HM	P	H1	J1	S4	AC	G12	1	RM NM	1	1353.1
1353.2	B	3'-0"	7'-0"	[illegible]	WD	[illegible]	[illegible]	HM	P	H2	J1	---	AC	F08	1	RM NM	1	1353.2
1354.1	B	3'-0"	7'-0"	[illegible]	WD	[illegible]	[illegible]	[illegible]	P	H1	J1	---	C-45	C04	1	RM NM	1,2	1354.1
1354.2	B	PR 3'-0"	7'-0"	1-3/4"	[illegible]	[illegible]	HM2	[illegible]	P	H1	J1	---	C-45	C15	1	RM NM	1,2	1354.2
1354.1.1	A	4'-0"	7'-0"	1-3/4"	[illegible]	[illegible]	HM1	HM	P	H1	J1	---	C-45	H04	1	RM NM	1	1354.1.1
1354.1.2	[illegible]	4'-0"	7'-0"	1-3/4"	WD	[illegible]	HM1	HM	P	H1	J1	---	---	H02	1	RM NM	1	1354.1.2
1355.1	B	PR 3'-0"	7'-0"	1-3/4"	WD	[illegible]	HM2	HM	P	H1	J1	S4	AC	C13	1	RM NM	1,2	1355.1
1355.2	B	[illegible]	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S4	AC	C12	1	RM NM	1,2	1355.2
1355.1.1	[illegible]	PR 3' [illegible]	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H1	J1	---	AC	H16	1	RM NM	1	1355.1.1
1355.2.1	[illegible]	3'-0"	7'-0"	1-3/4"	WD	PF	HM8	HM	P	H2	J1	---	---	F04	1	RM NM	1	1355.2.1
1356.1	B	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H2	J1	S4	AC	G11	1	RM NM	1	1356.1
1357.1	B	3'-0"	[illegible]	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S4	AC	C12	1	RM NM	1,2	1357.1
1357.2	B	PR 3'-0"	[illegible]	1-3/4"	WD	PF	HM2	HM	P	H1	J1	S4	AC	C13	1	RM NM	1,2	1357.2
1357.1.1	A	PR 3' [illegible]	[illegible]	1-3/4"	WD	PF	HM2	HM	P	H1	J1	---	AC	H18	1	RM NM	1	1357.1.1
1357.2.1	B	[illegible]	[illegible]	1-3/4"	WD	PF	HM1	HM	P	H1	J1	---	---	H02	1	RM NM	1	1357.2.1
1357.3.1	[illegible]	3'-6"	[illegible]	1-3/4"	WD	PF	HM1	HM	P	H1	J1	---	AC	H17	1	RM NM	1	1357.3.1
1357.4.1	[illegible]	3'-6"	[illegible]	1-3/4"	WD	PF	HM1	HM	P	H1	J1	---	AC	H17	1	RM NM	1	1357.4.1
1357.4.2	B	3'-6"	[illegible]	1-3/4"	WD	PF	HM1	HM	P	H1	J1	---	AC	H17	1	RM NM	1	1357.4.2
1357.5.1	B	3'-0"	7'-0"	1-3/4"	WD	PF	HM8	HM	P	H2	J1	---	---	F04	1	RM NM	1	1357.5.1
[illegible]	[illegible]	3'-0"	7'-0"	1-3/4"	WD	PF	HM8	HM	P	H2	J1	---	---	F04	1	RM NM	1	1357.6.1
1360.1	B	PR 4'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H1	J1	---	---	C17	2	RM NM STAGE	1,2	1360.1
1361.1	A	4'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	---	C-45	G04	2	RM NM BOYS DRESSING ROOM	1	1361.1
1361.2	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S6	---	E01	1 & 3	RM NM RESTROOM	1	1361.2
1362.1	A	4'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	---	C-45	G04	2	RM NM GIRLS DRESSING ROOM	1	1362.1
1362.2	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H1	J1	S6	---	E01	1 & 3	RM NM RESTROOM	1	1362.2
STADIUM																		
1600.1	A	3'-0"	7'-0"	1-3/4"	HM	P	HM1	HM	P	H24	J24	S1	---	A10	1	RM NM	1	1600.1
1600.2	G	12'-0"	4'-2"	1"	SS	---	---	---	---	H25	J25	S25	---	J01	---	---	11	1600.2
1611.1	A	3'-0"	7'-0"	1-3/4"	HM	P	HM1	HM	P	H24	J24	S1	---	A09	1 & 3	RM NM WOMEN	1	1611.1
1600.1.1	A	3'-0"	7'-0"	1-3/4"	HM	P	HM1	HM	P	H24	J24	S1	---	A09	1 & 3	RM NM MEN	1	1600.1.1
1620.1	A	3'-0"	7'-0"	1-3/4"	HM	P	HM1	HM	P	H21	J21	S1	---	A11	1	RM NM	1	1620.1
1621.1	B	3'-0"	7'-0"	1-3/4"	HM	P	HM1	HM	P	H1	J1	---	---	F01	---	---	---	1621.1
1621.2	B	3'-0"	7'-0"	1-3/4"	HM	P	HM1	HM	P	H1	J1	---	---	F01	---	---	---	1621.2
1822.1	A	3'-0"	7'-0"	1-3/4"	HM	P	HM1	HM	P	H21	J21	S1	---	A11	1	RM NM	1	1622.1
TICKET BOOTH																		
1700.1	A	3'-0"	7'-0"	1-3/4"	HM	P	HM1	HM	P	H24	J24	S1	---	A12	1	RM NM	1	1700.1
1700.2	G	8'-0"	4'-2"	1"	SS	---	---	---	---	H25	J25	S25	---	J01	---	---	11	1700.2
TEMPORARY CONSTRUCTION - PHASE 3																		
040.1	A	PR 3'-0"	7'-0"	1-3/4"	WD	P	HM2	HM	P	H8	J8	---	---	EX	---	---	1,2,14	040.1
112.1	A	PR 3'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H8	J8	---	B-60	EX	---	---	1,2,14	112.1
112.1.1	A	PR 3'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H8	J8	---	---	EX	---	---	14	112.1.1
113.1	A	PR 3'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H8	J8	---	B-60	EX	---	---	1,2,14	113.1
113.1.1	B	3'-0"	7'-0"	1-3/4"	WD	PF	HM8	HM	P	H8	J8	---	---	EX	---	---	14	113.1.1
113.2	B	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H8	J8	---	---	EX	---	---	1,2,14	113.2
113.3.1	B	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H8	J8	---	---	EX	---	---	14	113.3.1
119.1	A	PR 3'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H1	J1	---	B-90	EX	---	---	1,2,15	119.1
133.3	A	3'-0"	7'-0"	1-3/4"	HM	P	HM1	HM	P	H24 SIM	J24 SIM	S26	---	EX	---	---	1,2,14	133.3
501.1	A	PR 3'-0"	7'-0"	1-3/4"	WD	P	HM2	HM	P	H8	J8	---	---	EX	---	---	1,14	501.1
501.2	A	3'-0"	FV	1-3/4"	WD	P	HM1	HM	P	H24 SIM	J24 SIM	2/DA-8.35	---	EX	---	---	1,14	501.2
502.1	B	PR 3'-0"	7'-0"	1-3/4"	WD	PF	HM2	HM	P	H8	J8	---	---	EX	---	---	1,14	502.1
502.4	A	3'-0"	7'-0"	1-3/4"	HM	P	HM1	HM	P	H24 SIM	J24 SIM	S26	---	EX	---	---	1,2,14	502.4
504.1	A	3'-0"	7'-0"	1-3/4"	WD	PF	HM1	HM	P	H8	J8	---	---	EX	---	---	1,14	504.1

ABBREVIATIONS:

AC	ACOUSTICAL	S	STEEL
HM	HOLLOW METAL	GS	GALVANIZED STEEL
MIN	MINUTES	SIM	SIMILAR
P	PAINT	SS	STAINLESS STEEL
PF	PRE-FINISHED	WD	SOLID CORE WOOD
PR	PAIR	EX	EXISTING

GENERAL NOTES:

1. SEE A-8 SERIES SHEETS FOR DOOR ELEVATIONS, FRAME ELEVATIONS, HEAD DETAILS, JAMB DETAILS, SILL DETAILS AND SIGNAGE TYPE ELEVATIONS.
2. REFER TO FINISH SCHEDULE AND A-9 SERIES DRAWINGS FOR ADDITIONAL INFORMATION REGARDING LOCATIONS OF FLOOR FINISH TRANSITIONS. IN ADDITION TO THE METAL THRESHOLDS SCHEDULED HERE, PROVIDE TRANSITIONS AT ADJACENT FLOOR FINISHES AS DETAILED IN SILL DETAILS ON SHEET A-8.30.
3. GREY SHADING IN DOOR SCHEDULE INDICATES EXISTING DOORS AND HARDWARE TO BE SALVAGED FROM AREA TO BE DEMOLISHED AND REINSTALLED IN NEW FRAME FOR TEMPORARY USE.

FOOTNOTES:

1. CLOSER
2. PANIC/ FIRE EXIT DEVICE
3. PANIC/ FIRE EXIT DEVICE WITH VERTICAL RODS
4. AUTOMATIC HOLD OPEN DEVICE. PROVIDE CLOSER TO SWING FULL 180 DEGREES WHERE INDICATED.
5. ENTRANCE TO STUDENT TOILETS. PROVIDE AND INSTALL SIGNAGE AS SCHEDULED.
6. WIRE MESH PARTITION FILLING 8' WIDE X 9'-4" HIGH OPENING, WITH ONE SLIDING DOOR.
7. COILING COUNTER SHUTTER, MOTOR OPERATION. DIMENSIONS GIVEN ARE FOR CLEAR WALL OPENING. REFER TO HEAD, JAMB AND SILL DETAILS FOR FULL SIZE REQUIREMENTS.
8. PUSH/ PULL HARDWARE.
9. OVERHEAD FIRE-RATED COILING DOOR, MOTOR OPERATION. DIMENSIONS GIVEN ARE FOR CLEAR WALL OPENING. REFER TO HEAD, JAMB AND SILL DETAILS FOR FULL SIZE REQUIREMENTS.
10. OVERHEAD INSULATED COILING DOOR, MOTOR OPERATION. DIMENSIONS GIVEN ARE FOR CLEAR WALL OPENING. REFER TO HEAD, JAMB AND SILL DETAILS FOR FULL SIZE REQUIREMENTS.

FOOTNOTES:

11. COILING COUNTER SHUTTER, PUSH-UP OPERATION. DIMENSIONS GIVEN ARE FOR CLEAR WALL OPENING. REFER TO HEAD, JAMB AND SILL DETAILS FOR FULL SIZE REQUIREMENTS.
12. ACCESS CONTROL DEVICE
13. ADA AUTOMATIC OPENING DEVICE
14. SALVAGE EXISTING DOOR (S) AND HARDWARE FROM EXISTING LOCATION IN AREA INDICATED TO BE DEMOLISHED. REINSTALL IN NEW HM FRAME. REKEY EXISTING HARDWARE. CONTRACTOR FIELD VERIFY EXISTING DIMENSIONS.
15. SALVAGE EXISTING HARDWARE FROM EXISTING LOCATION IN AREA INDICATED TO BE DEMOLISHED. REINSTALL IN NEW DOOR AND HM FRAME. REKEY EXISTING HARDWARE. CONTRACTOR FIELD VERIFY EXISTING DIMENSIONS.

Architecture Planning Facilitation Design

CGLS ARCHITECTS

CHAPMAN GRIFFIN LANIER SUSSENBACH ARCHITECTS, INC.

© 2018

THIS DRAWING AND DIMENSIONS OF WHICH ARE 30" X 42" ARE THE PROPERTY OF CHAPMAN GRIFFIN LANIER SUSSENBACH ARCHITECTS, INC. AND MAY NOT BE USED OR REPRODUCED WITHOUT THEIR WRITTEN PERMISSION

RELEASED FOR CONSTRUCTION

CONSULTANT

SEAL

STATE OF GEORGIA · ROBERT SUSSENBACH · CERTIFICATE No. 4042 · REGISTERED ARCHITECT

DATE	NO.	DESCRIPTION
03/27/18		GDOE PRELIMINARY SUBMITTAL / DESIGN DEVELOPMENT
06/19/18		50% CONSTRUCTION DOCUMENTS
09/17/18		GDOE CHECK-SET/ PERMIT SET
10/10/18		FINAL GDOE SUBMITTAL
11/01/18		ISSUED FOR PROPOSALS

CHAPMAN GRIFFIN LANIER SUSSENBACH ARCHITECTS

400 Galleria Pkwy . Suite 100 . Atlanta, Ga 30339 . Phone: 404.733.5493

DOE FACILITY CODE: 660 -3066

RIVERWOOD HIGH SCHOOL-PHASE 3-8 AUDITORIUM/GYMNASIUM ADDITION

5900 RAIDER DRIVE NW SANDY SPRINGS, GA 30328

FULTON COUNTY SCHOOLS RFP NO. 411-19

SHEET TITLE

DOOR SCHEDULE - LEVEL 000 & LEVEL 100

PROJECT NO. 16015.02

DATE: 09/17/18

DRAWN BY: Author

CHECKED BY: Checker

SHEET NO.

A-8.01

11/1/2018 11:26:56 AM

Order Plans @ WWW.LDILine.com