Order Plans @ WWW.LDILine.com

PLUMBING GAS LOAD SCHEDULE

Total Equivalent Length of Pipe(Feet):	425	Pressure Drop (PSI):	1	Delivery Pressure After Meter & PRV (PSI):	2	Gas Type	NATURAL GAS

MARK	HVACTYPE	DESCRIPTION	STATUS	GAS HTG IN (CFH)	MIN GAS PRESSURE (IN WC)	MAX GAS PRESSURE (IN WC)
B109Ga	22 00 00.00.00	Oven		300	5	14
B109Gb	22 00 00.00.00	Oven		300	5	14
CN1	22 00 00.00.00	GENERATOR		1260	10	14
D307G	22 00 00.00.00	Pizza Oven		120	4	5
DOAS-1	23 74 33.00.00	PACKAGED OUTDOOR ROOFTOP UNIT		540	6	10.5
DOAS-2	23 74 33.00.00	PACKAGED OUTDOOR ROOFTOP UNIT		540	6	10.5
RTU-1	23 74 33.00.00	PACKAGED OUTDOOR ROOFTOP UNIT		195	6	10.5
RTU-2	23 74 33.00.00	PACKAGED OUTDOOR ROOFTOP UNIT		195	6	10.5
RTU-3	23 74 33.00.00	PACKAGED OUTDOOR ROOFTOP UNIT		195	6	10.5
RTU-4	23 74 33.00.00	PACKAGED OUTDOOR ROOFTOP UNIT		195	6	10.5
RTU-5	23 74 33.00.00	PACKAGED OUTDOOR ROOFTOP UNIT		195	6	10.5
RTU-6	23 74 33.00.00	PACKAGED OUTDOOR ROOFTOP UNIT		240	6	10.5
RTU-7	23 74 33.00.00	PACKAGED OUTDOOR ROOFTOP UNIT		240	6	10.5
RTU-8	23 74 33.00.00	PACKAGED OUTDOOR ROOFTOP UNIT		240	6	10.5
RTU-9	23 74 33.00.00	PACKAGED OUTDOOR ROOFTOP UNIT		240	6	10.5
RTU-10	23 74 33.00.00	PACKAGED OUTDOOR ROOFTOP UNIT		195	6	10.5
RTU-11	23 74 33.00.00	PACKAGED OUTDOOR ROOFTOP UNIT		195	6	10.5
RTU-12	23 74 33.00.00	PACKAGED OUTDOOR ROOFTOP UNIT		60	6	10.5
RTU-13	23 74 33.00.00	PACKAGED OUTDOOR ROOFTOP UNIT		90	6	10.5
RTU-14	23 74 33.00.00	PACKAGED OUTDOOR ROOFTOP UNIT		240	6	10.5
RTU-15	23 74 33.00.00	PACKAGED OUTDOOR ROOFTOP UNIT		240	6	10.5
RTU-16	23 74 33.00.00	PACKAGED OUTDOOR ROOFTOP UNIT		60	6	10.5
RTU-17	23 74 33.00.00	PACKAGED OUTDOOR ROOFTOP UNIT		195	6	10.5
RTU-18	23 74 33.00.00	PACKAGED OUTDOOR ROOFTOP UNIT		195	6	10.5
RTU-19	23 74 33.00.00	PACKAGED OUTDOOR ROOFTOP UNIT		195	6	10.5
RTU-20	23 74 33.00.00	PACKAGED OUTDOOR ROOFTOP UNIT		90	6	10.5
WH1	22 34 00.00.00	DOMESTIC GAS-FIRED TANK-TYPE WATER HEATER	BLUE	199	3.5	14
		TOTAL GAS LOAD:		6949		

PLUMBING WATER HEATER SCHEDULE

MARK	DESCRIPTION	LOCATION	MANUFACTURER	MODEL	EFFICIENCY	EWT (DEG F)	LWT (DEG F)	GAS HTG IN (MBH)	STORAGE (GAL)	FUEL	MIN GAS PRESSURE (IN WC)	MAX GAS PRESSURE (IN WC)	HTG KW (kW)	VOLTS	PHASE	WEIGHT	EMERGENCY	FLA	MCA	OCP	ACCESS
RC1a	RECLAIM TANK		THERMA-STOR	II-1	0	0	0	0	119					0	0						
RC1b	RECLAIM TANK		THERMA-STOR	II-1	0	0	0	0	119					0	0						
WH1	DOMESTIC GAS-FIRED TANK-TYPE WATER HEATER		LOCHINVAR	CGN200080	0	0	0	199	82	NATURAL GAS	3.5	14		0	0						

PLUMBING PUMP SCHEDULE

MARK	DESCRIPTION	LOCATION	STATUS	MANUFACTURER	MODEL	VOLTS	PHASE	EMERGENCY	WEIGHT (lbs)	FLOW (gpm)	HEAD (ft)	BHP (hp)	HP (hp)	WATTS (Watts)	RPM	FLA (amps)	OCP (amps)	ACCESSORIES
CP1	HOT WATER RECIRCULATING PUMP			B&G	[illegible]00BNF	[illegible]	[illegible]			0	0		1/12		1725	1.75		
CSP1	SEWAGE EJECTOR PUMP			ZOELLER	137	480	3			0	0		1/2		0			
ESP1	SEWAGE EJECTOR PUMP			ZOELLER	SEE SPEC. [illegible]429	115	[illegible]			0	0		1/2		0			SEE SPEC. 221429

PLUMBING ELECTRICAL COORDINATON SCHEDULE

ABBREVIATIONS
- DC LOCAL DISCONNECT
- MC MOTOR CONTROL (POWER)
- SD DUCT SMOKE DETECTOR
- CN CONTROL
- TS TOGGLE SWITCH
- C/B H.A.C.R. CIRCUIT BREAKER AT SOURCE PANELBOARD
- FUSE FUSE AT LOCAL DISCONNECT (VERIFY FIELD RATING)
- FLA OPERATING FULL LOAD AMPS
- MCA MINIMUM CIRCUIT AMPACITY
- CP CORD AND PLUG CONNECTION

CONTRACTOR TYPE
- EC ELECTRICAL CONTRACTOR
- EX EXISTING
- FC FIRE PROTECTION CONTRACTOR
- GC GENERAL CONTRACTOR
- HC HVAC CONTRACTOR
- MFR MANUFACTURER
- PC PLUMBING CONTRACTOR
- OR OWNER OR OTHERS

MOTOR CONTROL TYPE
- CS COMBINATION STARTER
- MCC MOTOR CONTROL STARTER
- MG MAGNETIC STARTER OR CONTACT
- MS MANUAL STARTER
- VFD VARIABLE FREQUENCY DRIVE
- MSR MANUAL STARTER W/ CONTROL RELAY
- OV OVERCURRENT PROTECTION

CONTROL TYPE
- TC TIMECLOCK
- CPT CONTROL POWER TRANSFORMER
- BAS BUILDING AUTOMATION SYSTEM
- LOW LOW VOLTAGE CONTROLS
- LINE LINE VOLTAGE CONTROLS
- RLINE REVERSE ACTING LINE VOLTAGE THERMOSTAT
- MAN MANUAL
- FA FIRE ALARM
- CO CARBON MONOXIDE SENSOR
- INT INTEGRAL TO EQUIPMENT

EQUIPMENT MARK	DESCRIPTION	VOLTS (V)	PHASE	EMERGENCY	BHP (HP)	HP (HP)	HTG KW (kW)	WATTS (W)	FLA (A)	MCA (A)	OCP (A)	DC TYPE	DC FURN	DC INST	DC WIRE	MC TYPE	MC FURN	MC INST	MC WIRE	CN TYPE	CN FURN	CN INST	CN WIRE
CP1	HOT WATER RECIRCULATING PUMP	120	1			1/12			1.75				EC	EC	EC	MG	MFR	MFR	MFR	LINE	PC	PC	PC
CSP1	SEWAGE EJECTOR PUMP	480	3			1/2							EC	EC	EC	MG	MFR	MFR	MFR	LINE	PC	PC	PC
ESP1	SEWAGE EJECTOR PUMP	115	1			1/2							EC	EC	EC	MG	MFR	MFR	MFR	LINE	PC	PC	PC

DRAIN SCHEDULE

FLOOR DRAIN TYPE	APPLICATION	REMARK
FD1	FLOOR DRAIN	REFER TO DETAIL PSD-3
FD2	FLOOR DRAIN	REFER TO DETAIL PSD-2
FD4	FLOOR SINK	REFER TO DETAIL PSD-16B
FD5	FLOOR SINK	REFER TO STARBUCKS PLANS
FD6	FLOOR DRAIN	REFER TO DETAIL PSD-16
TD1	TRENCH DRAIN	REFER TO DETAIL PSD-34

KROGER PLUMBING FIXTURE CONNECTION SCHEDULE

#	DESCRIPTION	HW	CW	REMARKS	PROVIDED BY	INSTALLED BY
B109G	GAS DOUBLE RACK OVEN	N.A.	[illegible]	PROVIDE 1/2" VALVED & FILTERED COLD WATER LINE W/PRESSURE REGULATOR SET AT 45 P.S.I. MOUNTED AT 8'-0" AB. FL.; 1 1/4" VALVED GAS LINE (300,000 BTU) 8'-0" AB. FL.; 4" FLOOR SINK FOR STEAM CONDENSATE	OWNER	P.C.
B124B-[illegible]	DOUBLE DOOR (60" DEEP) PROOFER (4-5 SINGLE RACKS)	N.A.	1/2"	STUB WATER 85" A.F.F. PROVIDE A SHUT-OFF VALVE AND SUPPLY FROM WATER FILTER, 4" DRAIN	OWNER	P.C.
CHB	COLD WATER HOSE BIBB	N.A.	3/4"	MOUNT 2'-0" A.F.F., SEE SPECS, PROVIDE A #1012 BACKFLOW PREVENTER. COORDINATE H.B. INSTALLATION WITH EQUIPMENT AND FIXTURES	P.C.	P.C.
D15CD-480	DOUBLE COMBI CHICKEN OVEN (480V)	N.A.	3/4"	PROVIDE 3/4" VALVED & FILTERED C.W. LINE AND ONE 3/4" VALVED UNTREATED C.W. LINE. (30-90PSI) PER OVEN, 4" HUB DRAIN TIED TO GREASE LADEN LINE.	OWNER	P.C.
D15CS-480	SINGLE COMBI CHICKEN OVEN W/ STAND (480V)	N.A.	3/4"	PROVIDE 3/4" VALVED & FILTERED C.W. LINE AND ONE 3/4" VALVED UNTREATED C.W. LINE. (30-90PSI), 4" HUB DRAIN TIED TO GREASE LADEN LINE.	OWNER	P.C.
[illegible]-480	UTENSIL WASHER (480V)	3/4"	N.A.	STUB WATER 6' - 2" A.F.F. AND PROVIDE A PRESSURE REGULATOR SET AT 25 PSI & WATER HAMMER ARRESTOR. 4" HUB DRAIN WITH 20' OF CAST IRON PIPING TO DISSIPATE HEAT. PROVIDE BFP.	OWNER	P.C.
D307G	PIZZA OVEN	N.A.	N.A.	PROVIDE A 3/4" VALVED NATURAL GAS LINE. EACH OVEN REQUIRES SEPARATE GAS CONNECTION (60,000 BTU'S EACH)	OWNER	P.C.
ETV	EMERGENCY TEMPERING VALVE WITH COLD WATER BYPASS	1/2"	1/2"	REFER TO PLUMBING SPEC SECTION 221100 FACILITY WATER DISTRIBUTION FOR MORE INFORMATION	P.C.	P.C.
F9	FLORAL HELIUM BALLOON SYSTEM	N.A.	N.A.	PROVIDE 1/2" COPPER PIPING FROM HELIUM TANK TO HELIUM BALLOON NOZZLE, EQUAL TO WESTERN MODEL 312-RPB-62HGV-2.	OWNER	P.C.
GCR7	RETRACTABLE HOSE REEL (100')	N.A.	N.A.	REQUIRES COLD WATER HOSE BIBB	OWNER	P.C.
GE235-2C	2 LEVER SPRAY DOWN PROPORTIONER (VENDOR SUPPLY)	1/2"	N.A.	REQUIRES COLD WATER HOSE BIBB, HOUSE INSIDE OF S/S CABINET, REFER TO DETAIL PSD-57. SEE VENDOR DETAIL	OWNER	P.C.
GE235-3	3 LEVER SPRAY DOWN PROPORTIONER (VENDOR SUPPLY)	3/4"	N.A.	PROPORTIONER REQUIRES A SEPARATE HOT WATER HOSE BIBB WITHIN 5' - 0" OF UNIT	OWNER	P.C.
GE236-2C	2 BUTTON PROPORTIONER FOR 3-COMP SINK (VENDOR SUPPLY)	N.A.	N.A.	REQUIRES A 3/8" NPT TEE INSTALLED BETWEEN FAUCET AND PRE-RINSE SPRAYER (TEE INCREASES MOUNTING HEIGHT OF SPRAYER 3")	OWNER	P.C.
GE236-2M	2 BUTTON PROPORTIONER FOR MOP SINK (VENDOR SUPPLY)	N.A.	3/4"	PROPORTIONER REQUIRES A SEPARATE COLD WATER HOSE BIBB WITHIN 5' - 0" OF UNIT	OWNER	P.C.
HHB1	HOT WATER HOSE BIBB	3/4"	N.A.	MOUNT 2'-0" A.F.F., SEE SPECS, PROVIDE A #1012 BACKFLOW PREVENTER. COORDINATE H.B. INSTALLATION WITH EQUIPMENT AND FIXTURES. SUPPLY WITH LOOSE TEE KEY OPTION.	P.C.	P.C.
HHB2	HOT WATER HOSE BIBB	3/4"	N.A.	MOUNT ABOVE CASE, SEE SPECS, PROVIDE A #1012 BACKFLOW PREVENTER, COORD. EXACT LOCATION WITH EQUIPMENT AND FIXTURES PRIOR TO INSTALLATION. SUPPLY WITH LOOSE TEE KEY OPTION.	P.C.	P.C.
P43B	REVERSE OSMOSIS UNIT FOR PRODUCE MISTING	N.A.	1/2"	PROVIDE VALVED 1/2"CW W/ PRESSURE REGULATOR SET AT 30 PSI TO REVERSE OSMOSIS UNIT FOR PRODUCE MISTING AS REQUIRED. PROVIDE BACKFLOW PREVENTER EQUAL TO WATTS #9D. SYSTEM PROVIDED BY KROGER. INSTALLATION BY GENERAL CONTRACTOR	OWNER	P.C.
P54	PRODUCE MISTING CONTROL/TIMER	N.A.	1/2"	PROVIDE VALVED 1/2"RO TO PRODUCE HUMIDITY CONTROL AS REQUIRED AT 84"AFF. PROVIDE BACKFLOW PREVENTER EQUAL TO WATTS #9D. MISTER CONTROLS & SYSTEM PROVIDED BY KROGER. INSTALLATION BY GENERAL CONTRACTOR	OWNER	P.C.
PL1BR	COUNTERTOP SINK (ACCESSIBLE BREAKROOM) (UNIVERSAL STAINLESS MODEL DI-1-5-DF)	1/2"	1/2"	PROVIDE VALVED WATER LINES AND DRAIN	P.C.	P.C.
PL1F	FLORAL SINK (DROP IN)	1/2"	1/2"	PROVIDE VALVED WATER LINES AND DRAIN	OWNER	P.C.
PL1L-24	1 COMP PREP SINK WITH 24" LHDB	3/4"	3/4"	PROVIDE VALVED WATER LINES AND DRAIN.	OWNER	P.C.
PL1M	MOP SINK	1/2"	1/2"	PROVIDE WATER LINES AND DRAIN. REFER TO DETAIL PSD-22. PROVIDE CHECK VALVES ON WATER SUPPLIES.	P.C.	P.C.
PL1PC	1 COMP PREP SINK (24" BOWL) (NO DRAINBOARD)	1/2"	1/2"	PROVIDE VALVED WATER LINES AND DRAIN.	OWNER	P.C.
PL1PC-18	1 COMPARTMENT PREP SINK (18" BOWL) (NO DRAINBOARD)	1/2"	1/2"	PROVIDE VALVED WATER LINES AND DRAIN	OWNER	P.C.
PL1RX	PHARMCY SINK (DROP IN)	1/2"	1/2"	PROVIDE VALVED WATER LINES AND DRAIN	OWNER	P.C.
PL1SRND	SEAFOOD PREP SINK DISPOSAL/LHDB	3/4"	3/4"	PROVIDE VALVED WATER LINE AND DRAIN. REFER TO DETAIL PSD-5S	OWNER	P.C.
PL3-20	3 COMPARTMENT SINK (20"DB)	3/4"	3/4"	PROVIDE VALVED WATER LINES AND DRAIN. REFER TO DETAIL PSD-7. PROVIDE CHECK VALVES ON WATER SUPPLIES.	OWNER	P.C.
PL3C-18	SMALL 3 COMPARTMENT SINK (18"DB)	3/4"	3/4"	PROVIDE VALVED WATER LINES AND DRAIN. REFER TO DETAIL PSD-7. PROVIDE CHECK VALVES ON WATER SUPPLIES.	OWNER	P.C.
PL20	EYE WASH STATION	1/2"	1/2"	PROVIDE VALVED WATER LINES, ETV AND DRAIN. REFER TO DETAIL PSD-22.	P.C.	P.C.
PL24	WALL MOUNTED DRINKING FOUNTAIN (ADA)	N.A.	1/2"	PROVIDE VALVED WATER LINE AND DRAIN.	P.C.	P.C.
PL24-2	BI-LEVEL WALL MOUNTED DRINKING FOUNTAIN	N.A.	1/2"	PROVIDE VALVED WATER LINE AND DRAIN.	P.C.	P.C.
PL24B-2	BI-LEVEL WALL MOUNTED DRINKING FOUNTAIN WITH BOTTLE FILLER	N.A.	1/2"	PROVIDE VALVED WATER LINE AND DRAIN.	P.C.	P.C.
PLBPWF	BAKERY & PRODUCE WATER FILTER SYSTEM	N.A.	3/4"	PROVIDE NMPT VALVED COLD WATER LINE AND WATTS #LF7 CHECK VALVE.	OWNER	P.C.
PLC-1B	COUNTER TOP SINK	1/2"	1/2"	PROVIDE VALVED WATER LINES AND DRAIN	P.C.	P.C.
PLC-2B	COUNTER TOP SINK	1/2"	1/2"	PROVIDE VALVED WATER LINES AND DRAIN	P.C.	P.C.
PLDWF1	DELI SINGLE COMBI OVEN WATER FILTER SYSTEM	N.A.	3/4"	PROVIDE NMPT VALVED COLD WATER LINE AND WATTS #LF7 CHECK VALVE.	OWNER	P.C.
PLDWF2	DELI DOUBLE COMBI OVEN WATER FILTER SYSTEM	N.A.	3/4"	PROVIDE NMPT VALVED COLD WATER LINE AND WATTS #LF7 CHECK VALVE.	OWNER	P.C.
PLHSW	HAND SINK (WALL MOUNT)	1/2"	1/2"	PROVIDE VALVED WATER LINES AND DRAIN. PROVIDE BACKFLOW PREVENTER	OWNER	P.C.
PLHSWE	COMB. HAND SINK & EYE WASH (WALL MOUNT)	1/2"	1/2"	PROVIDE VALVED WATER LINES & DRAIN. PROVIDE BACKFLOW PREVENTER & ETV	OWNER	P.C.
PLPROWS	PRODUCE REVERSE OSMOSIS WATER SYSTEM	N.A.	1/2"	PROVIDE NPT VALVED COLD WATER LINE	OWNER	P.C.
PLSFWF	SEAFOOD FILTER SYSTEM	N.A.	3/4"	PROVIDE MNPT VLAVED COLD WATER LINE	OWNER	P.C.
PLTLF	FLOOR SET FLUSH VALVE WATER CLOSET	N.A.	1"	PROVIDE VALVE WATER LINES AND DRAIN	P.C.	P.C.
PLTLFH	FLOOR SET FLUSH VALVE WATER CLOSET (ACCESSIBLE)	N.A.	1"	PROVIDE VALVE WATER LINES AND DRAIN	P.C.	P.C.
PLUR	URINAL (ACCESSIBLE)	N.A.	3/4"	PROVIDE VALVE WATER LINES AND DRAIN	P.C.	P.C.
R87	RECONSTITUTION WATER DISPENSER	N/A	1/2"	CONNECTION TO WATER LINE AT SINK IS REQUIRED	P.C.	P.C.
S7	MINI-COMBINATION OVEN/STEAMER (NUVU)	N.A.	1/4"	STUB VALVED WATER LINE 3' - 6" A.F.F. FEED FROM WATER FILTER	OWNER	P.C.
S36TSC-8	SELF-CONTAINED ICE FLAKER (1000 LB.)	N.A.	1/2"	PROVIDE A 3/8" (20-120PSIG) VALVED & FILTERED COLD WATER LINE AND 2" HUB DRAIN.	OWNER	P.C.
S204SC2	2 DOOR SEAFOOD STORAGE FREEZER (REMOTE)	N.A.	N.A.	2" HUB DRAIN	OWNER	P.C.
TET1	THERMAL EXPANSION TANK	N.A.	N.A.	PROVIDE EXPANSION TANK. REFER TO SPECIFICATION SECTION 221100 FACILITY WATER DISTRIBUTION. NO CHECK VALVE OR OTHER CONTROL VALVE SHALL BE INSTALLED BETWEEN THE WATER HEATER TANK AND THE THERMAL EXPANSION TANK	P.C.	P.C.
WH	WALL HYDRANT (EXTERIOR FROST-PROOF HOSE BIBB)	N/A	3/4"	MOUNT 2'-0" ABOVE FINISHED GRADE. SEE SPECS. PROVIDE A #1012 BACKFLOW PREVENTER. REFER TO DETAIL PSD-15D.	P.C.	P.C.

2" REFERENCE LINE

OWNERSHIP OF INSTRUMENTS OF SERVICE
All reports, plans, specifications, computer files, field data, notes and other documents and instruments prepared by the Consultant as instruments of service shall remain the property of the Consultant. The Consultant shall retain all common law, statutory and other reserved rights, including, without limitation, the copyright thereto.

11/1/2018 2:04:40 PM

creating extraordinary places
www.cr-architects.com
800.469.4949
architecture + design
CINCINNATI 600 Vine Street suite 2210 Cincinnati, OH 45202 P 513.721.8080
DENVER 1675 Broadway suite 2400 Denver, CO 80202 P 800.469.4949
DALLAS 750 North St Paul Street suite 450 Dallas, TX 75201 P 800.469.4949
SEATTLE 506 2nd Avenue suite 2800 Seattle, WA 98104 P 800.469.4949

CONSULTANTS

KLH ENGINEERS
MECHANICAL/ELECTRICAL ENGINEERS
WWW.KLHENGRS.COM
LEXINGTON, KENTUCKY
LOUISVILLE, KENTUCKY
COLUMBUS, OHIO
NEW YORK, NEW YORK
1538 ALEXANDRIA PIKE, SUITE 11
FT. THOMAS, KENTUCKY 41075
800-354-9783 859-442-8050
859-442-8058 FAX

OWNER

Kroger

DATE	ISSUE
10/23/2018	90% OWNER REVIEW
11/01/2018	100% BID/PERMIT

#	DATE	REVISION

PROJECT TITLE
KROGER STORE R543

MERCURY BLVD.
HAMPTON, VA

COMMISSION NO. 517315
ISSUE DATE 10/23/2018
SHEET TITLE
PLUMBING SCHEDULES

SHEET NO.
P6.1

©2017 Cole+Russell Architects, Inc.