



- GENERAL DEMOLITION NOTES:**
1. ITEMS TO BE DEMOLISHED ARE SHOWN IN BOLD, OUTLINE IN BOLD AS DESCRIBED HEREIN.
 2. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY THAT ALL EXISTING UTILITIES, SLABS, FOOTINGS, SLABS, DEBRIS, ETC., THAT MAY CONFLICT WITH THE PROPOSED CONSTRUCTION HAVE BEEN REMOVED.
 3. DEMOLITION DEBRIS REMOVAL OR REUSE MATERIALS MAY NOT CONTACT WITH THE PROJECT AT A MINIMUM DEPTH OF 18" THROUGHOUT THE SITE.
 4. CONTRACTOR IS TO COORDINATE DESTRUCTION OF GAS, TELEPHONE, TELEVISION, AND POWER UTILITIES WITH RESPECTIVE COMPANIES.
 5. IF CONTRACTOR ENCOUNTERS ANY SUSPICIOUS, POSSIBLY HAZARDOUS MATERIALS, HE SHALL IMMEDIATELY NOTIFY THE OWNER'S REPRESENTATIVE.
 6. THE DEMOLITION OF EXISTING BUILDINGS SHALL CONFORM TO ALL LOCAL, STATE, & FEDERAL REGULATIONS PERTAINING TO SUCH WORK. ALL MATERIALS SHALL BE DISPOSED OF OFFSITE. NO MATERIALS SHALL BE BURIED ON-SITE.
 7. TREE, SHRUB AND VEGETATION REMOVAL IS A PART OF CLEANING AND GRUBBING. THE REMOVAL OF ALL VEGETATION INCLUDES THE ROOTS AND ASSOCIATED ORGANIC MATTER.
 8. TREES AND OTHER VEGETATION ARE REMOVED, THE CONTRACTOR SHALL FILL THE VOID WITH SELECT FILL APPROVED BY THE OWNER'S REPRESENTATIVE, AND COMPACTED TO A MINIMUM OF 98% MAXIMUM DRY DENSITY AT 4" PLACED LAYERS UNLESS OTHERWISE SPECIFIED. REMOVAL OF ALL MATERIALS SHALL BE SAWCUT PRIOR TO DEMOLITION.
 9. PAVEMENTS OR CURBING AND PARTIAL SECTIONS DEMOLISHED SHALL BE SAWCUT PRIOR TO DEMOLITION.
 10. CONTRACTOR TO REFER TO GEOTECH REPORT AND FOLLOW RECOMMENDED PREVENTATIVE MEASURES BEFORE CONSIDERING UNSUITABLE SOILS.



G:\A-ACTIVE JOB FILES\2018-07-17 - MURPHEY MIDDLE SCHOOL PE BUILDING AND PARKING IMPROVEMENTS\AC-DRAWINGS\20180717_0404.DWG 11/27/2018 9:56 AM

E
D
C
B
A

Order Plans @

BRANSTON
ENGINEERING
ENGINEERS - PLANNERS - SURVEYORS
450 Ellis Street, Augusta, Georgia 30901
Post Office Box 2000, Augusta, Georgia 30903
main@branstonee.com
branstonee.com



Murphey Middle School PE Building
Existing Conditions & Demolition Plan

DRAWN BY: MAB/RDS
CHECKED BY: TMP
APPROVED BY: MMB
DATE: NOVEMBER 2, 2018
SCALE: 1" = 40'
JOB No. 2018-0178
DRAWING No. C300



Member of the American Institute of Architects

PROJECT TITLE:
MURPHEY MIDDLE SCHOOL PE BUILDING PROJECT # B-17-005-3756.1

REVISIONS			
REV #	DATE	APPRD BY	REVISION
1	11/29/18	MMB	STATE FINAL
2	11/29/18	MMB	ISSUE FOR BID

DA PROJECT NUMBER & NAME:
1707.1

DRAWING TITLE:
EXISTING CONDITIONS & DEMOLITION PLAN

DRAWING NO.:

C300