ELECTRICAL EQUIPMENT SCHEDULE

ITEM NO.	QTY	DESCRIPTION	FURNISHED BY	INSTALLED BY	MANUFACTURER	VOLTAGE	PHASE	LOAD	CIRCUIT/WIRING INFO	DISCONNECT DESCRIPTION	REMARKS
0125	1	RACETRAC CANDY ISLAND WITH OVAL BASE	RT	VENDOR	BROWN INDUSTRIES	120 V	1	2.5 A	2#12, 1#12G IN 1/2"C		
1003	2	HAND DRYER	RT	GC	BOBRICK	120 V	1	1725 W	2#12, 1#12G IN 1/2"C	DIRECT CONNECT	
2002	5	VANITY SINKS	RT	GC	KOHLER	120 V	1	VERIFY	2#12, 1#12G IN 1/2"C	DIRECT CONNECT - VIA POWER CONVERTER	
2003	2	LAVATORY FOR ACCESSIBLE STALLS (HARD WIRED FAUCET)	RT	GC	ZURN	120 V	1	VERIFY	2#12, 1#12G IN 1/2"C	DIRECT CONNECT - VIA POWER CONVERTER	
2004	2	URINAL	RT	GC	ZURN	120 V	1	VERIFY	2#12, 1#12G IN 1/2"C	DIRECT CONNECT - VIA POWER CONVERTER	
2019	4	WATER CLOSET	RT	GC	ZURN	120 V	1	VERIFY	2#12, 1#12G IN 1/2"C	DIRECT CONNECT - VIA POWER CONVERTER	
3002	2	TEA BREWER	RT	VENDOR	BUNN	120 V	1	14.4 A	2#12, 1#12G IN 1/2"C	CORD & PLUG - NEMA 5-15	
3004	2	10 HEAD SODA FOUNTAIN	RT	VENDOR	CORNELIUS	120 V	1	3.5 A	2#12, 1#12G IN 1/2"C	CORD & PLUG - NEMA 5-15	
3005	3	POST MIX SODA SYSTEM	RT	VENDOR	CORNELIUS	120 V	1	14.6 A	2#12, 1#12G IN 1/2"C	CORD AND PLUG - NEMA 5-20	
3007	2	GRANITA MACHINE	RT	VENDOR	BUNN	120 V	1	12.0 A	2#12, 1#12G IN 1/2"C	CORD & PLUG - NEMA 5-15	
3008	1	CAPPUCCINO DISPENCER - 5 HEAD	RT	GC	BUNN	120 V	1	15 A	2#12, 1#12G IN 1/2"C	CORD & PLUG - NEMA 5-15	
3011	2	COMBI OVEN STEAMER	RT	GC	CLEVELAND	208 V	3	17.9 A	3#10, 1#10G IN 3/4"C	CORD AND PLUG - NEMA 15-30	
3013	1	WATER HEATER (50 GAL - SHORT)	RT	GC	RHEEM	208 V	3	25.0 A	3#8, 1#10G IN 3/4"C	DIRECT CONNECT - DISCONNECT SWITCH	
3014	2	FCB VIPER (FROZEN CARBONATED BEVERAGE)	RT	VENDOR	FBD	208 V	1	30.0 A	2#10, 1#10G IN 3/4"C	CORD & PLUG - NEMA L6-30	
3017	5	BEAN TO CUP COFFEE MACHINE	RT	GC	SCHAERER	208 V	1	20 A	2#12, 1#12G IN 1/2"C	CORD & PLUG - NEMA 6-20	
4001	18	COOLER #1 DISPLAY DOOR	RT	GC	ANTHONY	120 V	1	VERIFY	2#12, 1#12G IN 1/2"C	DIRECT CONNECT	
4011	1	ICE MAKER (CUBER)	RT	VENDOR	ICE-O-MATIC	208 V	1	14.7A	2#12, 1#12G IN 1/2"C	CORD & PLUG - NEMA 6-20	
4012	1	ICE MAKER REMOTE CONDENSER (CUBER)	RT	VENDOR	ICE-O-MATIC	208 V	1	VERIFY	2#12, 1#12G IN 1/2"C	DIRECT CONNECT - DISCONNECT SWITCH (SERVES 4011)	
4013	1	ICE MAKER (CRUSHED/NUGGET)	RT	VENDOR	ICE-O-MATIC	208 V	1	15.3 A	2#12, 1#12G IN 1/2"C	CORD & PLUG - NEMA 6-20	
4014	1	ICE MAKER REMOTE CONDENSER (CRUSHED NUGGET)	RT	VENDOR	ICE-O-MATIC	208 V	1	VERIFY	2#12, 1#12G IN 1/2"C	DIRECT CONNECT - DISCONNECT SWITCH (SERVES 4013)	
4025	4	SOFT SERVE FREEZERS	RT	GC	STOELTING	208 V	1	12.0 A	2#12, 1#12G IN 1/2"C	CORD & PLUG - NEMA 6-20	
4033	2	TWO DOOR REFRIGERATOR	RT	GC	TURBO AIR	120 V	1	9.2 A	2#12, 1#12G IN 1/2"C	CORD AND PLUG - NEMA 5-15	
4065	1	BULLET IMPULSE COOLER (4 FT.)	RT	GC	HILLPHOENIX	120 V	1	1.0 A	2#12, 1#12G IN 1/2"C	VERIFY	
4096	1	YOGURT MACHINES CHILLER - PAK	RT	GC	AIRDYNE	208 V	3	13.1 A	3#12, 1#12G IN 3/4"C	DIRECT CONNECT - DISCONNECT SWITCH (MOCP [illegible]5A)	
4105	1	BULLET SANDWICH COOLER (6 FT.)	RT	GC	HILLPHOENIX	120 V		1.55 A	2#12, 1#12G IN 1/2"C		
4113	1	BEER COOLER CONDENSER	RT	GC	BOHN	208 V	3	21 MCA	3#10, 1#8G IN 3/4"C	DIRECT CONNECT - DISCONNECT SWITCH (MOCP [illegible]A)	
4114	1	BULLET SANDWICH COOLER CONDENSER	RT	GC	BOHN	208 V	3	20 MCA	3#10, 1#10G IN 3/4"C	DIRECT CONNECT - DISCONNECT SWITCH (MOCP 20 / SERVES 4065)	
4115	1	NON-ALCH COOLER CONDENSER	RT	GC	BOHN	208 V	3	21 MCA	3#10, 1#10G IN 3/4"C	DIRECT CONNECT - DISCONNECT SWITCH (MOCP 30A)	
4116	1	FREEZER CONDENSER	RT	GC	BOHN	208 V	3	24 MCA	3#8, 1#10G IN 3/4"C	DIRECT CONNECT - DISCONNECT SWITCH (MOCP 25A)	
4117	1	BULLET IMPULSE COOLER CONDENSER	RT	GC	BOHN	208 V	3	20 MCA	3#10, 1#10G IN 3/4"C	DIRECT CONNECT - DISCONNECT SWITCH (MOCP 20 / SERVES 4065)	
4118	1	FREEZER EVAPORATOR	RT	GC	BOHN	208 V	1	15.0 A	2#12, 1#12G IN 1/2"C	DIRECT CONNECT - DISCONNECT SWITCH	
4119	5	WALK-IN COOLER EVAPORATOR	RT	GC	BOHN	120 V	1	8.1 A	2#12, 1#12G IN 1/2"C	DIRECT CONNECT - DISCONNECT SWITCH	
5001	1	COIN SAFE	RT	GC	TIDEL	120 V	1	VERIFY	2#12, 1#12G IN 1/2"C	VERIFY	
5002	1	INTERCOM ESCO	RT	GC	ESCO	120 V	1	VERIFY	2#12, 1#12G IN 1/2"C	VERIFY	
5003	1	COMPUTER SYSTEM	RT	RT	-	120 V	1	VERIFY	2#12, 1#12G IN 1/2"C	CORD AND PLUG - NEMA 5-15	
5004	1	FAX/PRINTER	RT	RT	-	120 V	1	VERIFY	2#12, 1#12G IN 1/2"C	CORD AND PLUG - NEMA 5-20	
5006	3	46 INCH COMMERCIAL DISPLAY	RT	RT	AT&T	120 V	1	VERIFY	2#12, 1#12G IN 1/2"C	CORD AND PLUG - NEMA 5-15	
5007	1	BILL SAFE	RT	GC	TIDEL	120 V	1	VERIFY	2#12, 1#12G IN 1/2"C	VERIFY	
5008	3	CASH DRAWER	RT	GC	APG					POWERED BY UPS	
5009	3	POINT OF SALE TERMINAL	RT	RT	RADIANT					POWERED BY UPS	
5010	3	POINT OF SALE SCANNER	RT	RT	MOTOROLA					POWERED BY UPS	
5011	4	POINT OF SALE PRINTER	RT	RT	BIXOLON					POWERED BY UPS	
5012	3	UPS POWER SUPPLY	RT	GC	ONEAC	120 V	1	VERIFY	2#12, 1#12G IN 1/2"C	CORD & PLUG - NEMA 5-15 / (120V OUTPUT)	
5013	2	YOGURT SALES	RT	RT	AWS	120 V	1	10 W	2#12, 1#12G IN 1/2"C	CORD & PLUG - NEMA 5-15	
5014	1	FOOD WARMER WITH PUMP (YOGURT TOPPINGS)	RT	GC	SERVER	120 V	1	[illegible] A	2#12, 1#12G IN 1/2"C	CORD AND PLUG - NEMA 5-15	
5015	1	PASTRY CASE	RT	GC	ROYSTON	120 V	1	[illegible] A	2#12, 1#12G IN 1/2"C	CORD & PLUG - NEMA 5-15	
5016	4	CIGARETTE MERCHANDISER	RT	VENDOR	IMAGEWORKS	120 V	1	VERIFY	2#12, 1#12G IN 1/2"C	VERIFY	
5021	1	BEVERAGE AIR CENTER	RT	VENDOR	TAPRITE-FASSCO	120 V	1	1/4 HP	2#12, 1#12G IN 1/2"C	CORD AND PLUG - NEMA 5-20	
5022	1	WATER BOOSTER	RT	VENDOR	McCANN'S	120 V	1	7.0 A	2#12, 1#12G IN 1/2"C	CORD AND PLUG - NEMA 5-20	
5025	3	ROLLER GRILL	RT	GC	STAR	120 V	1	12.8 A	2#12, 1#12G IN 1/2"C	CORD AND PLUG - NEMA 5-15	
5026	2	MICROWAVE OVEN	RT	GC	PANASONIC	120 V	1	17.7 A	2#12, 1#12G IN 1/2"C	CORD AND PLUG - NEMA 5-20	
5028	1	CHILI / CHEESE W/ CHIP RACK	RT	GC	GEHLS	120 V	1	1.7 A	2#12, 1#12G IN 1/2"C	CORD & PLUG - NEMA 5-15	
5029	1	AUTOMATED TELLER MACHINE (ATM)	RT	GC	NCR	120 V	1	10.0 A	2#12, 1#12G IN 1/2"C	CORD AND PLUG - NEMA 5-20	
5034	1	COLD PAN (COFFEE PREP)	RT	GC	DELFIELD	120 V	1	4.0 A	2#12, 1#12G IN 1/2"C	CORD & PLUG - NEMA 5-15	
5039	6	VARIABLE FREQUENCY CONTROLLER	RT	GC	FE PETRO	208 V	3		3#10, 1#10G IN 3/4"C	VERIFY	
5040	2	FOOD WARMER BOILED PEANUTS	RT	GC	WELLS MANUFRACTURING	120 V	1	6.9 A	2#12, 1#12G IN 1/2"C	CORD & PLUG - NEMA 5-15	
5041	4	SECURITY MONITORS	RT	GC	SAMSUNG	120 V	1	54W	2#12, 1#12G IN 1/2"C	CORD & PLUG - NEMA 5-15	
5042	1	UNITIZED PANEL SYSTEM	RT	GC	SCHNEIDER-ELECTRIC		-	-	-	-	
5043	1	INSTANT TICKET VENDING MACHINE (GA)	RT	GC	-	120 V	1	VERIFY			
5044	2	ICE MERCHANDISER	VENDOR	VENDOR	REDDY ICE	120 V		VERIFY	2#12, 1#12G IN 1/2"C	VERIFY	
5046	1	HOT CASE	RT	GC	VENDO	120 V	1	9.2 A	2#12, 1#12G IN 1/2"C	CORD & PLUG - VERIFY	
5055	2	POWER CONVERTER	RT	GC		120 V	1	2.0 A	VERIFY WITH SUPPLIER	DIRECT CONNECT	
5059	2	SINGLE FOOD WARMER WITH PUMP (YOGURT TOPPINGS)	RT	GC	SERVER	120 V	1	2.0 A	2#12, 1#12G IN 1/2"C	CORD AND PLUG - NEMA 5-15	
5064	1	YOGURT COLDPAN	RT	GC	DELFIELD	120 V	1	1/5 HP	2#12, 1#12G IN 1/2"C	CORD & PLUG - NEMA 5-15	
5067	1	PIZZA PREP STATION	RT	GC	DUKE	120 V	1	9.3 A	2#12, 1#12G IN 1/2"C	CORD AND PLUG - NEMA 5-20	
5069	1	HOLDING CABINET	RT	GC	DUKE	208 V	1	16 A	2#10, 1#10G IN 3/4"C	CORD AND PLUG - NEMA L6-20P	
5071	1	BUMP BAR	RT	GC	NCR					POWERED THROUGH SERIAL PORT FROM KPS CONTROLLER	
5074	4	POS BATTERY BACKUP	RT	GC	GTS	120 V	1	2.0 A	2#12, 1#12G IN 1/2"C	CORD & PLUG - NEMA 5-15 / (OUTPUT: 120V)	
5078	1	MTO MEASURING SCALE	RT	RT	TAYLOR	120 V	1	1.0 A	2#12, 1#12G IN 1/2"C	CORD & PLUG - NEMA 5-15 (AC ADAPTER)	
5083	1	SINGLE DOOR WINE COOLER 54 IN TALL	RT	GC	EXCELLENCE INDUSTRIES	120 V	1	6.5 A	2#12, 1#12G IN 1/2"C	CORD & PLUG - NEMA 5-15	
5084	1	DOUBLE BATCH PIZZA OVEN	RT	GC	TURBOCHEF	208 V	1	50.0 A	2#6, 1#10G IN 1"C	CORD AND PLUG - NEMA 6-50	
5085	2	BUN WARMER	RT	GC	APW WYOTT	120 V	1	4.0 A	2#12, 1#12G IN 1/2"C	CORD & PLUG - NEMA 5-15	
5086	1	FOOD LABEL PRINTER	RT	GC	AVERY DENNISON	120 V	1	1.5 A	2#12, 1#12G IN 1/2"C	CORD AND PLUG - NEMA 5-15	
5091	1	DOUBLE STACK PIZZA FREEZER BASE	RT	GC	RANDELL	120 V	1	7.8 A	2#12, 1#12G IN 1/2"C	CORD AND PLUG - NEMA 5-15	
5093	1	IPAD	RT	GC	APPLE					-	
5097	1	ICE MERCHANDISER	VENDOR	VENDOR	REDDY ICE	120 V		VERIFY	2#12, 1#12G IN 1/2"C	VERIFY	
5098	3	PANIC BUTTON	RT	RT	HUB					POWERED BY UPS	
5099	1	MONEYGRAM	RT	GC	-	120 V	1	2.0 A	2#12, 1#12G IN 1/2"C	CORD & PLUG - NEMA 5-15 / (OUTPUT: 120V)	
5101	1	EMERGENCY FUEL SHUTOFF	RT	RT	-					-	
5111	1	HIGH SPEED OVEN	RT	GC	TURBO CHEF	208 V	1	30.0 A	2#10, 1#10G IN 3/4"C	CORD AND PLUG - NEMA 6-50	
5125	1	WORKTOP REFRIGERATOR	RT	GC	TURBO AIR	120 V	1	7.8 A	2#12, 1#12G IN 1/2"C	CORD AND PLUG - NEMA 5-15	

EQUIPMENT SCHEDULE ELECTRICAL GENERAL NOTES

1. E.C. SHALL COORDINATE WITH EQUIPMENT SUPPLIER/MANUFACTURER AND PROVIDE ALL OUTLETS, CONNECTIONS AND CORD AND PLUGS SETS REQUIRED FOR COMPLETE INSTALLATION.
2. E.C. SHALL VERIFY WITH EQUIPMENT SUPPLIER/MANUFACTURER NEMA CONFIGURATION REQUIRED FOR EACH PIECE OF EQUIPMENT UTILIZING CORD AND PLUG AS A DISCONNECTING MEANS.
3. E.C. SHALL PROVIDE DISCONNECT SWITCHES PER EQUIPMENT SUPPLIER RECOMMENDATIONS, VERIFY FUSING REQUIREMENTS WITH EQUIPMENT SUPPLIER/MANUFACTURER.

RaceTrac
COPYRIGHT NOTICE
THESE PLANS ARE SUBJECT TO FEDERAL COPYRIGHT LAWS: ANY USE OF SAME WITHOUT THE EXPRESSED WRITTEN PERMISSION OF RACETRAC PETROLEUM, INC. IS PROHIBITED. 2018 RACETRAC PETROLEUM INC.

DESIGN PROFESSIONALS

HILLFOLEYROSS & ASSOCIATES
ARCHITECTURE
ENGINEERING
3680 Pleasant Hill Road
Suite 200
Duluth, Georgia 30096
p 770.622.9858
f 770.622.9535
www.hillfoleyrossi.com

© Copyright (as dated below). This drawing and all reproductions thereof are the property of Hill Foley Rossi & Associates, LLC (HFR). It is intended for the sole use of the project named hereon. Reproduction without the written consent of HFR is unlawful. All copies are to be returned to HFR upon project completion.

ISSUE/REVISION RECORD

DATE	DESCRIPTION
2018.08.22	PERMIT ISSUE

RaceTrac
RACETRAC PETROLEUM, INC.
200 GALLERIA PKWY SE
SUITE 900
ATLANTA, GEORGIA 30339
(770) 431-7600

PROJECT NAME
GRIFFIN

GRIFFIN
GEORGIA
1638 US HWY 41
GRIFFIN, GA 30223

RACETRAC PROJECT NUMBER
#1242

PROTOTYPE SERIES 5.5K 2.0
2018 LH MO

PLAN MODIFICATION NOTICE
SPB NO. DATE

STANDARD PLAN BULLETINS (SPB) MODIFY THE PROTOTYPE SERIES SET NOTED ABOVE. THE LISTED SPB REPRESENTS THE LATEST MODIFICATION INCORPORATED TO THIS PROTOTYPE SERIES SET AT ORIGINAL RELEASE. THE ISSUE/REVISION RECORD COLUMN ABOVE LISTS ANY REVISIONS OR SPB INCORPORATED IN THIS SET AFTER THE ORIGINAL RELEASE. CONTACT RACETRAC ENGINEERING AND CONSTRUCTION FOR ANY SUBSEQUENT BULLETINS NOT INCORPORATED HEREIN.

PROFESSIONAL SEAL
GEORGIA REGISTERED No. 26276 PROFESSIONAL ENGINEER WILLIAM S. GADDY, JR.
08/22/18

PROJECT NUMBER
17.721.00

SHEET TITLE
ELECTRICAL EQUIPMENT SCHEDULE

SHEET NUMBER
E002

ISSUED FOR PERMIT

Order Plans @ www.LDIline.com