FINISH SCHEDULE

ID	MANUFACTURER	MATERIAL	FINISH	COMMENTS
BASE				
B-2	EMSER	QUARRY COVER BASE; E-QUARRY BEIGE 6x6		GROUT G-1
B-7	EMSER	AMBIANCE, FIJI MATTE, 6"x12"		GROUT G-1
B-8	EMSER	PERSPECTIVE COVE BASE; 6"X12", GRAY		GROUT G-1
B-9	EMSER	PERSPECTIVE COVE BASE CORNER; 1"X6", GRAY		GROUT G-1
CARPET				
C-1	--	ANTIFATIGUE MAT	-	FURNISHED BY RACETRAC; FLAME SPREAD AND SMOKE DEVELOPMENT TO MEET 'CLASS A'
CEILING				
CL-1	ARMSTRONG	24"x48" #2712 DUNE SECOND LOOK	WHITE	15/16" WHITE GRID; ASTM E84 FLAME SPREAD INDEX 25 OR LESS, SMOKE DEVELOPED INDEX 50 OR LESS
CL-2	ARMSTRONG	24"x48" #793 GEORGIAN - HIGH WASHABILITY	WHITE	15/16" WHITE GRID; ASTM E84 FLAME SPREAD INDEX 25 OR LESS, SMOKE DEVELOPED INDEX 50 OR LESS
CL-3	--	GYPSUM BOARD WITH PAINTED FINISH	-	GYPSUM BOARD SELECTED MUST MEET FLAME SPREAD AND SMOKE DEVELOPMENT 'CLASS A'
PAINT				
IP-4	SHERWIN WILLIAMS	7007 CEILING BRIGHT WHITE, BRILLIANCE HIGH PERFORMANCE	FLAT	GYPSUM BOARD SELECTED FOR INTERIOR FINISHES MUST MEET FLAME SPREAD AND SMOKE DEVELOPMENT 'CLASS A'
IP-6	SHERWIN WILLIAMS	7014 EIDER WHITE	HIGH-GLOSS	GYPSUM BOARD SELECTED FOR IN SERIOR FINISHES MUST MEET FLAME SPREAD AND SMOKE DEVELOPMENT 'CLASS A'
IP-7	SHERWIN WILLIAMS	7014 EIDER WHITE	SEMI-GLOSS	
IP-10	SHERWIN WILLIAMS	7015 REPOSE GREY	SEMI-GLOSS	
TILE				
FT-2	EMSER	6"X6" E-QUARRY TILE, BEIGE		INSTALLED AT 90 DEGREES WITH 3/8" SPACING; GROUT G-1
FT-8	EMSER	6"X36" ALPINE IN CAFE PORCELAIN TILE		INSTALL BRICKS IN STRAIGHT STAGGERED PATTERN WITH OFFSET NOT TO EXCEED 33%
FT-9	EMSER	CITADEL GRAY 24"X24"		INSTALLED AT 45 DEGREES WITH 1/8" SPACING; GROUT G-1
WT-5	EMSER	3"X6" SEMPLICE IN WHITE		INSTALL TILE IN RUNNING BOND PATTERN; GROUT G-1
WT-7	EMSER	EMSER 12X24 JAZZ RIPPLE WHITE, GLOSS FINISH		STRAIGHT LAY TILE PATTERN, 1/8" GROUT LINE; GROUT G-4
WT-9	EMSER	AMBIANCE FIJI MATTE 12"X24"		RUNNING BOND PATTERN; GROUT G-2; 3/16" GROUT LINE
WALL CLADDING				
FRP-1	MARLITE	P100 WHITE	WHITE	
WALL COVERING				
WC-1	--	BRAND WALL COVERING - RED	VINYL	MANUFACTURER, PRODUCT LINE, PROVIDED BY RACETRAC; FLAME SPREAD AND SMOKE DEVELOPMENT TO MEET 'CLASS A'
WC-8	--	COOLER WALL COVERINGS - BUBBLES		MANUFACTURER, PRODUCT LINE, PROVIDED BY RACETRAC; FLAME SPREAD AND SMOKE DEVELOPMENT TO MEET 'CLASS A'
WC-9	--	BEER/WINE GRAPHIC WALL COVERING		MANUFACTURER, PRODUCT LINE, PROVIDED BY RACETRAC; FLAME SPREAD AND SMOKE DEVELOPMENT TO MEET 'CLASS A'
WC-10	--	COFFEE WALL GRAPHIC WALL COVERING		MANUFACTURER, PRODUCT LINE, PROVIDED BY RACETRAC; FLAME SPREAD AND SMOKE DEVELOPMENT TO MEET 'CLASS A'
WINDOW FILM				
WF-1		WINDOW FILM; 3M PRESTIGE 70 SOLAR FILM		
WF-2		WINDOW FILM; OPAQUE		
FLASHING/WEEPS				
FL-1	-	STAINLESS STEEL THROUGH WALL FLASHING	COLOR TO MATCH BR-1	INSTALL AT ALL THROUGH WALL FLASHING LOCATIONS AND UNLESS NOTED OTHERWISE
FL-2	-	ANODIZED ALUMINUM SILL FLASHING AND TRIM	ANODIZED BRONZE TO MATCH STOREFRONT	INSTALL AT ALL WINDOW SILL S AND LOCATIONS ADJACENT TO ACM PANELS
WP-1	HOHMANN AND BARNARD, INC.	QV MICRO VENT	CLEAR	1/4" WIDTH, SEE SHEET C100. USE FOR EXTERIOR BRICK MORTAR
EXTERIOR SHEATHING				
ES-1	GEORGIA-PACIFIC GYP	5/8" DENSGLASS EXTERIOR SHEATHING		SCREW SIZE TO MATCH MANUFACTURER SPECIFICATIONS: # 6 x 1/4" BUNGLE HEAD SCREW
		5/8" EXT. GRADE CDX PLYWOOD SHEATHING: #10 TEKS SCREW @ 6" O.C.		

DENSGLASS SHEATHING ATTACHMENT CHART

WIND SPEED (MPH)	SCREWS (IN/O.C.)
110-169	8
170-215	6

NOTES: PROJECTS MUST ADHERE TO THE FOLLOWING REQUIREMENTS:
1. 5/8" THICK DENSGLASS MINIMUM.
2. 18 GAUGE STUD (MIN).
3. 16" O.C. STUD SPACING.
4. SCREWS DETERMINED BY MANUFACTURER.
5. SEE BUILDING WIND DESIGN FOR WIND SPEED.
6. WIND SPEED DETERMINED

MASONRY TIES				
MT-1	HOHMANN & BARNARD, INC.	HB-213 ADJUSTABLE VENEER ANCHOR		BRICK TO STUD
MT-2	HOHMANN & BARNARD, INC.	#170-2X LOX-ALL ADJUSTABLE TRUSS EYE-WIRE LADDER REINFORCEMENT		BRICK TO CMU
MT-3	HECKMAN	POS-I-TIE VENEER ANCHOR		CULTURED STONE VENEER ANCHOR ORIENTED VERTICALLY.
BUILDING INSULATION - BASIS OF DESIGN				
INS-1	JOHNS MANSVILLE	ROOF INSULATION - RIGID INSULATION R-20 FLAME SPREAD 25 OR LESS. SMOKE DEVELOPED OF 0-450		
INS-2	JOHNS MANSVILLE	EXTERIOR WALL INSULATION - BATT INS. R-19 FLAME SPREAD 25 OR LESS		
INS-3	JOHNS MANSVILLE	8" CMU INSULATION: CORE FILL 500 R VALUE - 14.2. FLAME SPREAD - 0. SMOKE DENSITY - 5		
WEATHER BARRIER				
WB-1	STO	STO GUARD GOLD COAT VAPOR PERMEABLE FLUID-APPLIED WATER BARRIER MEMBRANE WITH PVC STARTER STRIP/WEEP AND METAL FLASHING AS RECOMMENDED BY MANUFACTURER		
GROUT				
G-1	MERKRETE	MERKRETE PROGROUT #00525 BLACK SAPPHIRE		FLOORS AND WALLS
G-2	MERKRETE	MERKRETE PROGROUT #00012 NAVAJO WHITE		BATHROOMS WALLS
G-4	MERKRETE	MERKRETE PROGROUT #00010 BRIGHT WHITE		YOGURT WALLS
SEALANT				
SL-1	DOW CORNING	#790 SILICONE SEALANT "LIMESTONE"		
SL-2	TREMCO	SPECTREM #3 LOW-MODULUS SILICONE SEALANT "PRECAST WHITE"		USE AT EXPANSION JOINTS
SL-3	DOW CORNING	NEUTRAL CURE "CLEAR"		USE AT ALL EIFS PENETRATIONS
SL-5	PROSOCO SURE KLEAN	WEATHER SEAL SILOXANE PD WATER REPELLENT		USE AT CAST STONE

Order Plans @ WWW.DLINE.COM

RaceTrac.

COPYRIGHT NOTICE
THESE PLANS ARE SUBJECT TO FEDERAL COPYRIGHT LAWS: ANY USE OF SAME WITHOUT THE EXPRESSED WRITTEN PERMISSION OF RACETRAC PETROLEUM, INC. IS PROHIBITED. 2016 RACETRAC PETROLEUM INC.

DESIGN PROFESSIONALS

HILLFOLEYROSSI & ASSOCIATES
ARCHITECTURE
ENGINEERING
3680 Pleasant Hill Road
Suite 200
Duluth, Georgia 30096
p 770.622.9858
f 770.622.9535
www.hillfoleyrossi.com

© Copyright (as dated below)
This drawing and all reproductions thereof are the property of Hill Foley Rossi & Associates, LLC (HFR). It is intended for the sole use of the project named hereon. Reproduction without the written consent of HFR is unlawful. All rights are to be retained by HFR upon project completion.

ISSUE/REVISION RECORD

DATE	DESCRIPTION

RaceTrac.

RACETRAC PETROLEUM, INC.
200 GALLERIA PARKWAY SOUTHEAST
SUITE 900
ATLANTA, GEORGIA 30339
(770) 431-7600

PROJECT NAME

PEACHTREE PKWY & ENG.

PEACHTREE CORNERS
5780 PEACHTREE PKWY
PEACHTREE CORNERS, GA

RACETRAC STORE NUMBER

1201

PROTOTYPE SERIES 5.5K 2.0

2018 RH MO

PLAN MODIFICATION NOTICE

SPB NO. DATE

STANDARD PLAN BULLETINS (SPB) MODIFY THE PROTOTYPE SERIES SET NOTED ABOVE. THE LISTED SPB REPRESENTS THE LATEST MODIFICATION INCORPORATED TO THIS PROTOTYPE SERIES SET AT ORIGINAL RELEASE. THE ISSUE/ REVISION RECORD COLUMN ABOVE LISTS ANY REVISIONS OR SPB INCORPORATED IN THIS SET AFTER THE ORIGINAL RELEASE. CONTACT RACETRAC ENGINEERING AND CONSTRUCTION FOR ANY SUBSEQUENT BULLETINS NOT INCORPORATED HEREIN.

PROFESSIONAL SEAL

STATE OF GEORGIA
JON B. ERICKSON
CERTIFICATE NO. 030115
REGISTERED ARCHITECT
09/04/18

PROJECT NUMBER
18.703.00

SHEET TITLE

ROOM FINISH AND MATERIAL SCHEDULES

SHEET NUMBER

A500

ISSUED FOR PERMIT