



**WOODSPRING SUITES**  
 CYPRESS CREEK, FLORIDA  
 Pasco County  
 Cypress Creek, FL

Issues & Revisions:

COORDINATE WALL FRAMING W/ SHOWER / TUB CONTROLS (ON ALL FLOORS)

NOTE: SAW JOINTS OR KEYED CONSTRUCTION JOINTS IN SLABS SHALL BE SPACED TO DIVIDE SLABS INTO PANELS NOT TO EXCEED 225 SQUARE FEET. THE LONGER DIMENSION OF EACH PANEL SHALL NOT EXCEED THE SHORTER DIMENSIONS BY MORE THAN 20%. CONTRACTOR SHALL SUBMIT JOINT LAYOUT TO ARCHITECT FOR APPROVAL. REFER TO DETAILS 1/SO.1 & 2/SO.1.

Order Plans

**FOOTING AND FOUNDATION PLAN**

PLAN NOTES:  
 1. REFER TO ARCH. SHEET A6.1 FOR STAIRWELL AND LANDING DIMENSIONS & ELEVATIONS  
 2. WALL ELEVATIONS A/S6.1 & B/S6.1 INDICATE CORRIDOR WALL FRAMING AND CLP ROD LOCATIONS.

Proj. No.: 078761  
 Date: 10/02/2018  
 Sheet Name:  
 FTG. & FNDN.  
 PLAN

**S1.1**