

GENERAL ELECTRICAL NOTES

1.1 THE GENERAL CONDITIONS, GENERAL REQUIREMENTS, AND SPECIAL CONDITIONS SHALL BE AND ARE HEREBY MADE A PART OF THIS SECTION. THE ELECTRICAL CONTRACTOR SHALL FURNISH ALL LABOR, MATERIALS, TOOLS, TRANSPORTATION, EQUIPMENT, SERVICES AND FACILITIES REQUIRED FOR THE COMPLETE, PROPER AND SUBSTANTIAL INSTALLATION OF ALL ELECTRICAL WORK SHOWN ON THE DRAWINGS AND/OR OUTLINED IN THESE SPECIFICATIONS. THE INSTALLATION SHALL INCLUDE ALL MATERIALS, APPLIANCES AND APPARATUS NOT SPECIFICALLY IDENTIFIED HEREIN OR NOTED ON THE DRAWINGS, BUT WHICH ARE NECESSARY TO MAKE A COMPLETE WORKING INSTALLATION OF ALL ELECTRICAL SYSTEMS.

10.8 FINAL OBSERVATION WILL BE MADE UPON WRITTEN REQUEST FROM THE CONTRACTOR AFTER THE PROJECT IS COMPLETE. AT THE TIME OF FINAL OBSERVATION, THE CONTRACTOR SHALL BE PRESENT OR SHALL BE REPRESENTED BY A PERSON OF AUTHORITY. THE CONTRACTOR SHALL DEMONSTRATE, AS DIRECTED BY THE ARCHITECT/ENGINEER, THAT HIS WORK FULLY COMPLES WITH THE PURPOSE AND INTENT OF THE DRAWINGS AND SPECIFICATIONS. ALL LABOR, SERVICE, AND ALL INSTRUMENTS OR TOOLS NECESSARY FOR SUCH DEMONSTRATION AND TESTS SHALL BE PROVIDED BY THE CONTRACTOR.

25 CATV (TELEVISION) OUTLET SYSTEM
26 ELECTRICAL CONTRACTOR
A. ENTRANCE CONDUIT: THERE SHALL BE PROVIDED A 3" MINIMUM MAIN SERVICE CONDUIT FROM BELOW THE CATV TERMINAL BOARD TO THE PROPERTY LINE (UNLESS A LARGER SIZE IS NOTED OTHERWISE ON THE DRAWINGS OR REQUIRED BY THE CATV COMPANY). CONDUIT SIZING AND ROUTING TO BE PER THE REQUIREMENTS OF THE SERVING CATV COMPANY.

WOODSPRING SUITES
CYPRESS CREEK, FLORIDA
Pasco County
Cypress Creek, FL
Woolpert
Northridge Road
Suite 300
Atlanta, GA 30350
770.391.4095
FAX: 770.391.4104
ACERTUS CONSULTING GROUP, LLC
14817 West 95th Street
P.O. Box 2155
Kennesaw, GA 30144
P 770.322.5150
F 770.322.5155
www.AcertusGroup.com

11/20/2018 6:01:02 PM

Issues & Revisions:

Proj. No.: 078761
Date: 10/05/2018

Sheet Name: ELECTRICAL GENERAL NOTES

E-8

60% OWNER REVIEW | 09.10.18