

Order Plans @

Table: -- FAN SCHEDULE --

- (1) COMPLETE WITH BACKDRAFT DAMPER, ADAPTOR CURB, BIRDSCREEN AND DISCONNECT MEANS.
(2) CONTROL WITH FACILITY MANAGEMENT SYSTEM (OR TIME CLOCK).
(3) SWITCH WITH ROOM LIGHTS. FURNISH CONTACTORS AS REQUIRED.
(4) CONTROL WITH THERMOSTAT SET AT 85° (ADJ.).
(5) INTERLOCK CONTROL WITH DISHWASHER.
(6) CONTROL WITH FACILITY MANAGEMENT SYSTEM USING INTERVAL TIMER.
(7) CONTROL WITH WALL SWITCH BY DIV. 16.

Table: -- WALL MOUNT GAS UNIT --

- (1) NOT USED.
(2) FURNISH ION GENERATOR AS SCHEDULED.
(3) UNITS SHALL HAVE INTEGRAL DISCONNECTS AND HOT GAS REHEAT DEHUMIDIFICATION SYSTEM.
(4) UNITS SHALL HAVE WALL MOUNTED ADAPTOR CURB.

Table: -- INDOOR HEAT PUMP SCHEDULE --

- (1) RATINGS IN ACCORDANCE WITH A.S.I. STANDARD 240.
(2) PROVIDE GRAVITY FED CONDENSATE PUMP KIT FOR NEW INDOOR HEAT PUMP. RECTORSEAL OR EQUIVALENT MANUFACTURER. COLOR OF CONDENSATE PUMP SHALL MATCH COLOR OF INDOOR UNIT.
(3) PROVIDE LINE HIDE KIT FOR NEW INDOOR HEAT PUMP.

Table: -- OUTDOOR HEAT PUMP SCHEDULE --

- (1) RATINGS IN ACCORDANCE WITH A.S.I. STANDARD 240.

Table: -- ELECTRIC HEATER SCHEDULE --

- (1) COMPLETE WITH RECESSED CEILING TRIM KIT AND INTEGRAL THERMOSTAT.
(2) COMPLETE WITH SURFACE MOUNT KIT AND INTEGRAL THERMOSTAT.

Table: -- THRU WALL HEAT PUMP SCHEDULE --

- (1) UNITS SHALL HAVE WALL MOUNTED ADAPTOR CURB.

Table: -- REFRIGERATION PIPE SCHEDULE --

- (1) REFRIGERANT PIPE SIZES INDICATED ARE FOR ESTIMATING PURPOSES ONLY. EXACT SIZES AND ACCESSORIES REQUIRED SHALL BE DETERMINED BY EQUIPMENT MANUFACTURER FROM FIELD OBTAINED DIMENSIONS.

DELOACH ARCHITECTS PC

ALLATOONA ELEMENTARY SCHOOL




FRUIT, RORD & ASSOCIATES, INC. CONSULTING ENGINEERS

THESE DOCUMENTS, AS INSTRUMENTS OF SERVICE, REMAIN THE PROPERTY OF THE ARCHITECT AND NO PART OF THESE DOCUMENTS SHALL BE REPRODUCED OR USED IN ANY FORM WITHOUT WRITTEN PERMISSION.

Table: DATE, REVISIONS, NO.

CONSTRUCTION DOCUMENTS

HVAC PLAN SCALE: 1/8" = 1'-0" SHEET M4.02 19 OF 32 FILE: 18.04 DATE: 12/14/18



DELOACH ARCHITECTS, INC. 721 WALNUT STREET POST OFFICE BOX 8226 WADON, GEORGIA 31726 phone 478-742-6599 fax 478-742-5007 deloach@deloacharchitects.com