# DRAWING SYMBOLS LEGEND

**SHEET NUMBER**

A521

SHEET NUMBER

DISCIPLINE LETTER

**VIEW TITLE**

GRAPHIC SHEET POSITION — GRAPHIC DESCRIPTION

| A1 | View Name | |
|---|---|---|
| A101 | 1/8" = 1' - 0" | A1 / A201 |

SHEET NUMBER — REFERENCE VIEW — GRAPHIC SCALE

**NORTH ARROW**

TRUE NORTH

**GRAPHIC SCALE**

0 2" 4" 8"

SCALE: 1" = 4'-0"

**SCOPE LEGEND**

NEW WALL

OR — EXISTING WALL

DEMOLISHED WALL

**ROOM NAME AND NUMBER**

ROOM NAME

XXXX

**DOOR TAG AND NUMBER**

(106) — DOOR NUMBER

DEMOLITION NOTES TAG

D-X

**NOTE SHEET NOTE**

**TOILET ROOM ACCESSORY TAG**

X

**EQUIPMENT AND FURNITURE TAG**

XXX

**KEY NOTE**

00 0000.00

**BUILDING SECTION TAG**

1 / A-100 — SECTION DESIGNATION — SHEET NUMBER

**DETAIL/WALL SECTION TAG**

1 / A-100 — SECTION DESIGNATION — SHEET NUMBER

**PARTIAL PLAN AND DETAIL TAG**

1 / A-100 — PLAN OR DETAIL DESIGNATION — SHEET NUMBER

**EXTERIOR ELEVATION TAG**

1 / A-100 — ELEVATION DESIGNATION — SHEET NUMBER

**INTERIOR ELEVATION TAG**

ELEVATION DESIGNATION — SHEET NUMBER

**DRAWING REVISION**

3

**VERTICAL ELEVATION**

LEVEL 2 FRE 18'-6"

**SPOT ELEVATION**

SECOND FLOOR EL. 18'-6"

**MATCH LINE**

MATCH LINE SEE XXX-XXX

SHEET NUMBER ON WHICH CONTINUATION IS FOUND

## E10 SYMBOLS LEGEND

G001 N.T.S




URINAL

## C10 URINAL SCREEN MOUNTING HEIGHTS

G001 N.T.S




VCT - CARPET




VCT - VCT

## A10 TYP. SILL DETAIL

G001 3" = 1'-0"

## A12 TYP. SILL DETAIL

G001 3" = 1'-0"

## A14 ABBREVIATION LIST

G001 N.T.S

| | | | |
|---|---|---|---|
| A.B. | ANCHOR BOLT | L. | LENGTH |
| ACOUST. | ACOUSTICAL | LAD. | LADDER |
| A.C.T. | ACOUSTICAL CEILING TILE | LAM. | LAMINATE |
| ADJ. | ADJUSTABLE | LAV. | LAVATORY |
| A.F.F. | ABOVE FINISH FLOOR | LB. | POUND |
| AGG. | AGGREGATE | LKR. | LOCKER |
| ALT. | ALTERNATE | LT. | LIGHT |
| ALUM. | ALUMINUM | LVL | LEVEL |
| ANOD. | ANODIZED | LVR. | LOUVER |
| APPLIC. | APPLICABLE | LW. | LIGHTWEIGHT |
| APPROX. | APPROXIMATE | | |
| ARCH. | ARCHITECTURAL | MACH. | MACHINE |
| ASP. | ASPHALT | MAS. | MASONRY |
| AUTO. | AUTOMATIC | MAT. | MATERIAL |
| AUX. | AUXILIARY | MAX. | MAXIMUM |
| | | M.B. | MARKER BOARD |
| BD. | BOARD | M.C.J. | MASONRY CONTROL JOINT |
| BIT. | BITUMINOUS | MECH. | MECHANICAL |
| B.R. | BORROWED LITE | MED. | MEDIUM |
| BLDG. | BUILDING | MEMB. | MEMBRANE |
| BLK. | BLOCK | MEZZ. | MEZZANINE |
| BLKG. | BLOCKING | MFR. | MANUFACTURER |
| BM. | BEAM | MH. | MANHOLE |
| BOT. | BOTTOM | MIN. | MINIMUM |
| BR. | BRONZE | MIR. | MIRROR |
| BRDG. | BRIDGING | MISC. | MISCELLANEOUS |
| BRG. | BEARING | M.O. | MASONRY OPENING |
| BRK. | BRICK | MTD. | MOUNTED |
| B.S. | BOTH SIDES | MTL. | METAL |
| BTWN. | BETWEEN | MUL. | MULLION |
| B.U.R. | BUILT-UP ROOF | MDF | MEDIUM DENSITY FIBERBOARD |
| CAB. | CABINET | | |
| C.C. | CENTER TO CENTER | N. | NORTH |
| CEM. | CEMENT | N.I. | NOT INCLUDED |
| C.G. | CORNER GUARD | N.I.C. | NOT IN CONTRACT |
| CHAM. | CHAMFER | NO. | NUMBER |
| C.I. | CAST IRON | NOM. | NOMINAL |
| C.I.P. | CAST IN PLACE | N.T.S. | NOT TO SCALE |
| C.J. | CONTROL JOINT | | |
| CLG. | CEILING | O.A. DUCT | OUTSIDE AIR DUCT |
| CLK. | CAULKING | O.C. | ON CENTER |
| CL. | CENTER LINE | O.D. | OUTSIDE DIAMETER |
| CLO. | CLOSET | OFF. | OFFICE |
| C.M.U. | CONCRETE MASONRY UNIT | O.H. | OVER HEAD |
| CSD. | CASED OPENING | OPNG. | OPENING |
| COL. | COLUMN | OPP. | OPPOSITE |
| COMB. | COMBINATION | OZ. | OUNCE |
| COMP. | COMPOSITION | | |
| CONC. | CONCRETE | P.C. | PRECAST |
| CON. | CONNECTION | PERF. | PERFORATED |
| CONST. | CONSTRUCTION | PL. | PROPERTY LINE |
| CONT. | CONTINUOUS | PLAM. | PLASTIC LAMINATE |
| CONTR. | CONTRACTOR | PLAS. | PLASTIC |
| COR. | CORRIDOR | PLWD. | PLYWOOD |
| C.T. | CERAMIC TILE | PR. | PAIR |
| CTR. | CENTER | PROP. | PROPERTY |
| C.U. | CONDENSER UNIT | P.S.F. | POUNDS PER SQUARE FOOT |
| | | P.S.I. | POUNDS PER SQUARE INCH |
| DBL. | DOUBLE ACTING DOUBLE | P.T. | PRESSURE TREATED |
| D.C.J. | DRYWALL CONTROL JOINT | P.T.D./R. | PAPER TOWEL DISPENSER PAPER TOWER |
| DEPT. | DEPARTMENT | | DISP./RECEPT. |
| D.F. | DRINKING FOUNTAIN | PTN. | PARTITION |
| DIA. | DIAMETER | P.V.C. | POLYVINYL CHLORIDE |
| DIAG. | DIAGONAL | PVMT. | PAVEMENT |
| DIFF. | DIFFUSER | | |
| DIM. | DIMENSION | Q.T. | QUARRY TILE |
| DISP. | DISPENSER | | |
| DIV. | DIVIDER/DIVISION | R. | RISER |
| DN. | DOWN | RAD. | RADIUS |
| D.S. | DOWN SPOUT | R.D. | ROOF DRAIN |
| DTL. | DETAIL | REF. | REFRIGERATOR |
| D.V. | DRYER VENT | REG. | REGISTER |
| DWG. | DRAWING | REINF. | REINFORCEMENT |
| | | REQD. | REQUIRED |
| E. | EAST | RESIL. | RESILIENT |
| EA. | EACH | RET. | RETAINING |
| E.F. | EXHAUST FAN | REV. | REVISION |
| E.H.D. | ELECTRIC HAND DRYER | RF. | ROOF(ING) |
| E.I.F.S. | EXTERIOR INSULATION FINISH SYSTEM | RM. | ROOM |
| | | R.O. | ROUGH OPENING |
| E.J. | EXPANSION JOINT | R.O.W. | RIGHT OF WAY |
| E.J.C. | EXPANSION JOINT COVER | RTN. | RETURN |
| EL. | ELEVATION | | |
| ELEC. | ELECTRICAL | S. | SOUTH |
| ELEV. | ELEVATOR | SAN. | SANITARY |
| EMER. | EMERGENCY | S.C. | SOLID CORE |
| ENCL. | ENCLOSURE | SCHED. | SCHEDULE |
| ENTR. | ENTRANCE | S.D. | SOAP DISPENSER |
| E.P. | ELECTRIC PANEL | SEC. | SECTION |
| EQ. | EQUAL | S.F. | SQUARE FOOT |
| EQPT. | EQUIPMENT | SH. | SHELF |
| E.S. | EACH SIDE | SHT. | SHEET |
| E.W. | EACH WAY | SIM. | SIMILAR |
| E.W.C. | ELECTRIC WATER COOLER | S.N.D. | SANITARY NAPKIN DISPENSER |
| EXIST. | EXISTING | | |
| EXP. | EXPANSION | S.N.R. | SANITARY NAPKIN RECEPTICLE |
| EXT. | EXTERIOR | | |
| | | SPEC. | SPECIFICATION |
| F.A. | FIRE ALARM | SPL. BLK. | SPLASH BLOCK |
| F.D. | FLOOR DRAIN | SQ. | SQUARE |
| F.E. | FIRE EXTINGUISHER | S.S. | STAINLESS STEEL |
| F.E.B. | FIRE EXT. ON BRACKET | STA. | STATION |
| F.E.C. | FIRE EXT. CABINET | STD. | STANDARD |
| F.H.C. | FIRE HOSE CABINET | STL. | STEEL |
| F.I. | X-RAY FILM ILLUNINATOR | STOR. | STORAGE |
| FIN. | FINISH | STRUCT. | STRUCTURAL |
| FIN. FLR. | FINISH FLOOR | SUSP. | SUSPENSION/SUSPENDED |
| FIN. SLAB | FINISH SLAB | SYN. | SYNTHETIC |
| FLR. | FLOOR | SYS. | SYSTEM |
| FLASH. | FLASHING | | |
| FLUOR. | FLUORESCENT | T. | TREAD |
| F.O.C. | FACE OF CONCRETE | T/B | TOP AND BOTTOM |
| F.O.W. | FACE OF WALL | T.O.C. | TOP OF CURB |
| F.R. | FIRE RESISTIVE | TELE. | TELEPHONE |
| F.S. | FULL SIZE | TEMP. | TEMPERED |
| FT. | FOOT/FEET | TER. | TERRAZO |
| FTG. | FOOTING | T&G | TONGUE AND GROOVE |
| FURN. | FURNISH | THK. | THICK |
| FURR. | FURRING | THD. | THRESHOLD |
| FUT. | FUTURE | T.O.M. | TOP OF MASONRY |
| | | T.O.P. | TOP OF PAVEMENT |
| GA. | GAUGE | T.PL. | TOP OF PLATE |
| GALV. | GALVANIZED | T.S. | TUBULAR STEEL |
| G.B. | GRAB BAR | T.O.S. | TOP OF STEEL |
| GEN. | GENERAL | T.V. | TELEVISION |
| G.I. | GALVANIZED IRON | T.O.W. | TOP OF WALL |
| GL. | GLASS | TYP. | TYPICAL |
| GND. | GROUND | | |
| GR. | GRADE | U.L. | UNDERWRITERS LABORATORIES |
| GYP. BD. | GYPSUM WALL BOARD | | |
| | | UNF. | UNFINISHED |
| H. | HIGH | U.N.O. | UNLESS OTHERWISE NOTED |
| H.B. | HOSE BIB | UR. | URINAL |
| H.C. | HOLLOW CORE | UTIL. | UTILITY |
| HDW. | HARDWARE | | |
| HDWD. | HARDWOOD | V.F. | VENTILATION FAN |
| H.M. | HOLLOW METAL | V.I.F. | VERIFY IN FIELD |
| HORIZ. | HORIZONTAL | VIN. | VINYL |
| HR. | HOUR | V.C.T. | VINYL COMPOSITION TILE |
| HT. | HEIGHT | VERT. | VERTICAL |
| | | VEST. | VESTIBULE |
| I.D. | INSIDE DIAMETER | V.T.R. | VENT THRU ROOF |
| INFO. | INFORMATION | V.W.C. | VINYL WALL COVERING |
| INSUL. | INSULATION | | |
| INT. | INTERIOR | W. | WEST |
| INV. | INVERT | W/ | WITH |
| I.P. | IRON PIPE | W.C. | WATER CLOSET |
| JAN. | JANITOR | WD. | WOOD |
| JT. | JOINT | W.H. | WATER HEATER |
| JST. | JOIST | W/O | WITH OUT |
| JST. BRG. | JOIST BEARING | W.P. | WATERPROOF |
| J.V. | JOB VERIFY | W.R. | WATER RESISTIVE |
| | | WSCT. | WAINSCOT |
| K.O. | KNOCK OUT | WT. | WEIGHT |
| K.D. | KNOCK DOWN | W.W.M. | WELDED WIRE MESH |

## KEYNOTE LEGEND

| | |
|---|---|
| 096513.C01 | RESILIENT MOLDING ACCESSORY |
| 096519 | RESILIENT TILE FLOORING |


CDH
Partners
2400 Piedmont Road
Suite 100
Atlanta, GA 30060-67
770.42
www.cdhpartners.com



COPYRIGHT © 2018 CDH PARTNERS, INC
ALL RIGHTS RESERVED


FULTON COUNTY SCHOOL SYSTEM

# RIVER EVES ELEMENTARY SCHOOL - RENOVATIONS

9000 EVES ROAD, ROSWELL, GA 30076

PROJECT NO: 18046.00

| | | |
|---|---|---|
| | 50% CD'S | 09/07/2018 |
| | PERMIT SET | 09/20/2018 |
| | 95% CD'S | 11/08/2018 |
| | BID SET | 12/03/2018 |
| | | |
| | | |

STATE OF GEORGIA
MELISSA ANNE CARROLL
12-3-18
REGISTERED ARCHITECT

CONTRACT DOCUMENT
ISSUED FOR CONSTRUCTION

SHEET TITLE

GENERAL INFORMATION

SHEET NUMBER

G001


Order Plans @ WWW.LDLine.com