



- GENERAL CASEWORK NOTES
- A. ALL CASEWORK MODEL NUMBERS ARE BASED ON TMI SYSTEMS CORPORATION.
 - B. CASEWORK ELEVATIONS ARE SHOWN IN ONE CONFIGURATION. CONTRACTOR SHALL MIRROR CASEWORK AS REQUIRED BASED ON THE EXISTING ROOM LAYOUT AND PLUMBING FIXTURE LOCATIONS.
 - C. NEW SINK BASE CABINETS SHOULD BE PLACED IN THE SAME LOCATION AS THE EXISTING PLUMBING FIXTURES.
 - D. BUBBLER FIXTURE SHALL BE ON THE WHITE SIDE OF THE SINK FROM THE ADJACENT ROOM TO AVOID THE PAPER TOWEL DISPENSER MIRROR SINK FIXTURE AS REQUIRED BASED ON THE ROOM LAYOUT.
 - E. PROVIDE PROTECTIVE PPE AT ALL WHEEL CHAIR ACCESSIBLE STATIONS.
 - F. NEW CASEWORK MAY VARY IN SIZE AND CONFIGURATION FROM THE EXISTING CASEWORK. REMOVE SEALANT AND PAINT LINES FROM EXISTING CASEWORK IF REMOVED, PREP, & PAINT.
 - G. ALL NEW FLOOR MOUNTED CASEWORK SHALL RECEIVE NEW 4 INCH RUBBER BASE ALONG THE ENTIRE LENGTH ALIGNING WITH THE EXISTING WALL BASE. THE INTENT IS FOR ALL NEW RUBBER BASE TO MATCH THE HEIGHT AND COLOR OF THE EXISTING RUBBER BASE.
 - H. ALL COUNTERTOPS AND BACKPLASHES SHALL BE POST FORMED. SEE DETAIL M1A601. CASEWORK SHOWN IN DETAILS AT A17 & F7A801 DO NOT HAVE BACKPLASHES AND SHALL HAVE A SQUARE EDGE IN LIEU OF THE ROUNDED EDGE.

FULTON COUNTY SCHOOL SYSTEM
**RIVER EVES ELEMENTARY SCHOOL -
 RENOVATIONS**
 9000 EVES ROAD, ROSWELL, GA 30076

PROJECT NO: 19046.00

50% CD'S	08/07/2018
PERMIT SET	09/20/2018
95% CD'S	11/08/2018
BD SET	12/03/2018



CONTRACT DOCUMENT
ISSUED FOR CONSTRUCTION

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

SHEET TITLE
**CASEWORK &
INTERIOR
ELEVATIONS**

SHEET NUMBER
A601

Order Plans

WWW.ONLINE