2016 ROAD & BRIDGE STANDARDS

DI-3A, 3B, 3C



VDOT ROAD AND BRIDGE STANDARDS

SHEET # OF 2	REVISION DATE
104.09	08/10

STANDARD CURB DROP INLET

12" - 30" PIPE: MAXIMUM DEPTH (H) = 8'

VIRGINIA DEPARTMENT OF TRANSPORTATION

SPECIFICATION REFERENCE
233 302

2016 ROAD & BRIDGE STANDARDS

2016 ROAD & BRIDGE STANDARDS

DI-3A, 3B, 3C

TABLE OF QUANTITIES

TYPE	L	AREA OF SLOT	REINFORCING STEEL																		WEIGHT
			Concrete	BARS A		BARS B		BARS C		BARS D		BARS E		BARS F		BARS G					
	Ft.	Sq. Ft.	Cu. Yds.	No.	Lin. Ft. #	No.	Lin. Ft. #	No.	Lin. Ft. #	No.	Lin. Ft. #	No.	Lin. Ft. #	No.	Lin. Ft. #	No.	Lin. Ft. #				Lbs.
DI-3A	2'-8"	1.15	2.28	1	-	-	-	3	5'-7"	3	5'-7"	3	3'-2"	-	-	-	-				22
DI-3B	4'	1.83	2.59	5	7'-6"	2	6'-7" to 5'-10"	3	5'-7"	3	5'-7"	3	3'-2"	4	7'-6"	3	7'-8"	4	1'-0"		64
	6'	2.75	3.03	5	5'-6"	6	6'-7" to 6'-10"	3	5'-7"	3	5'-7"	3	3'-2"	4	9'-6"	3	7'-8"	4	1'-0"		111
	8'	3.67	3.46	5	5'-6"	10	6'-7" to 6'-10"	3	5'-7"	3	5'-7"	3	3'-2"	4	5'-6"	3	7'-8"	4	1'-0"		158
	10'	4.58	3.90	5	7'-6"	14	6'-7" to 6'-10"	3	5'-7"	3	5'-7"	3	3'-2"	4	7'-6"	3	7'-8"	4	1'-0"		204
	12'	5.50	4.34	5	9'-6"	18	6'-7" to 6'-10"	3	5'-7"	3	5'-7"	3	3'-2"	4	9'-6"	3	7'-8"	4	1'-0"		251
	14'	6.42	4.78	5	11'-6"	22	6'-7" to 6'-10"	3	5'-7"	3	5'-7"	3	3'-2"	4	11'-6"	3	7'-8"	4	1'-0"		298
	16'	7.33	5.22	5	13'-6"	26	6'-7" to 6'-10"	3	5'-7"	3	5'-7"	3	3'-2"	4	13'-6"	3	7'-8"	4	1'-0"		345
	18'	8.25	5.66	5	15'-6"	30	6'-7" to 6'-10"	3	5'-7"	3	5'-7"	3	3'-2"	4	15'-6"	3	7'-8"	4	1'-0"		391
	20'	9.17	6.09	5	17'-6"	34	6'-7" to 6'-10"	3	5'-7"	3	5'-7"	3	3'-2"	4	17'-6"	3	7'-8"	4	1'-0"		438
DI-3C	6'	2.75	3.01	10	7'-9"	4	6'-7" to 6'-10"	5	5'-7"	3	5'-7"	3	3'-2"	8	7'-9"	3	7'-8"	2	1'-0"		111
	8'	3.67	3.45	10	2'-9"	8	6'-7" to 6'-10"	5	5'-7"	3	5'-7"	3	3'-2"	8	2'-9"	6	1'-6"	2	1'-0"		158
	10'	4.58	3.89	10	3'-9"	12	6'-7" to 6'-10"	5	5'-7"	3	5'-7"	3	3'-2"	8	3'-9"	6	1'-6"	2	1'-0"		200
	12'	5.50	4.33	10	4'-9"	16	6'-7" to 6'-10"	5	5'-7"	3	5'-7"	3	3'-2"	8	4'-9"	6	1'-6"	2	1'-0"		252
	14'	6.42	4.77	10	5'-9"	20	6'-7" to 6'-10"	5	5'-7"	3	5'-7"	3	3'-2"	8	5'-9"	6	1'-6"	2	1'-0"		298
	16'	7.33	5.21	10	6'-9"	24	6'-7" to 6'-10"	5	5'-7"	3	5'-7"	3	3'-2"	8	6'-9"	6	1'-6"	2	1'-0"		345
	18'	8.25	5.65	10	7'-9"	28	6'-7" to 6'-10"	5	5'-7"	3	5'-7"	3	3'-2"	8	7'-9"	6	1'-6"	2	1'-0"		392
	20'	9.17	6.09	10	8'-9"	32	6'-7" to 6'-10"	5	5'-7"	3	5'-7"	3	3'-2"	8	8'-9"	6	1'-6"	2	1'-0"		438

NOTES

1. DEPTH OF INLET (H) TO BE SHOWN ON PLANS.
2. THE "H" DIMENSION SHOWN ON THE STANDARDS AND SPECIFIED ON THE PLANS WILL BE MEASURED FROM THE INVERT OF THE OUTFALL PIPE TO THE TOP OF THE STRUCTURE. PLAN "H" DIMENSIONS ARE APPROXIMATE ONLY FOR ESTIMATING PURPOSES AND THE ACTUAL DIMENSIONS SHALL BE DETERMINED BY THE CONTRACTOR FROM FIELD CONDITIONS.
3. WHEN SPECIFIED ON THE PLANS THE INVERT OF THE OUTFALL PIPE IS TO BE SHAPED WITH CEMENT MORTAR TO PREVENT STANDING OR PONDING OF WATER IN THE STRUCTURE, THE COST OF FURNISHING AND PLACING ALL MATERIALS INCIDENTAL TO THE SHAPING IS TO BE INCLUDED IN THE BID PRICE FOR THE STRUCTURE.
4. IN THE EVENT THE INVERT OF THE OUTFALL PIPE IS HIGHER THAN THE BOTTOM OF THE STRUCTURE, THE INVERT OF THE STRUCTURE SHALL BE SHAPED WITH CEMENT MORTAR TO PREVENT STANDING OR PONDING OF WATER IN THE STRUCTURE. THE COST OF FURNISHING AND PLACING ALL MATERIALS INCIDENTAL TO THE SHAPING IS TO BE INCLUDED IN THE BID PRICE FOR THE STRUCTURE.
5. STEPS ARE TO BE PROVIDED WHEN H IS 4'-0" OR GREATER. FOR DETAILS SEE STANDARD ST-1.
6. THIS ITEM MAY BE PRECAST OR CAST-IN-PLACE.
7. ⌀ 4 X 6" SMOOTH DOWELS AT APPROXIMATELY 12" C-C TO BE PLACED IN ALL AREAS ADJACENT TO ABUTTING CONCRETE TO PREVENT SETTLEMENT.
8. 3" DIAMETER WEEP HOLE TO BE LOCATED TO DRAIN SUBBASE MATERIAL. WEEP HOLE WITH 12"X12" PLASTIC HARDWARE CLOTH 1/4" MESH OR GALVANIZED STEEL WIRE, MINIMUM WIRE DIAMETER 0.03", NUMBER 4 MESH HARDWARE CLOTH ANCHORED FIRMLY TO THE OUTSIDE OF THE STRUCTURE.
9. ALL REINFORCING STEEL SHALL HAVE A MIN. COVER OF 2".
10. ALL REINFORCING STEEL TO BE CUT CLEAR OF ALL OPENINGS BY 2".
11. CAST-IN PLACE CONCRETE IS TO BE CLASS A3 (3000 PSI). PRECAST CONCRETE IS TO BE 4000 PSI.
12. LENGTH OF SLOT (L) WILL, IN ALL CASE, BE SHOWN ON PLANS.
13. 6" INLET IS CONSTRUCTED IN MEDIAN STRIP OR WITH INTEGRAL CURB, GUTTER IS TO BE OMITTED (SEE DETAIL).
14. STANDARD INLETS MAY BE CONSTRUCTED WITH CONSOLIDATED BLOCKS IN ACCORDANCE WITH THE DETAILS SHOWN ON STANDARD DRAWING DI-1.
15. THIS AREA MAY BE EARTHEN IN WHICH CASE THE EXPANSION JOINTS WILL APPLY ONLY TO CURB AND GUTTER.
16. CONCRETE QUANTITIES SHOWN ARE FOR DEPTH (H) OF 2'-0" WITHOUT PIPE. THE AMOUNT DISPLACED BY PIPES MUST BE DEDUCTED TO OBTAIN TRUE QUANTITIES. FOR INLETS OF DIFFERENT DEPTHS ADD OR SUBTRACT 0.32 CUBIC YARDS OF CONCRETE FOR EACH FOOT OF DEPTH.
17. LENGTH OF ANGLE IRON AS SHOWN ON SHEET 1 OF 2 IS EQUAL TO L+9.5" AT 4.0 LBS./FT..
18. * DENOTES LENGTH OF ONE (1) BAR.

ALL REINFORCING BARS TO BE #5 UNLESS OTHERWISE NOTED.

SPECIFICATION REFERENCE
233 302

STANDARD CURB DROP INLET

12" - 30" PIPE: MAXIMUM DEPTH (H) = 8'

VIRGINIA DEPARTMENT OF TRANSPORTATION

VDOT ROAD AND BRIDGE STANDARDS

REVISION DATE	SHEET # OF 2
	104.10

2016 ROAD & BRIDGE STANDARDS

NYLOPLAST 30" INLINE DRAIN: 2730AG__X



ADAPTER SIZE	H
4"	15.25
6"	15.50
8"	15.75
10"	16.00
12"	16.50
15"	17.00
18"	17.75
24"	14.00
30"	9.50

GRATE OPTIONS	LOAD RATING	PART #	DRAWING #
PEDESTRIAN	H-20	3099GRP	7001-110-220
SLOTTED	H-20	3099GRS	7001-110-221
SOLID COVER	MEETS H-20	3099GSC	7001-110-222
	N/A	3099GSD	7001-110-223

1 - GRATE/SOLID COVER SHALL BE DUCTILE IRON PER ASTM A536 GRADE 70-50-05.
2 - FRAMES SHALL BE DUCTILE IRON PER ASTM A536 GRADE 70-50-05.
3 - DRAINAGE CONNECTION STUB JOINT TIGHTNESS SHALL CONFORM TO ASTM D3212 FOR CORRUGATED HDPE (ADS N-12/HANCOR DUAL WALL), N-12 HP, & PVC SEWER.
4 - DIMENSIONS ARE FOR REFERENCE ONLY. ACTUAL DIMENSIONS MAY VARY.
5 - DIMENSIONS ARE IN INCHES
8 - SEE DRAWING NO. 7001-110-270 FOR ADS N-12 & HANCOR DUAL WALL BELL INFORMATION & DRAWING NO. 7001-110-264 FOR HP BELL INFORMATION.

THIS PRINT DISCLOSES SUBJECT MATTER IN WHICH NYLOPLAST HAS PROPRIETARY RIGHTS. THE RECEIPT OR POSSESSION OF THIS PRINT DOES NOT CONVEY TRANSFER, OR LICENSE THE USE OF THE DESIGN OR TECHNICAL INFORMATION DISCLOSED HEREIN. REPRODUCTION OF THIS PRINT OR ANY INFORMATION CONTAINED HEREIN, OR MANUFACTURE OF ANY ARTICLE SHOWN HEREON FOR THE DISCLOSURE TO OTHERS IS STRICTLY PROHIBITED BY SPECIFIC WRITTEN PERMISSION FROM NYLOPLAST.

DRAWN BY	ESC	MATERIAL
DATE	04-22-96	
CHECKED BY	MRH	PROJECT NO./NAME
	03-15-16	
DWG SIZE	A	SCALE 1:40 SHEET 1 OF 1

Nyloplast
3126 VERONA AVE
BUFORD, GA 30518
PHN (770) 932-2442
FAX (770) 932-2486
www.nyloplast-us.com
TITLE
30-IN INLINE DRAIN QUICK SPEC INSTALLATION DETAIL
DWG NO. 7001-110-025 REV E

Rinker MATERIALS — Concrete Pipe Division

RTC 4501 Precast Concrete Stormceptor (4500 U.S. Gallon Capacity)



Notes:
1. The Use Of Flexible Connection is Recommended at The Inlet and Outlet Where Applicable.
2. The Cover Should be Positioned Over The Inlet Drop Pipe and The Oil Port.
3. The Stormceptor System is protected by one or more of the following U.S. Patents: #4985148, #5498331, #5725760, #5753115, #5849181, #6068765, #6371690.
4. Contact a Concrete Pipe Division representative for further details not listed on this drawing.

Rinker 027

2016 ROAD & BRIDGE STANDARDS



NOTES

1. DEPTH OF INLET (H) TO BE SHOWN ON PLANS.
2. THE "H" DIMENSION SHOWN ON THE STANDARDS AND SPECIFIED ON THE PLANS WILL BE MEASURED FROM THE INVERT OF THE OUTFALL PIPE TO THE TOP OF THE STRUCTURE. PLAN "H" DIMENSIONS ARE APPROXIMATE ONLY FOR ESTIMATING PURPOSES AND THE ACTUAL DIMENSIONS SHALL BE DETERMINED BY THE CONTRACTOR FROM FIELD CONDITIONS. MAXIMUM DEPTH (H) TO BE 12'-8".
3. WHEN SPECIFIED ON THE PLANS THE INVERT IS TO BE SHAPED IN ACCORDANCE WITH STANDARD (3). THE COST OF FURNISHING AND PLACING ALL MATERIALS INCIDENTAL TO THE SHAPING IS TO BE INCLUDED IN THE BID PRICE FOR THE STRUCTURE.
4. IN THE EVENT THE INVERT OF THE OUTFALL PIPE IS HIGHER THAN THE BOTTOM OF THE STRUCTURE, THE INVERT OF THE STRUCTURE SHALL BE SHAPED WITH CEMENT MORTAR TO PREVENT STANDING OR PONDING OF WATER IN THE STRUCTURE. THE COST OF FURNISHING AND PLACING ALL MATERIALS INCIDENTAL TO THE SHAPING IS TO BE INCLUDED IN THE BID PRICE FOR THE STRUCTURE.
5. STEPS ARE TO BE PROVIDED WHEN H IS 4'-0" OR GREATER. FOR DETAILS SEE STANDARD ST-1.
6. REINFORCED CONCRETE FOOTING MAY BE PRECAST OR CAST-IN-PLACE. TWO LIFTING HOOKS OF FABRICATORS DESIGN TO BE PROVIDED IN PRECAST FOOTING
7. 4" DEPTH AGGREGATE #68,#78, OR #8 X 6" WIDTH.
8. 3" DIAMETER WEEP HOLE WITH 12"X12" PLASTIC HARDWARE CLOTH 1/4" MESH OR GALVANIZED STEEL WIRE, MINIMUM WIRE DIAMETER 0.03" NUMBER 4 MESH HARDWARE CLOTH ANCHORED FIRMLY TO THE OUTSIDE OF THE STRUCTURE.
9. THE TYPE OF INLET (PRECAST OR CAST IN PLACE), DETAILED HEREON, TO BE CONSTRUCTED, WILL BE AT THE OPTION OF THE CONTRACTOR.
10. FOR DETAILS OF CONCRETE COVER, COLLAR AND GRATE, AND THE METHOD OF PLACING APPROACH GUTTER SEE SHEET 2 OF 3.
11. CAST-IN PLACE CONCRETE IS TO BE CLASS A3 (3000 PSI). PRECAST CONCRETE IS TO BE 4000 PSI.
12. CONCRETE QUANTITIES SHOWN ARE FOR INDICATED DEPTH (H) WITHOUT PIPES. THE AMOUNT DISPLACED BY PIPES MUST BE DEDUCTED TO OBTAIN TRUE QUANTITIES. FOR INLETS OF DIFFERENT DEPTHS ADD OR SUBTRACT THE APPROPRIATE CUBIC YARDS OF CONCRETE FOR EACH FOOT OF DEPTH.
13. PAVED DITCHES ARE TO BE TRANSITIONED TO MEET INLET GUTTER AS SHOWN IN STANDARD PG-2A.
14. PROVIDE SAFETY SLABS WHEN SPECIFIED ON THE PLANS.
15. DI-7 ---------- NO GUTTER
    DI-7A ---------- SINGLE GUTTER WHEN DROP INLET IS ON A GRADE.
    DI-7B ---------- DOUBLE GUTTER WHEN DROP INLET IS IN A SAG BETWEEN TWO GRADES.
16. FOR DETAILS OF PRECAST DI-7 NOT SHOWN HEREON SEE PRECAST UNIT ASSEMBLY DIAGRAM, PAGE 103.01, FOR PRECAST GENERAL NOTES, PAGE 103.02 AND FOR APPLICABLE PRECAST BASE, RISER AND TOP DETAILS, PAGES 103.07 THRU 103.12.
17. GRATE BARS TO BE PARALLEL TO DITCH FLOW.

RECOMMENDED MINIMUM HEIGHT CHART		
PIPE SIZE	H DIMENSION CONC.	CORR. METAL
12"	2'-6"	2'-5"
15"	2'-9¼"	2'-8"
18"	3'-0½"	2'-11"
21"	3'-3¾"	3'-2"
24"	3'-7"	3'-5"
27"	3'-10¼"	3'-8"
30"	4'-1½"	3'-11"
33"	4'-4¾"	4'-2"
36"	4'-8"	4'-5"
42"	5'-2½"	4'-11"

PIPE SIZE	12"	15"	18"	24"	30"	36"	42"
MINIMUM DEPTH H	2'-0"	2'-3¼"	2'-6½"	3'-1"	3'-7½"	4'-2"	4'-8½"
CONCRETE CUBIC YARDS	.947	1.045	1.143	1.339	1.535	1.731	1.927

INCREMENT PER FOOT OF ADDITIONAL DEPTH (H) { = 0.362 CU. YDS. (12" - 36" PIPE) / = 0.410 CU. YDS. (42" PIPE)

SPECIFICATION REFERENCE
241 503

STANDARD MEDIAN DROP INLET

12" TO 42" PIPE

VIRGINIA DEPARTMENT OF TRANSPORTATION

VDOT ROAD AND BRIDGE STANDARDS

REVISION DATE	SHEET 1 OF 3
	104.22

2016 ROAD & BRIDGE STANDARDS

Order Plans @ WWW.IDLine.com

Kimley»Horn
© 2018 KIMLEY-HORN AND ASSOCIATES, INC.
1700 WILLOW LAWN DR, SUITE 200, RICHMOND, VA 23230
PHONE: 804-673-3882
WWW.KIMLEY-HORN.COM

NO.	REVISIONS	DATE	BY

COMMONWEALTH OF VIRGINIA
J. RANDALL ROYAL
Lic. No. 14950
8/24/18
PROFESSIONAL ENGINEER

KHA PROJECT 116607003
DATE 08/24/2018
SCALE AS SHOWN
DESIGNED BY LEY
DRAWN BY LEY
CHECKED BY JR

WAWA AT NEWTOWN AND STONEY POINT
PREPARED FOR WAWA
CITY OF NORFOLK VIRGINIA

DRAINAGE DETAILS

SHEET NUMBER
CG-502

Plotted By: Young, Lauren (Virginia Beach) Sheet Set: Misc. Layout: CG-502 DRAINAGE DETAILS October 02, 2018 09:01:43pm K:\vab_civil\116607003 - wawa - newtown & stoney\CADD\Construction\CG-502 DRAINAGE DETAILS.dwg
This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.