



- GENERAL SHEET NOTES**
- VERIFY FINAL LOCATIONS OF RECESSES AND THICKENED SLAB
  - FOR ACTUAL ELEVATION (REF. ELEV. 0'-0" HEREIN)
  - SEE GENERAL NOTES AND SPECIFICATIONS FOR SOIL, SOIL TREATMENT AND MOISTURE PROTECTION.
  - FOR COLUMN BASE PLATES SEE DETAIL SHEETS

**DRAWING SYMBOLS**

	STEP IN SLAB NUMBER (IF GIVEN) IS STEP HEIGHT.
	4" CAI
	COLUMN SIZE
	COLUMN / FOOTING / PIER / BASE PLATE TAG
	FOOTING MARK (REF. DET. 3/S7.1)

**FOUNDATION SCHEDULE**

MARK	LENGTH	WIDTH	THICKNESS	TOP REINF.	BOTTOM REINF.	ELEV. AT BOTTOM
F4.0	4'-0"	4'-0"	1'-6"	-	(5) #5 E.W.	-3'-6"
F8.5	8'-6"	8'-6"	2'-0"	-	(8) #7 E.W.	-4'-0"
WF24	CONT.	2'-0"	1'-6"	-	(3) #5 CONT.	-3'-6"

**CONCRETE PIER SCHEDULE**

MARK	SIZE	DEPTH	VERTICAL REINFORCEMENT	TIES
P1	36" X 36"	1'-4"	(12) #7 REBAR	#3 @ 6" O.C.
P2	24" X 24"	2'-0"	(12) #5 REBAR	#3 @ 6" O.C.

NOTE: P1 HAS (2) TIES SPACED 2" FROM TOP OF PIER. SEE DETAIL 3/S7.

**1 FLOOR PLAN**  
3/16" = 1'-0"

Order Plans @ [www.ldilines.com](mailto:www.ldilines.com)

1925 Prospect Ave.  
Oxford, PA 17081-32814  
(407) 661-1100  
(407) 661-9101  
[www.e-p.com](http://www.e-p.com)

**LD**  
Chhaci & Peterson  
Architects Engineers Planners

CLIENT NAME  
**WAWA**  
260 W. BALTIMORE PIKE  
WAWA, PA 19063

PROJECT NAME  
**WAWA U45-FB-VA-M v2017.01**  
STORE #6661-STO  
NEWTOWN RD & STONEY POINT ST  
NORFOLK, VA

SHEET TITLE  
**FOUNDATION PLAN**

No.	Description	Date
1	PERMIT SET	05/11/2018
2	PRE-BID REVIEW SET	01/09/2019
3	BID SET	01/29/2019

PROJECT NO. 2170577  
DATE 05-11-2018  
DRAWN RC  
CHECKED JJ