

DRIVE THRU WINDOW DETAILS

GLAZING SCHEDULE ' INSULATED CLEAR GLASS UNIT LOW-E) ' INSULATED CLEAR FULLY 'EMPERED GLASS UNIT (LOW-E) G-3: 1/4" FULLY TEMPERED GLASS G-4: 1/4" CLEAR WIRE GLASS

NOTE: PROVIDE FULLY TEMPERED GLASS AT ALI HAZARDOUS LOCATIONS PER IBC SECTION 2406


I. PREWIRE ALL DOORS AND FRAME FOR SECURITY SYSTEM CONNECTIONS.


2. CARE SHALL BE TAKEN NOT TO SCRATCH OR MAR GLASS IN ANY FASHION, ANY FLAMED GLAZING WILL HAVE TO BE REPLACED PRIOR TO PROJECT CLOSEOU

3. ALL DOOR HARDWARE IS TO BE LEVER TYPE COMPLYING WITH THE AMERICANS WITH DISABILITIES ACT (ADA) AND ANY APPLICABLE STATE AND LOCAL ACCESSBILITY CODES.


4. CONTRACTOR SHALL COORDINATE ALL HARDWARE KEYING WITH THE OWNER AND OBTAIN OWNER'S APPROVAL PRIOR TO PLACING HARDWARE ORDER.

5. ALL CLOSERS ARE TO BE INSTALLED ON THE INTERIOR SIDE OF DOORS, UNLESS OTHERWISE NOTED.






ALUM. STOREFRONT -G-1. TYPICAL




3

NOTE-1: SAFETY GLAZING NOT REQUIRED AT LOWER LITES PER 2406.4, 7.1 (LESS THAN 9 SF) \$ 7.3 (TOP EDGE LESS THAN 36" ABOVE ALL ALUMINUM STOREFRONT SYSTEMS SHALL BE KAWNEER SYSTEM 451-T CENTER SET STOREFRONT

NOTE-2: REFER TO PLANS, ELEVATIONS AND WALL SECTIONS FOR ADDITIONAL HEAD AND JAMB DETAILS DEPENDING ON ACTUAL WALL SUBSTRATES AND FINISHES.



FRAME ELEVATIONS SCALE: 1/4"=1'-0'



NOT USED

WT ALUMINUM PASS THRU WINDOW

DOOR ELEVATIONS SCALE: 1/4-"=1'-0'

WINDOW ELEVATIONS

SCALE!/4-"=1'-0" - DRAWN FROM EXTERIOR VIEW

THE ARCHITECT/ENGINEER DOES NOT DEFINE THE SCOPE OF INDIVIDUAL TRADES SUBCONTRACTORS, MATERIAL SUPPLIERS, OR VENDORS. ANY SHEET NUMBERING SYSTE USED WHICH IDENTIFIES DISCIPLINES IS SOLELY TO SEPARATE ARCHITECTS AND ENGINEERS SCOPE: IT DOES NOT DEFINE A SUBCONTRACTOR'S SCOPE OF WORK, ANY DISCREPANCIES BETWEEN DRAWINGS, SPECIFICATIONS, CODES OR CONSTRUCTION SEQUENCING SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT PRIOR TO PROCEEDING. NO CONSIDERATION WILL BE GIVEN TO REQUESTS FOR CHANGE ORDERS FAILURE TO DESTAIN AND REVIEW THE COMPLETE SET OF CONSTRUCTION DOCUMENTS, C FOR FAILURE TO SEEK INTERPRETATION FROM ARCHITECT FOR DISCREPANCIES.

RESTAURANT IDGE ROAD GEORGIA AT WILLIS DRIVE STOCKBRIDGE, GEOF BRIDGE 4 HUDSON BOJANGLES

ISSUE DATE: 2-4-2019 PRELIM-BUDGET REVISION 1: = REVISION 2: = REVISION 4: I PROJECT #: 18-164-000 CONTENT: DOOR & WINDOW ELEVATIONS & SCHEDULES PROJECT ARCHITECT: ECE DRAWN BY: BH/CDD

Sheet A-5.1