	REVISION 1 -	DATE: -	SHEETS AFFECTED
ITEM #	DESCRIPTION		
1	-		-

Order Plans @ WWW.LDILine.com

SYMBOL LEGEND

DRAWING SUBTITLE — DETAIL NUMBER / DRAWING NUMBER; DETAIL, SCALE: 1/4" = 1'-0"

DETAIL MARKS — DETAIL NUMBER / DRAWING NUMBER

ELEVATION MARK — DRAWING NUMBER / ELEVATION NUMBER

SECTION MARKS — SECTION NUMBER / DRAWING NUMBER

ROOM TAG — ROOM NAME; XXX; ROOM NUMBER

DOOR NUMBER — #

EQUIPMENT — X-##

ELEVATION DATUM — ELEVATION REFERENCE; SLAB 0'-0"; ELEVATION HEIGHT

CEILING TAG — C1; 10'-0"; CEILING TYPE / CEILING HEIGHT

NOTE REFERENCE — #

WALL + BASE FINISH TAGS — W# B#

WALL TYPE — #

GENERAL NOTES

1. CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL PERMITS & INSPECTIONS REQUIRED FOR CERTIFICATE OF OCCUPANCY.
2. ALL WORK SHALL CONFORM TO THE REQUIREMENTS OF FEDERAL, STATE, AND LOCAL CODES, LAWS, RULES, & REGULATIONS OF ALL LEGALLY CONSTITUTED PUBLIC AUTHORITIES HAVING JURISDICTION. IN CASE OF CONFLICT BETWEEN REQUIREMENTS, THE MOST RESTRICTIVE SHALL APPLY.
3. CONTRACTOR TO VERIFY FIT & FINISH REQUIREMENTS FOR ALL PROJECT COMPONENTS, WITH OWNER, PRIOR TO ORDERING MATERIALS. REPORT CONFLICTING INFORMATION TO OWNER PRIOR TO PROCEEDING WITH WORK.
4. CONTRACTOR SHALL DISPOSE OF ALL DEMOLITION & CONSTRUCTION DEBRIS AS REQUIRED BY FEDERAL, STATE, AND LOCAL ORDINANCES.
5. CONTRACTOR SHALL STENCIL/LABEL ON ALL RATED WALLS IN CONCEALED AREAS THE FOLLOWING: "FIRE AND SMOKE BARRIER – PROTECT ALL OPENINGS".
6. BY THE USE OF THE DRAWINGS FOR CONSTRUCTION OF THE PROJECT, THE OWNER REPRESENTS THAT HE HAS REVIEWED AND APPROVED THE DRAWINGS, AND THAT THE CONSTRUCTION DOCUMENT PHASE OF THE PROJECT IS COMPLETE.
7. CONTRACTOR SHALL COORDINATE HIS WORK WITH ALL OTHER CONTRACTORS FURNISHING THE LABOR, MATERIALS, AND ALL WORK, SO THAT THE WORK AS A WHOLE SHALL BE EXECUTED AND COMPLETED WITHOUT CONFLICT OR DELAY.
8. CONTRACTOR SHALL COORDINATE THE REQUIREMENTS OF ANY AND ALL DRAWINGS INCLUDING ARCHITECTURAL, MECHANICAL, PLUMBING, AND ELECTRICAL. ANY CONFLICTS SHALL BE BROUGHT TO THE ATTENTION OF THE OWNER & ARCHITECT PRIOR TO ANY WORK.
9. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO ACQUAINT HIMSELF WITH THE DIMENSIONS OF ALL EQUIPMENT INCLUDED IN THIS PROJECT SO THAT PREPARATIONS CAN BE MADE TO PROVIDE ENTRY INTO THE FACILITY WITH SUFFICIENT CLEARANCE, AND TO ENSURE THAT ADEQUATE FLOOR SPACE IS AVAILABLE.
10. CONTRACTOR SHALL NEVER SCALE DRAWINGS. LOCATIONS FOR ALL PARTITIONS, WALLS, CEILINGS, ETC. WILL BE DETERMINED BY DIMENSIONS ON THE DRAWINGS. ANY SUCH DIMENSIONS MISSING FROM THE PLANS MUST BE BROUGHT TO THE ATTENTION OF THE OWNER & ARCHITECT IMMEDIATELY.
11. THE CONTRACTOR SHALL ADHERE TO THE DRAWINGS AND SPECIFICATIONS. SHOULD ANY ERROR OR INCONSISTENCY APPEAR REGARDING THE TRUE MEANING AND/OR INTENT OF THE DRAWINGS OR SPECIFICATIONS, THE CONTRACTOR SHALL IMMEDIATELY REPORT SAME TO THE ARCHITECT WHO WILL MAKE ANY NECESSARY CLARIFICATION, INTERPRETATION, OR REVISION AS REQUIRED.
12. IF THE CONTRACTOR DISCOVERS AN ERROR OR INCONSISTENCY AND PROCEEDS WITH WORK WITHOUT NOTIFYING THE OWNER & ARCHITECT OF ANY SUCH DISCREPANCIES, HE SHALL ASSUME ALL CHARGES AND MAKE ANY CHANGES TO HIS WORK MADE NECESSARY BY HIS FAILURE TO OBSERVE AND/OR REPORT THIS CONDITION.
13. IF THE INTENT OF THE DRAWINGS & SPECIFICATIONS ARE UNCLEAR, THE CONTRACTOR SHALL ASK THE ARCHITECT FOR CLARIFICATION, PRIOR TO PROCEEDING WITH WORK, IN THE FORM OF A WRITTEN R.F.I. (REQUEST FOR INFORMATION). THE ARCHITECT SHALL THEN RESPOND IN WRITING TO ALL APPROPRIATE PARTIES.
14. CONTRACTOR SHALL PROVIDE ADEQUATE PROTECTION OF WORK, MATERIALS, FIXTURES, ETC. IN LEASED SPACE FROM LOSS, DAMAGE, FIRE, THEFT, ETC.
15. WHEREVER THE TERM "OR EQUAL" IS USED, IT SHALL MEAN EQUAL PRODUCT AS APPROVED IN WRITING BY ARCHITECT.
16. IF THE CONTRACTOR PROPOSES A MATERIAL OR EQUIPMENT SUBSTITUTION HE SHALL PROVIDE ALL APPROPRIATE DOCUMENTATION AND INFORMATION REQUIRED FOR THE ARCHITECT TO DETERMINE WHETHER OR NOT THE SUBSTITUTION IS EQUAL TO THE SPECIFICATION.
17. CONTRACTOR SHALL PROVIDE AND INSTALL ALL NECESSARY INWALL FRAMING REQUIRED TO CARRY SHELF, HANGING, AND VALANCE LOADS, RAILINGS, ETC. AS PER PLANS.
18. PROVIDE SILICONE SEALANT AT ALL JOINTS AND INTERFACES OF ALL COUNTERTOPS, EQUIPMENT AND WALLS.
19. PROJECT SHALL BE LEFT CLEANED AND POLISHED AFTER COMPLETION OF WORK.
20. CONTRACTOR SHALL REFER TO THESE DOCUMENTS, AS WELL AS SPECIFICATIONS, FOR IDENTIFICATION OF ALL OWNER SUPPLIED ITEMS. CONTRACTOR SHALL VERIFY WITH OWNER, PRIOR TO ORDERING, WHICH ITEMS THE OWNER SHALL SUPPLY. ALL ITEMS NOT MARKED AS "OWNER SUPPLIED" ARE TO BE SUPPLIED BY THE CONTRACTOR. UNLESS NOTED OTHERWISE ALL ITEMS ARE TO BE INSTALLED BY GENERAL CONTRACTOR.
21. MINIMUM FLAME SPREAD CLASSIFICATION OF INTERIOR FINISHES SHALL CONFORM TO THE BUILDING CODE AND LOCAL GOVERNING BUILDING CODES/ORDINANCES.
22. CONTRACTOR SHALL CONTACT THE LOCAL FIRE MARSHALL, AND PROVIDE AND INSTALL FIRE EXTINGUISHERS PER THE FIRE MARSHALS DIRECTION, INCLUDING: TYPE, QUANTITY, AND LOCATIONS. AS A MINIMUM, CONTRACTOR SHALL PROVIDE FIRE EXTINGUISHERS HAVING A RATING OF 2-A10-BC FOR EVERY 3,000 S.F. OF FLOOR AREA AND TRAVEL DISTANCE TO AN EXTINGUISHER SHALL NOT EXCEED 75 FEET.
23. FOR CONSTRUCTION DETAILS NOT SHOWN, USE THE MANUFACTURER'S STANDARD DETAILS OR APPROVED SHOP DRAWINGS/DATA SHEETS IN ACCORDANCE WITH THE PROJECT SPECIFICATIONS.
24. CONTRACTOR SHALL CONTACT ALL UTILITY COMPANIES PRIOR TO COMMENCEMENT OF WORK TO VERIFY LOCATIONS OF ALL UNDERGROUND UTILITIES. NOTIFY ARCHITECT IMMEDIATELY IF CONFLICTS EXIST BETWEEN EXISTING UTILITIES AND NEW CONSTRUCTION. PATCH, REPAIR, AND/OR REPLACE ALL ADVERSELY AFFECTED FINISHES AND SURFACES AS REQ'D. UPON COMPLETION OF CONSTRUCTION. ALL PARKING AREA PAVEMENT AND NEW CONCRETE PADS SHALL TRANSITION SMOOTHLY.

LMHT Project No. 19100

THIS DRAWING IS THE PROPERTY OF THE ARCHITECT AND MAY NOT BE REPRODUCED OR USED WITHOUT HIS WRITTEN PERMISSION.

LMHT Associates
Architecture/Interiors
Janet Cathryn Mill Bnd.
Huntsville, AL 35816
phone: 256.534.0100 fax: 256.539.9399

STATE OF ALABAMA — TIMOTHY L. DEHMANN — 19311 — REGISTERED ARCHITECT — 7611

PROJECT: *SHERWIN WILLIAMS*
1980 GADSDEN HIGHWAY
TRUSSVILLE, AL 35235

DRAWING: ADDENDUM LIST

Revisions

REVISION	DATE

PROJECT DATE
1/17/2019

Drawn By
MTP

Checked By
TD

Sheet No.
G103