

EQUIVALENT NOMINAL PIPE SIZES	
PLAN SIZE (COPPER)	PEX
1/2"	1/2"
3/4"	1"
1"	1 1/4"
1 1/4"	1 1/2"
1 1/2"	2"
2"	NA
2 1/2"	NA
3"	NA
4"	NA

NOTE: REFER TO SPECIFICATIONS FOR APPROVED MANUFACTURERS.

PLUMBING FIXTURE SCHEDULE							DESCRIPTION
MARK	FIXTURE	C.W.	H.W.	WASTE	TRAP	VENT	
P1	A.D.A. WATER CLOSET	1/2"	-	3"	-	2"	ZURN, Z5561 FLUSH TANK PRESSURE ASSIST HIGH EFFICIENCY 1.0 GPF, WHITE, ELONGATED OPEN FRONT SEAT WITHOUT PLASTIC COVER Z5955SS-EL-ST5 AND ZURN Z5972-COMB TOILET KIT. NEW A.D.A. WATER CLOSET WITH COLD WATER TAP WITH SHUT-OFF VALVE. FLOOR MOUNTED VITREOUS CHINA, SIPHON-ACTION-JET. MOUNT FLUSH LEVER OPPOSITE OF WALL SUPPLIES AND STOPS: ZURN Z8804-XL-CR-PC. PROVIDE CAULKING AROUND BASE.
P2	A.D.A. LAVATORY	1/2"	1/2"	2"	1-1/2"	1-1/2"	ZURN Z5344 "WHITE" WALL MOUNT. WITH ZURN Z86500-XL METERING CENTERSET FAUCET NO LIFT ROD HOLE. WALL MOUNTED VITREOUS CHINA FRONT OVERLAY SELF RIMMING, FURNISH WITH ZURN Z8743-PC GRID AND OFFSET TAILPIECE, VANDAL-RESISTANT AERATOR, CENTERSET FAUCET WITH FACTORY SET FOR A MAXIMUM OF 0.25 GALLON FLOW PER ACTIVATION. ZURN Z1021WL-PC TRAP PRIMER WITH TRAP ARM AND ZURN Z8595-1INT AIR PROTECTOR COMBINATION KIT, ZURN Z8804-XL-LR-PC SUPPLIES AND STOPS. PROVIDE CAULKING AROUND LAVATORY.
P3	MOP SINK	1/2"	1/2"	3"	3"	2"	ZURN Z1996-36 FLOOR MOUNT; ZURN Z843M1-R FAUCET WITH VACUUM BREAKER, MOLDED HIGH DENSITY POLYPROPYLENE, MOD. ZURN Z1996 HOSE BRACKET, AND MOP HANGER. PROVIDE CAULK AROUND MOP SINK.
P4	A.D.A. ELECTRIC WATER COOLER	1/2"	-	2"	1-1/2"	1-1/2"	OASIS MODEL # PACSING REFRIGERATED STAINLESS STEEL, WALL MOUNTED, DOUBLE STATION, FINISH WITH WATER DRAIN WITH TRAP, SUPPLY, STOP AND WALL HANGER. PROVIDE WITH ZURN Z35174-001 APRON. EXACT COLOR AND FINISH TO BE SELECTED BY ARCHITECT. SUPPLIES AND STOPS: ZURN X8804-XL-LR-PC.
WH1	WATER HEATER	3/4"	3/4"	-	-	-	ELECTRIC WATER HEATER BRADFORD WHITE MODEL RE110U6 LOW-BOY WATER HEATER, GLASS LINED, 10 GALLON TANK, 1500 WATT ELEMENT, MINIMUM 6 YEAR WARRANTY, 120V 60HZ/60HZ, 10 GPH RECOVERY AT 60 DEG. TEMPERATURE RISE. FURNISH WITH ZURN VACUUM RELIEF VALVE ON COLD WATER RISER. PROVIDE SAFETY DRAIN PAN AND DRAIN LINE. FURNISH WITH HEAT TRAPS ON INLET AND OUTLET. PROVIDE EXPANSION TANK, 2.1 GALLON CAPACITY, WATTS MODEL PL105. MOUNT WATER HEATER ABOVE MOP SINK WITH 6"-8" CLEAR TO BOTTOM OF WATER HEATER SUPPORT PLATFORM.
FPWH	FREEZE PROOF WALL HYDRANT	3/4"	-	-	-	-	WOODFORD B65 NON-FREEZE TYPE WITH 3/4" H.P.T. OUTLET, PROVIDE RECESSED BOX TYPE WITH AUTOMATIC DRAINING ANTI-SIPHON VACUUM BREAKER, LENGTH TO SUIT WALL THICKNESS MOUNTED 30" ABOVE GRADE.
FCO	FLOOR CLEAN OUT	-	-	4"	4"	-	FLOOR CLEAN OUTS SHALL BE ZURN MODEL Z-1454 CAST IRON ADJUSTABLE FLOOR CLEAN OUT, CLEAN OUT SIZE SHALL MATCH LINE SIZE. PROVIDE ACCESSORIES SUCH AS CARPET MARKER OR TILE RECESS AS REQUIRED TO MATCH FLOOR FINISH.
TMV	THERMOSTATIC MIXING VALVE	1/2"	1/2"	-	-	-	SYMMONS MODEL 7-225-CK-F WITH A MINIMUM FLOW OF 0.5 GPM AND 2 GPM AT 10 PSI PRESSURE DIFFERENTIAL. TEMPERING VALVE MUST CONFORM TO ASSE 1070 AND BE SET AT 110 DEGREES FAHRENHEIT.
YCO	YARD CLEAN OUT	-	-	4"	4"	-	EXTERIOR CLEAN OUTS SHALL BE EQUAL TO J.R. SMITH MODEL 4240 ADJUSTABLE FLOOR CLEAN OUT WITH CAST IRON BODY AND TOP. CLEAN OUT SIZE SHALL MATCH LINE SIZE. PROVIDE WITH 24"x24"x8" THICK CONCRETE PAD AT GRADE.

NOTE:
 1. NO SUBSTITUTIONS ALLOWED.
 2. PROVIDE CAULK AROUND MOP SINK, WATER CLOSETS, AND LAVATORIES.
 3. PLUMBING FIXTURES P1, P2, P3, P4, WH1, TMV AND ASSOCIATED ACCESSORIES ARE BEING FURNISHED BY GC AS PART OF THE "BATH-IN-A-BOX". FIXTURES SHALL BE INSTALLED BY PC.
 4. PLUMBING FIXTURES FCO, YCO, AND FPWH SHALL BE FURNISHED AND INSTALLED BY PC.


pb2
 architecture
 +engineering
 100
 22738
 479.636.3545
 479.636.1209
 Engineer of Record
 Joshua Dole, Inc. d.o.p.
 Mississippi License No. 26626
 Certificate of Authority: 1813

STIPULATION FOR REUSE
 THIS DRAWING WAS PREPARED FOR
 GREENVILLE, MISSISSIPPI.
 DATE: 03/01/19 AND IT IS NOT
 TO BE REUSED FOR ANY OTHER
 PROJECT WITHOUT THE WRITTEN
 PERMISSION OF THE ARCHITECT.
 USE OF THIS DRAWING FOR ANY OTHER
 PROJECT REQUIRES THE SERVICES OF
 ENGINEERS, ARCHITECTS, AND/OR
 OTHER PROFESSIONALS WHOSE
 PROJECT IS NOT AUTHORIZED AND
 MAY BE CONTRARY TO THE LAW.

**FAMILY DOLLAR
 STORE**
 21 DALLRIVA DRIVE
 GREENVILLE, MISSISSIPPI
 JOB NUMBER: 2019.0072

ISSUE BLOCK	

CHECKED BY: JDM
 DRAWN BY: BEH
 PROTO CYCLE: 2017-01
 DOCUMENT DATE: 03-01-19



DOCUMENTS THAT DO NOT
 HAVE THE ARCHITECT OR
 ENGINEER OF RECORD
 SEAL AND SIGNATURE
 SHALL BE CONSIDERED
 NOT FOR CONSTRUCTION

**PLUMBING
 SCHEDULES**

SHEET:
P2.1

PRINTED: 3/1/2019 9:40 AM BY: Brandon Hampton LAST SAVED: 2/20/2019 11:16 AM BY: Brandon Hampton
 c:\family dollar\2019.00072_greenville.ms\drawings\mop\plumb\sheets\p021.dwg

Order Plans @ WWW.IDDLINE.COM