

1 FINISH PLAN & SIGNAGE PLAN  
A701 1/4" = 1'-0"

ROOM FINISH SCHEDULE						
ROOM NUMBER	ROOM NAME	FLOOR FINISH	BASE FINISH	WALL FINISH	CEILING FINISH	COMMENTS
101	ELEC. ROOM	FINISH CONCRETE	-	EXPOSED CMU	EXPOSED, STAINED	
102	STORAGE	FINISH CONCRETE	-	EXPOSED CMU	EXPOSED, STAINED	
103	FEMALE RESTROOM	POLY-CRETE	6" POLY-CRETE	PAINTED CMU	EXPOSED, STAINED	SEMI-GLOSS FINISH ON FLOORS AND WALLS
104	MALE RESTROOM	POLY-CRETE	6" POLY-CRETE	PAINTED CMU	EXPOSED, STAINED	SEMI-GLOSS FINISH ON FLOORS AND WALLS


KEYNOTE LEGEND	
KEYNOTE VALUE	KEYNOTE TEXT
30	MEN SIGN
31	WOMEN SIGN
34	ELECTRICAL ROOM SIGN

**SIGNAGE GENERAL NOTES:**

1. PROVIDE SIGNAGE AT ALL EXTERIOR DOORS LOCATIONS. VERIFY WITH OWNER LOCATIONS AND VERBIAGE, SEE DETAIL BELOW FOR MOUNTING HEIGHT
2. ALL DOOR SIGNAGE SHALL INCLUDE BRAILLE AND RAISED LETTERING; MEET ALL ADA & LOCAL ACCESSIBILITY REQUIREMENTS.
3. ALL SIGNAGE TO BE 8"x8", U.N.D.
4. G.C. TO PROVIDE SAMPLE OPTIONS PRIOR TO ORDER OR INSTALLATIONS.
5. G.C. TO PROVIDE ROOM ID SIGNS, MALE, FEMALE, AND ACCESSIBILITY SYMBOL OUTSIDE TOILET ROOMS. G.C. TO PROVIDE SAMPLE OPTIONS PRIOR TO INSTALLATION.

**FINISHES:**

1. ALL PARTIES RESPONSIBLE FOR DELIVERING FINISHES TO THE SITE SHOULD CHECK QUANTITIES AND DELIVERY DATES AS SOON AS BID IS AWARDED TO AVOID ANY RE-SELECTION OF MATERIAL.
2. THE GENERAL CONTRACTOR SHALL CAREFULLY STUDY AND COMPARE THE CONTACT DOCUMENTS AND FINISH PLANS AND SHALL AT ONCE REPORT TO THE ARCHITECT ANY ERROR, INCONSISTENCY OR OMISSION DISCOVERED.
3. ITEMS REQUIRING FINISH SELECTIONS THAT DO NOT APPEAR ON THE EXTENT OF FINISH DRAWINGS SHALL BE SELECTED FROM SHOP DRAWINGS, SUBMITTALS AND/OR SAMPLES AS REQUIRED BY THE ARCHITECTURAL SPECIFICATIONS.
4. UNLESS OTHERWISE NOTED, ALL FLOOR MATERIAL CHANGES SHALL OCCUR AT THE CENTERLINE OF A DOOR, WITH A DIVIDER STRIP. COLOR OF DIVIDER STRIP SHALL BE SELECTED FROM SUBMITTALS.
5. WOOD SHELVES IN CLOSETS AND STORAGE AREAS AND CASEWORK SUPPORTS ARE TO BE PAINTED TO MATCH ADJACENT WALL.
6. FOR ALL PRODUCTS INSTALLED, NOTE INDUSTRY STANDARDS AND MANUFACTURER SPECIFICATIONS FOR INSTALLATION.
7. PAINT SPECIFIED IS FOR COLOR ONLY. NOTE ARCHITECTURAL SPECIFICATIONS FOR MANUFACTURER AND TYPE OF FINISH.
8. ALL PLASTIC LAMINATE IS TO BE INSTALLED WITH CANPLAST VINYL EDGE.
9. UNDERSIDE OF EXPOSED WOOD DECK SHALL BE STAINED.
10. ALL EXPOSED STEEL SHALL BE PAINTED.
11. THE CONTRACTOR SHALL SUBMIT 8.5"x11" PHYSICAL DRAWDOWNS OF PAINT COLORS. DRAWDOWNS SHALL BE REFLECTIVE OF EACH PAINT COLOR IN TYPE SPECIFIED.



4 SIGNAGE DRAWING  
A701 3" = 1'-0"

Prepared by:

**JOEL AVILES ARCHITECTS**  
ARCHITECTS | PLANNING | RENDERINGS  
110 Main Street, Forest Park, Georgia 30226  
Tel: 404.876.7885 | email: info@joelaviles.com  
www.joelaviles.com  
© 2019 JOEL AVILES ARCHITECTS. ALL RIGHTS RESERVED.

Professional Seal:

Prepared for:  
CITY OF FOREST PARK

Consultants:

NO.	DATE	DESCRIPTIONS	BY
ISSUES / REVISIONS			

Project:  
**MAIN STREET RESTROOMS**

Project Address:  
NORTHEAST QUADRANT OF COLLEGE AND MAIN ST  
FOREST PARK, GA 30297

Drawing Title:  
**FLOOR FINISH PLAN & SIGNAGE PLAN**

Drawing Status:  
**RELEASED FOR CONSTRUCTION**

Scale: As indicated Drawn by: JA Reviewed by: JA  
Date/Time Printed: 2/7/2019 2:43:05 PM  
Date: 02.08.2019 Project number: 18031

Drawing:  
**A701**

Order Plans @

WWW.LDILine.com