



- LEGEND, SYMBOLS AND NOTES APPLY TO BOTH AD1.2.1 AND AD1.2.2 SHEETS. SOME ITEMS MAY NOT APPEAR ON THIS SHEET.
- SYMBOL LEGEND**
- ===== SOFFIT TO BE DEMOLISHED
  - PARTITION TO BE DEMOLISHED
  - 2x4 SUSPENDED ACoustICAL CEILING TO BE DEMOLISHED
  - 2x4 SUSPENDED VINYL CEILING TO BE DEMOLISHED
  - 2x4 SUSPENDED METAL CEILING TO BE DEMOLISHED
  - GYPSUM BOARD SOFFIT/CEILING TO BE DEMOLISHED
  - SOFFIT PANELS TO BE DEMOLISHED
  - EXISTING AIR DISTRIBUTION DEVICE TO BE DEMOLISHED
  - AIR DISTRIBUTION DEVICE TO BE DEMOLISHED
  - EXIT SIGN TO BE DEMOLISHED
  - EXISTING SUSPENDED LIGHT
  - SOFFIT LIGHT TO BE DEMOLISHED
  - 2X2 LIGHT TO BE DEMOLISHED
  - 4'0" SUSPENDED LIGHT TO BE DEMOLISHED
  - 4'0" SUSPENDED LIGHT TO BE DEMOLISHED
  - TRACK LIGHT TO BE DEMOLISHED
  - BUILDING MOUNTED LIGHT TO BE DEMOLISHED
  - TRACK LIGHT TO BE DEMOLISHED
  - COOLER/FREEZER LIGHT TO BE DEMOLISHED
- GENERAL NOTES**
1. RAISE, LOWER AND OR RELOCATE PLUMBING, MECHANICAL, ELECTRICAL, REFRIGERATION AND FIRE SPRINKLER LINES AND EQUIPMENT AS REQUIRED FOR DEMOLITION AND NEW WORK. VERIFY IN FIELD. SEE PLUMBING, MECHANICAL, ELECTRICAL, REFRIGERATION, FIRE SPRINKLER AND STRUCTURAL DRAWINGS FOR ADDITIONAL INFORMATION AND DEMOLITION REQUIREMENTS.
  2. GENERAL CONTRACTOR TO PREP SURFACES FOR FINISHES. ALL MONEY SERVICE RECORDS TO BE DEMOLISHED/SALVAGED AND BE RECORDED AS DIRECTED BY KROGER INC.
  3. REFER TO A.S.1 SERIES FOR ARCHITECTURAL STANDARD DETAILS (ASD'S) AND GENERAL INSTALLATION DETAILS (GSD'S).
- KEYED NOTES**
1. EXISTING SUSPENDED ACoustICAL CEILING TILE AND TO BE DEMOLISHED.
  2. GRID EXISTING VINYL FACED CEILING TILE AND GRID TO BE DEMOLISHED.
  3. EXISTING METAL FACED CEILING TILE AND GRID TO BE DEMOLISHED.
  4. EXISTING GYPSUM BOARD CEILING TO BE DEMOLISHED.
  5. DEMOLISH ALL COMPONENTS OF EXISTING DROP PARTITION/SOFFIT.
  6. MODIFY HEIGHT OF DOOR OPENING IN PREPARATION FOR NEW DOOR AND FRAME.
  7. THE EXISTING SALES FLOOR STRUCTURE, DUCT WORK, COUPLER, UNITS, SPRINKLER LINES, ETC. ARE TO BE CLEANED AND PREPPED FOR PAINT.
  8. DEMOLISH ALL COMPONENTS OF EXISTING WOODEN PLATFORM ABOVE THE COOLER, RESTROOMS AND BREAKROOM.
  9. DEMOLISH ALL COMPONENTS OF EXISTING WOODEN PLATFORM ABOVE THE DELI COOLER.
  10. DEMOLISH ALL COMPONENTS OF EXISTING MEZZANINE, INCLUDING BUT NOT LIMITED TO SOFFIT PANELS, STRUCTURE, FRAMING, LIGHTING, GYPSUM BOARD, WALLS, ETC.
  11. DEMOLISH ALL COMPONENTS OF EXISTING EXTERIOR CANOPY, INCLUDING BUT NOT LIMITED TO SOFFIT PANELS, FRAMING, LIGHTING, GYPSUM BOARD, STRUCTURE, ETC.
  12. DEMOLISH ALL COMPONENTS OF EXISTING RETAIL BRINDING, INCLUDING BUT NOT LIMITED TO SOFFITS, WIRING, CEILING LIGHTING, DUCT WORK, AIR DISTRIBUTION DEVICES, FRAMING, GYPSUM BOARD, ETC.
  13. THE REFRIGERATION CONTRACTOR IS TO DEMOLISH THE EXISTING COOLER/FREEZER IN ITS EXISTENCY.
  14. THE REFRIGERATION CONTRACTOR IS TO DEMOLISH THE EXISTING REFRIGERATION COIL.
  15. EXISTING AIR DISTRIBUTION DEVICE IS TO REMAIN. RE: MECHANICAL DRAWINGS.
  16. EXISTING MECHANICAL DUCT WORK IS TO REMAIN. THE DUCT WORK IS TO BE CLEANED AND PREPPED FOR PAINT. RE: MECHANICAL DRAWINGS.
  17. THE REFRIGERATION CONTRACTOR IS TO DEMOLISH THE EXISTING PROTOCOL UNIT LOCATED ABOVE THE DELI COOLER CEILING ON A WOODEN PLATFORM.
  18. THE REFRIGERATION CONTRACTOR IS TO DEMOLISH THE EXISTING PROTOCOL UNIT LOCATED ABOVE THE BREAKROOM CEILING ON A WOODEN PLATFORM.
  19. EXISTING GAS FIRED UNIT HEATER TO REMAIN.
  20. DEMOLISH EXISTING MECHANICAL DUCT WORK. RE: MECHANICAL DRAWINGS.
  21. DEMOLISH EXISTING AIR DISTRIBUTION DEVICE. RE: MECHANICAL DRAWINGS.
  22. EXISTING GAS LINE TO REMAIN. RE: MECHANICAL DRAWINGS.
  23. EXISTING GAS LINE TO BE DEMOLISHED. RE: MECHANICAL DRAWINGS.
  24. EXISTING HOOD TO BE DEMOLISHED. RE: MECHANICAL DRAWINGS.
  25. EXISTING LIGHT FIXTURE TO REMAIN. RE: ELECTRICAL DRAWINGS.
  26. DEMOLISH EXISTING EXIT SIGN. RE: ELECTRICAL DRAWINGS.
  27. DEMOLISH EXISTING LIGHT FIXTURE. RE: ELECTRICAL DRAWINGS.
  28. EXISTING EXTERIOR WALL MOUNTED LIGHT TO BE DEMOLISHED. NEW LIGHT TO BE REINSTALLED IN THE SAME LOCATION. RE: ELECTRICAL DRAWINGS.
  29. THE REFRIGERATION CONTRACTOR IS TO DEMOLISH THE EXISTING PROTOCOL UNIT LOCATED ABOVE THE PRODUCE COOLER.

**Kroger**  
**KROGER**  
**STORE #473**  
 2013 UNIVERSITY AVENUE  
 OXFORD, MISSISSIPPI 38655  
 A DEVELOPMENT OF  
**THE KROGER COMPANY**

**naos**  
 Naos Design Group Of Mississippi, PLLC.  
 MARC BREETZ, ARCHITECT  
 645 Lakeland East Drive, Suite 301  
 Flowood, Mississippi 39232  
 (p) 303.759.5777  
 (f) 720.360.4281  
**ARCHITECT OF RECORD**

**CDS**  
**COMMERCIAL DESIGN SYSTEMS, INC.**  
 13225 SW GALBREATH DRIVE  
 SHERWOOD, OREGON 97140  
 503.855.7000 (P) 503.625.5902  
**INTERIOR DECOR**

**Pickering Firm, Inc.**  
 Architects - Engineering  
 Planning - Surveying  
 6775 Lenox Center Court, Suite 300  
 Memphis, TN 38115  
 901.726.0319  
**ENGINEER OF RECORD:**  
 STRUCTURAL  
 MECHANICAL  
 ELECTRICAL  
 CIVIL ENGINEER

**SOFT**  
**INFRASTRUCTURE**  
 1500 CHESTER ROAD  
 CINCINNATI, OH 45216  
 T: 513-970-3000  
**LOW VOLTAGE**

**telgian**  
 TELGIAN CORPORATION  
 10230 SOUTH 50TH PLACE  
 SUITE 100  
 PHOENIX, AZ 85044  
 T: (602) 836-4426  
 HTTP://WWW.TELGIAN.COM  
**FIRE PROTECTION**

**ISSUE LOG**

NO.	REV.	DESCRIPTION	DATE
1	-	PERMIT SET	12/05/18
2	-	810 SET	03/21/19

JOB: 2018041 SCALE: 3/32" = 1'-0"  
 SHEET NO.

**AD1.2.1**  
 PARTIAL DEMOLITION  
 REFLECTED CEILING PLAN WEST  
COPYRIGHT © 2018 BY CDS GROUP OF MEMBERS. ALL RIGHTS RESERVED. ON-PAPER PRODUCTION. NOT FOR REPRODUCTION IN ANY FORM. ALL RIGHTS RESERVED. FOR ANY PURPOSES WITHOUT EXPRESS WRITTEN CONSENT FROM CDS.

**MEZZANINE DEMOLITION**  
**02 REFLECTED CEILING PLAN**  
 SCALE: 3/32" = 1'-0"

**PARTIAL DEMOLITION**  
**01 REFLECTED CEILING PLAN WEST**  
 SCALE: 3/32" = 1'-0"

