

Order Plans @ www.LDILine.com



- SYMBOL LEGEND**
- EXISTING ROOF TOP EQUIPMENT
 - ROOF TOP EQUIPMENT TO BE DEMOLISHED
 - - - EXISTING GAS LINE, RE: MECHANICAL DRAWINGS
 - - - DEMOLISHED GAS LINE, RE: MECHANICAL DRAWINGS
- GENERAL NOTES**
1. SEAL ALL ROOF PENETRATIONS.
 2. ALL DEBRIS AND FOREIGN MATTER SHOULD BE REMOVED FROM THE ROOF'S SURFACE AND DISPOSED PROPERLY OFF-SITE.
 3. REFER TO AS-1 SERIES FOR ARCHITECTURAL STANDARD DETAILS (ASD'S) AND GENERAL INSTALLATION DETAILS (GID'S).

- KEYED NOTES**
1. EXISTING DOCK HOOD TO REMAIN.
 2. EXISTING DOOR HOOD TO REMAIN.
 3. REMOVE EXISTING DOOR HOOD.
 4. REMOVE EXISTING ROOF HATCH AND PREP FOR DECKING INFILL. RE: STRUCTURAL DRAWINGS.
 5. REMOVE EXISTING CHIMNEY FLASHING.
 6. REMOVE EXISTING CHIMNEY STOP FLASHING.
 7. REMOVE EXISTING CHIMNEY FLASHING AND PREP FOR DECKING INFILL. RE: STRUCTURAL DRAWINGS.
 8. REMOVE EXISTING CHIMNEY STOP, GUTTER, DOWNSPOUT AND FLASHING.
 9. REMOVE EXISTING CHIMNEY FLASHING AND PREP FOR DECKING INFILL. RE: STRUCTURAL DRAWINGS.
 10. REMOVE EXISTING CHIMNEY FLASHING AND PREP FOR DECKING INFILL. RE: STRUCTURAL DRAWINGS.
 11. REMOVE EXISTING RETAIL BUILDING IN ITS ENTIRETY, INCLUDING BUT NOT LIMITED TO ROOFING, INSULATION FLASHING, DECKING, STRUCTURE, ROOF TOP UNITS, EXHAUST FANS, GAS PIPING, ETC.
 12. REMOVE EXISTING REFRIGERATION CONDENSER UNIT AND CURB. PREP FOR DECKING INFILL. RE: STRUCTURAL DRAWINGS.
 13. REMOVE EXISTING REFRIGERATION PIPE CHASE. PREP FOR DECKING INFILL. RE: STRUCTURAL DRAWINGS.
 14. REMOVE METAL DECK, INSULATION, AND ROOFING AS NECESSARY TO INSTALL NEW REFRIGERATION OR MECHANICAL PIPE CHASE PER ASD-78. RE: REFRIGERATION AND MECHANICAL DRAWINGS.
 15. EXISTING ROOF TOP UNIT AND CURB TO REMAIN. RE: MECHANICAL DRAWINGS.
 16. EXISTING MECHANICAL FLUE TO REMAIN. RE: MECHANICAL DRAWINGS.
 17. REMOVE EXISTING ROOF TOP UNIT AND CURB.
 18. REMOVE EXISTING ROOF TOP UNIT AND CURB. PREP FOR DECKING INFILL. RE: STRUCTURAL DRAWINGS.
 19. REMOVE EXISTING MAKE UP AIR UNIT AND CURB. PREP FOR DECKING INFILL. RE: STRUCTURAL DRAWINGS.
 20. REMOVE EXISTING EXHAUST FAN AND CURB.
 21. REMOVE EXISTING EXHAUST FAN AND CURB. PREP FOR DECKING INFILL. RE: STRUCTURAL DRAWINGS.
 22. REMOVE EXISTING EXHAUST FAN AND CURB. PREP FOR NEW EXHAUST FAN AND CURB. RE: ASD-88 AND STRUCTURAL AND MECHANICAL DRAWINGS.
 23. REMOVE METAL DECK, INSULATION AND ROOFING AS NECESSARY TO INSTALL NEW ROOF EXHAUST FAN. RE: ASD-88 AND MECHANICAL DRAWINGS.
 24. REMOVE METAL DECK, INSULATION AND ROOFING AS NECESSARY TO INSTALL NEW ROOF EXHAUST FAN. RE: ASD-88 AND MECHANICAL DRAWINGS.
 25. REMOVE EXISTING CONDENSING AND CURB. PREP FOR DECKING INFILL. RE: STRUCTURAL DRAWINGS.
 26. REMOVE METAL DECK, INSULATION AND ROOFING AS NECESSARY TO INSTALL NEW CONDENSING UNIT AND CURB. RE: ASD-88 AND MECHANICAL DRAWINGS.
 27. EXISTING PLUMBING VENT TO REMAIN. RE: PLUMBING DRAWINGS.
 28. REMOVE EXISTING PLUMBING VENT AND PREP FOR DECKING INFILL. RE: STRUCTURAL DRAWINGS.
 29. REMOVE METAL DECK, INSULATION, AND ROOFING AS NECESSARY TO INSTALL NEW PLUMBING VENT. RE: PLUMBING DRAWINGS.
 30. EXISTING GAS LINES TO REMAIN. PREP FOR PAINT. RE: MECHANICAL DRAWINGS.
 31. REMOVE EXISTING GAS PIPING. RE: MECHANICAL DRAWINGS.
 32. REMOVE EXISTING SATELLITE DISH AND BALLASTED BASE. RE: ELECTRICAL DRAWINGS.
 33. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR THE ABATEMENT AND REMOVAL OF THE FOLLOWING ITEMS PER THE ASBESTOS REPORT:
 - ASBESTOS-CONTAINING SEALANT ASSOCIATED WITH THE WHITE CEMENT ON THE ROOF AROUND PENETRATIONS
 - BLACK CEMENT ON THE ROOF AROUND PENETRATIONS CONTAINS ASBESTOS IN CONCENTRATIONS LESS THAN 1%.
 - GRAY CEMENT ON THE ROOF AROUND PENETRATIONS CONTAINS ASBESTOS IN CONCENTRATIONS LESS THAN 1%.
 34. REMOVE METAL DECK, INSULATION, AND ROOFING AS NECESSARY TO INSTALL NEW PLUMBING ROOF HYDRANT. RE: PLUMBING DRAWINGS.

Kroger
KROGER
STORE #473
 2013 UNIVERSITY AVENUE
 OXFORD, MISSISSIPPI 38655
 A DEVELOPMENT OF THE KROGER COMPANY

naos
 Naos Design Group Of Mississippi, PLLC.
 MARC BREETZ, ARCHITECT
 645 Lakeland East Drive Suite 101
 Flowood, Mississippi 39232
 (p) 303.759.5777
 (f) 720.360.4281
 ARCHITECT OF RECORD

CDS
 COMMERCIAL DESIGN SYSTEMS, INC.
 1925 SW GALBREATH DRIVE
 SHERWOOD, OREGON 97140
 503.885.7000 (P) 503.825.9002
 INTERIOR DECOR

Pickering
 Pickering Firm, Inc.
 Architects - Engineers
 Planning - Surveying
 6775 Lenox Center Court, Suite 300
 Memphis, TN 38115
 901.726.0818
 ENGINEER OF RECORD:
 STRUCTURAL
 MECHANICAL
 ELECTRICAL
 CIVIL ENGINEER

SOFT
 INFRASTRUCTURE
 1600 CHESTER ROAD
 CHESTERTON, IN 46716
 T: 305-870-3009
 LOW VOLTAGE

telgian
 TELGIAN CORPORATION
 10230 SOUTH 50TH PLACE
 SUITE 100
 PHOENIX, AZ 85044
 T: (677) 836-4426
 HTTP://WWW.TELGIAN.COM
 FIRE PROTECTION


ISSUE LOG

NO.	REV.	DESCRIPTION	DATE
1	-	PERMIT SET	12/06/18
2	-	BID SET	03/21/19

JOB: 2018041 SCALE: 3/32" = 1'-0"

SHEET NO. **AD1.3.2**
 PARTIAL DEMOLITION ROOF PLAN EAST

PARTIAL 01 ROOF PLAN EAST
 SCALE: 3/32" = 1'-0"



COPYRIGHT © 2018 NAOS DESIGN GROUP OF MISSISSIPPI, PLLC. THESE DRAWINGS OR PARTS THEREOF MAY NOT BE REPRODUCED, COPIED, OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, WITHOUT THE WRITTEN CONSENT OF NAOS.