

**DEMO KEYNOTES**

1. DEMO EXISTING GREASE HOOD, GREASE DUCT, MAKE UP AIR DUCT, MAKE UP AIR FAN ON ROOF, EXHAUST FAN ON ROOF, ANSUL SYSTEM, PULL STATION, AND GAS PIPE UP THRU ROOF.
2. DEMO EXISTING GREASE HOOD, GREASE DUCT, EXHAUST FAN ON ROOF, ANSUL SYSTEM, AND PULL STATION.
3. DEMO EXISTING EXHAUST FAN, EXHAUST DUCT, AND GAS PIPE UP THRU ROOF.
4. DEMO ALL DIFFUSERS, RETURN GRILLES, T'STAT, AND DUCT WORK UP TO RDU-3E ON ROOF.
5. DEMO ALL GRILLES AND EXHAUST DUCT UP TO EF-4E ON ROOF.
6. DEMO PORTION OF SUPPLY DUCT, DIFFUSERS, AND CAP DUCT.
7. DEMO PORTION OF RETURN DUCT, RETURN GRILLES, AND CAP DUCT.
8. DEMO EXHAUST GRILLES AND EXHAUST DUCT TO MAIN DUCT TRUNK.
9. DEMO ALL MECHANICAL EQUIPMENT, DUCT, DIFFUSERS, GRILLES, AND THERMOSTATS.
10. DEMO GAS PIPE FROM EMERGENCY GENERATOR CAP PIPE.
11. DEMO PORTION OF SUPPLY DUCT, DIFFUSERS, AND GRILLE. CAP DUCT.
12. DEMO EXHAUST DUCT, DIFFUSERS, T'STAT, AND GRILLES CONNECTED TO RDU-3E.

**EXISTING GENERAL HVAC NOTES**


1. THESE DRAWINGS ARE BASED ON GENERAL STORE DRAWINGS. CONTRACTOR TO FIELD VERIFY EXISTING CONDITIONS PRIOR TO BIDDING OF PROJECT. WHERE ANY EQUIPMENT ON ROOF IS DISTURBED, IT IS THE HVAC CONTRACTOR'S RESPONSIBILITY TO COORDINATE WITH THE GENERAL CONTRACTOR FOR THE REPAIR OF ANY ROOFING ITEMS AFTER THE COMPLETION OF HVAC WORK.
2. ALL EQUIPMENT SHALL BE CONSIDERED EXISTING UNLESS OTHERWISE NOTED. EXISTING EQUIPMENT NOT SHOWN SHALL REMAIN UNCHANGED.
3. DAMAGED DIFFUSERS: IT IS THE CONTRACTOR'S RESPONSIBILITY TO IDENTIFY AND REPAIR ANY DAMAGED DIFFUSERS. PRE-BID, LOCATE AND ITEMIZE EXPECTED QUANTITY OF DAMAGED DIFFUSERS TO BE REPLACED. CONSTRUCTION: COORDINATE WITH KROGER ENGINEER FOR REPLACING OF DAMAGED DIFFUSERS.
4. EXISTING DIFFUSERS TO REMAIN: IT IS CONTRACTOR'S RESPONSIBILITY TO CLEAN ALL EXISTING DIFFUSERS AND RETURN GRILLES THAT ARE NOT REPLACED.
5. DEMOED DUCTWORK AND DIFFUSERS SHALL BE TAKEN DOWN AND PROPERLY DISPOSED OF.
6. ALL EXISTING SALES FLOOR DUCTWORK IS TO BE CLEANED AND PREPARED FOR PAINT, BOTH NEW AND EXISTING.



**KROGER**  
STORE #473

2013 UNIVERSITY AVENUE  
OXFORD, MISSISSIPPI 38655

A DEVELOPMENT OF  
THE KROGER COMPANY



**Naos Design Group Of Mississippi, PLLC.**

MARC BREETZ  
ARCHITECT

645 Lakeland East Drive  
Suite 101  
Flowood, Mississippi 39232  
(p) 303.759.5777  
(f) 720.360.4281

ARCHITECT OF RECORD



**CDS**  
COMMERCIAL DESIGN SYSTEMS, INC.

13825 SW GALLBREATH DRIVE  
SHERWOOD, OREGON 97140  
503.855.7000 (P) 503.825.8902

INTERIOR DECOR



**Pickering Firm, Inc.**  
Architecture - Engineering  
Planning - Surveying

6775 Lenox Center Court, Suite 300  
Memphis, TN 38115  
901.728.0810

ENGINEER OF RECORD:  
STRUCTURAL  
MECHANICAL  
ELECTRICAL  
CIVIL ENGINEER



**V-SOFT**  
INFRASTRUCTURE


11280 CHESTER ROAD  
CINCINNATI, OH 45246  
T: 513-950-3810  
LOW VOLTAGE



**telgian**  
TELGIAN CORPORATION  
10230 SOUTH 50TH PLACE  
SUITE 100  
PHOENIX, AZ 85044  
T: (602) 938-4426  
HTTP://WWW.TELGIAN.COM  
FIRE PROTECTION

**ISSUE LOG**

NO.	REV.	DESCRIPTION	DATE
1	-	PERMIT SET	12/06/18
2	-	BID SET	03/21/19



01 PARTIAL HVAC DEMO PLAN WEST  
SCALE: 3/32" = 1'-0"

KEY PLAN  
SCALE: NOT TO SCALE

JOB: 2018041 SCALE: AS SHOWN  
SHEET NO. MD1.1.1  
PARTIAL HVAC DEMO PLAN WEST

Order Plans @ WWW.DILine.com