


GENERAL NOTES

- REFER TO SHEET ED.1 FOR PROJECT GENERAL NOTES, LEGEND AND ABBREVIATIONS.
- THE CONTRACTOR SHALL ALLOW FOR THE DISCONNECTION AND DEMOLITION OF POWER SUPPLIES TO ALL EQUIPMENT IDENTIFIED ON THE PLANS FOR DEMOLITION AND/OR RELOCATION. (SHOWN BOLD) DISCONNECT AND REMOVE WIRING TO SOURCE. REFER TO THE F1 PLANS FOR ADDITIONAL INFORMATION. ELECTRICAL SUPPLIES TO EXISTING SERVICES/EQUIPMENT NOT IDENTIFIED FOR DEMOLITION TO REMAIN.
- EACH OF THE FOLLOWING ELECTRICAL SYSTEMS SHALL REMAIN IN ITS ENTIRETY UNLESS OTHERWISE NOTED. SYSTEMS TO INCLUDE BUT NOT LIMITED TO POWER, TELEPHONE, DATA, PAGING AND TV CABLING SYSTEMS. THE EXISTING SECURITY CAMERAS, MONITORS, AND WIRING SHALL REMAIN. REMOVE POWER TO OWNER'S EQUIPMENT BEING REMOVED. REMOVE ALL UNUSED EQUIPMENT, DEVICES, EXPOSED CONDUIT, AND WIRING BACK TO THE SOURCE INCLUDING THE NEXT UPSTREAM DEVICE, EQUIPMENT OR THE PANEL BOARD. REMOVE UNUSED WIRING IN CONDUITS CONCEALED IN WALLS, FLOORS AND ABOVE LAY-IN CEILING AND ABANDON THE CONDUITS IN PLACE. MODIFY EXISTING CIRCUITS AS REQUIRED TO MAINTAIN CIRCUIT CONTINUITY TO EXISTING EQUIPMENT AND DEVICES THAT ARE TO REMAIN DURING DEMOLITION AND AFTER. ALL EXISTING SYSTEMS SHALL REMAIN OPERATIONAL DURING THE PHASED TRANSITION UNTIL THE NEW SYSTEMS ARE OPERATIONAL.
- COORDINATE DEMOLITION WITH THE OWNER'S PROJECT MANAGER AND PHASING PLAN BEFORE EQUIPMENT, DEVICES, OR WIRING IS REMOVED.
- REMOVE ALL DEMOLISHED MATERIALS FROM THE SITE AND DISPOSE PROPERLY AND LEGALLY.
- FIELD VERIFY EXISTING CONDITIONS AND PROJECT SCOPE PRIOR TO BEGINNING THE PROJECT.
- INCLUDE IN THE SCOPE OF WORK, TEMPORARY POWER FOR EQUIPMENT DEVICES, AND OWNER'S EQUIPMENT THAT MUST BE TEMPORARILY RELOCATED DUE TO CONSTRUCTION PHASING. CONSIDER MOVING OWNER'S EQUIPMENT SUCH AS CHECKSTANDS, REFRIGERATED CASES, ETC. SEE THE PHASING PLAN AND COORDINATE WITH OWNER'S PROJECT MANAGER'S OFFICE.
- PROVIDE TEMPORARY CIRCUITS TO DEVICES AND EQUIPMENT WHERE THE SOURCE SUCH AS THE PANEL IS REMOVED IN AN EARLIER PHASE. THIS SHOULD INCLUDE BUT NOT BE LIMITED TO TEMPORARILY RELOCATING THE PANEL AND MODIFYING THE EXISTING WIRING AND BRANCH WIRING AS REQUIRED.
- CAREFULLY REMOVE EQUIPMENT AND DEVICES THAT ARE NOTED TO BE REMOVED, STORED AND REUSED. REPLACE ANY OF THESE THAT ARE DAMAGED DURING REMOVAL, STORAGE, OR REINSTALLATION.
- EXISTING SWITCHBOARDS, PANELS, TRANSFORMERS, AND ASSOCIATED WIRING SHALL REMAIN UNLESS OTHERWISE INDICATED. SEE SINGLE LINE DIAGRAM FOR DISTRIBUTION EQUIPMENT AND FEEDERS TO BE REMOVED. ALL EQUIPMENT SHOWN ON THIS PLAN IS EXISTING.
- OUTLET BOX AND WIRING IN EXISTING WALLS TO REMAIN U.O.I.
- REFER TO SHEET ED.1 FOR THE LOCATION OF EXISTING WALLS THAT REMAIN. PATCH THE WALL OR PROVIDE A BLANK COVERPLATE FOR THE OUTLET BOX. COORDINATE THE REQUIREMENTS WITH THE OWNER'S PROJECT MANAGER.
- ALL EXISTING EXTERIOR POWER DEVICES AND RECEPTACLES ON THE ROOF, AND ASSOCIATED WIRING SHALL REMAIN U.O.I.
- TURN OFF ALL UNUSED CIRCUIT BREAKERS AND RELABEL AS SPARES.
- DISCONNECT, ISOLATE, AND MAKE SAFE ALL ELECTRICAL CONNECTIONS TO DEMOLISHED AND RELOCATED EQUIPMENT.
- REFER TO MECHANICAL AND PLUMBING DEMOLITION DRAWINGS FOR EQUIPMENT BEING DEMOLISHED. REMOVE CIRCUITS ASSOCIATED WITH DEMOLISHED EQUIPMENT BACK TO THE SOURCE UNLESS OTHERWISE INDICATED. CIRCUIT TO EQUIPMENT REMAINING TO REMAIN AS IS AND BE PROTECTED AS NECESSARY.
- THE CONTRACTOR IS TO DEMOLISH THE EXISTING FIRE ALARM AND SECURITY SYSTEMS. COORDINATE WITH THE OWNER'S PROJECT MANAGER REGARDING THE PHASING/SEQUENCE/TIMING OF THE REMOVAL AND REPLACEMENT TO ENSURE THAT ADEQUATE COVERAGE IS MAINTAINED AT ALL TIMES TO THE SATISFACTION OF THE OWNERS AND THE A.H.J.
- REMOVE ALL DEVICES AND WIRING IN WALLS BEING DEMOLISHED BACK TO SOURCE MAINTAINING CIRCUIT CONTINUITY TO OTHER DEVICES ON THE CIRCUIT(S) THAT REMAIN.
- DEMOLITION WORK TO BE PHASED IN ACCORDANCE WITH PROGRAM/SCHEDULE AGREED WITH THE OWNER'S PROJECT MANAGER.

KEYNOTES

- AFTER NEW GENERATOR IS INSTALLED AND COMMISSIONED, EXISTING GENERATOR TO BE DEMOLISHED AND FEEDERS DEMOLISHED BACK TO SOURCE AFTER CUT OVER TO NEW SYSTEM. CONTRACTOR TO ENSURE ALL REQUIRED EMERGENCY/LIFE SAFETY SYSTEMS ARE OPERATIONAL AT ALL TIMES (REFER SHEET E6.2 AND E1-3.2 FOR ADDITIONAL INFORMATION).
- EXISTING TELEPHONE/DATA DEMARINATION BOARD TO REMAIN. CONTRACTOR TO PROVIDE PROTECTION TO BOARD THROUGHOUT ALL PHASES OF CONSTRUCTION.
- EXISTING REFRIGERANT COOLANT PUMP TO BE DEMOLISHED. DISCONNECT AND DEMOLISH FEEDER BACK TO SOURCE.
- DISCONNECT EXISTING WATER HEATER AND RECLAIM TANKS AND RETAIN CIRCUITS FOR RECONNECTION TO NEW UNITS. (SEE SHEET E1.3.1 FOR RECONNECTION OF NEW UNITS).
- EXISTING MAIN SWITCH BOARD TO REMAIN. REFER SHEET E6.2 FOR DETAILS OF MODIFICATIONS.
- EXISTING PANEL BOARD(S) TO REMAIN. MAKE ADJUSTMENTS AS SHOWN ON RESPECTIVE PANEL SCHEDULE(S) AND SINGLE LINE DIAGRAM AND/OR REQUIRED FOR NEW/ALTERED CIRCUITS. UPDATE EXISTING LEGEND CARDS.
- EXISTING LIGHTING CONTRACTORS TO BE DEMOLISHED. DEMOLISH CONDUIT, WIRING ETC BACK TO SOURCE.
- EXISTING TRANSFER SWITCH TO BE DEMOLISHED - REFER TO SHEET E6.2 FOR ADDITIONAL INFORMATION.
- EXISTING BALER TO BE DEMOLISHED. DEMOLISH DISCONNECT, CONDUIT AND WIRING BACK TO SOURCE.
- DISCONNECT AND REMOVE EXISTING DOCK LIGHTS BACK TO SOURCE.
- EXISTING COMPACTOR TO REMAIN "AS IS".
- EXISTING UTILITY TRANSFORMER TO BE REMOVED BY UTILITY COMPANY. DEMOLISH EXISTING LATERALS AFTER TRANSFER TO NEW SYSTEMS - REFER TO SHEET E6.2 FOR ADDITIONAL INFORMATION.
- EXISTING PANEL BOARD(S) TO BE DEMOLISHED. DEMOLISH EXISTING FEEDER AND BRANCH CIRCUITS BACK TO SOURCE.
- EXISTING ELECTRICAL SERVICES IN THIS AREA TO REMAIN AS IS UNLESS OTHERWISE SHOWN.
- DISCONNECT, REMOVE AND DEMOLISH CONDUIT AND WIRING BACK TO SOURCE FOR ALL EQUIPMENT IN THIS AREA SCHEDULED FOR DEMOLITION (NOTED IN BOLD). MODIFY CIRCUITS AS REQUIRED TO MAINTAIN CONTINUITY TO REMAINING EQUIPMENT/OUTLETS WHERE AFFECTED BY UPSTREAM CHANGES.
- EXISTING RECOIL UNIT TO BE DEMOLISHED. DISCONNECT AND DEMOLISH FEEDER BACK TO SOURCE.
- DISCONNECT EXISTING WATER HEATER ABOVE. DEMOLISH CONDUIT AND WIRING BACK TO SOURCE.



01 PARTIAL POWER DEMOLITION PLAN WEST
SCALE: 3/32" = 1'-0"

KROGER
STORE #473

2013 UNIVERSITY AVENUE
OXFORD, MISSISSIPPI 38655

A DEVELOPMENT OF
THE KROGER COMPANY

naos
Naos Design
Group Of
Mississippi,
PLLC.

MARC BREETZ
ARCHITECT

645 Lakeland East Drive
Suite 101
Flowood, Mississippi 39232
(p) 303.759.5777
(f) 720.360.4281

ARCHITECT OF RECORD

CDS
COMMERCIAL DESIGN SYSTEMS,
INC.

13825 SW GALLBREATH DRIVE
SHERWOOD, OREGON 97140
503.855.7000 (p)503.855.8502

INTERIOR DECOR

Pickering Firm, Inc.
Architecture - Engineering
Planning - Surveying

6775 Lenox Center Court, Suite 300
Memphis, TN 38115
901.726.8816

ENGINEER OF RECORD:
STRUCTURAL
MECHANICAL
ELECTRICAL
CIVIL ENGINEER

V-SOFT
INFRASTRUCTURE

11280 CHESTER ROAD
CINCINNATI, OH 45248
T: 513-990-3819
LOW VOLTAGE

telgian
TELGIAN CORPORATION
10230 SOUTH 60TH PLACE
SUITE 100
PHOENIX, AZ 85044
T: (677) 836-4426
HTTP://WWW.TELGIAN.COM
FIRE PROTECTION

ISSUE LOG

NO.	REV.	DESCRIPTION	DATE
1	-	PERMIT SET	12/06/18
2	-	BID SET	03/21/19

JOB	SCALE
2019041	AS SHOWN
SHEET NO.	

ED1.2.1
PARTIAL POWER DEMOLITION
PLAN WEST

COPYRIGHT © 2018 NAOS DESIGN GROUP OF MISSISSIPPI, PLLC. THESE DRAWINGS, OR ANY PART THEREOF, MAY NOT BE REPRODUCED, COPIED, EITHER WHOLLY OR IN PART, FOR ANY PURPOSE, WITHOUT PRIOR WRITTEN CONSENT FROM NAOS.