



**02 POWER DEMOLITION PLAN - MEZZANINE**  
SCALE: 3/32" = 1'-0"

**GENERAL NOTES**

- REFER TO SHEET ED.1 FOR PROJECT GENERAL NOTES, LEGEND AND ABBREVIATIONS.
- THE CONTRACTOR SHALL ALLOW FOR THE DISCONNECTION AND DEMOLITION OF POWER SUPPLIES TO ALL EQUIPMENT IDENTIFIED ON THE PLANS FOR DEMOLITION AND/OR RELOCATION. (SHOWN BOLD) DISCONNECT AND REMOVE WIRING TO SOURCE. REFER TO THE F1 PLANS FOR ADDITIONAL INFORMATION. ELECTRICAL SUPPLIES TO EXISTING SERVICES/EQUIPMENT NOT IDENTIFIED FOR DEMOLITION TO REMAIN.
- EACH OF THE FOLLOWING ELECTRICAL SYSTEMS SHALL REMAIN IN ITS ENTIRETY UNLESS OTHERWISE NOTED. SYSTEMS TO INCLUDE BUT NOT LIMITED TO POWER, TELEPHONE, DATA, PAGING AND TV CABLING SYSTEMS. THE EXISTING SECURITY CAMERAS, MONITORS, AND WIRING SHALL REMAIN. REMOVE POWER TO OWNER'S EQUIPMENT BEING REMOVED. REMOVE ALL UNUSED EQUIPMENT, DEVICES, EXPOSED CONDUIT, AND WIRING BACK TO THE SOURCE INCLUDING THE NEXT UPSTREAM DEVICE, EQUIPMENT OR THE PANEL BOARD. REMOVE UNUSED WIRING IN CONDUITS CONCEALED IN WALLS, FLOORS AND ABOVE LAY-IN CEILING AND ABANDON THE CONDUITS IN PLACE. MODIFY EXISTING CIRCUITS AS REQUIRED TO MAINTAIN CIRCUIT CONTINUITY TO EXISTING EQUIPMENT AND DEVICES THAT ARE TO REMAIN DURING DEMOLITION AND AFTER. ALL EXISTING SYSTEMS SHALL REMAIN OPERATIONAL DURING THE PHASED TRANSITION UNTIL THE NEW SYSTEMS ARE OPERATIONAL.
- COORDINATE DEMOLITION WITH THE OWNER'S PROJECT MANAGER AND PHASING PLAN BEFORE EQUIPMENT, DEVICES, OR WIRING IS REMOVED.
- REMOVE ALL DEMOLISHED MATERIALS FROM THE SITE AND DISPOSE PROPERLY AND LEGALLY.
- FIELD VERIFY EXISTING CONDITIONS AND PROJECT SCOPE PRIOR TO BEGINNING THE PROJECT.
- INCLUDE IN THE SCOPE OF WORK, TEMPORARY PROTECTIVE EQUIPMENT, DEVICES, AND OWNER'S EQUIPMENT THAT MUST BE TEMPORARILY RELOCATED DUE TO CONSTRUCTION PHASING. CONSIDER MOVING OWNER'S EQUIPMENT SUCH AS CHECKSTANDS, REFRIGERATED CASES, ETC. SEE THE PHASING PLAN AND COORDINATE WITH OWNER'S PROJECT MANAGER REGARDING PHASING.
- PROVIDE TEMPORARY CIRCUITS TO DEVICES AND EQUIPMENT WHERE THE SOURCE SUCH AS THE PANEL IS REMOVED IN AN EARLIER PHASE. THIS SHOULD INCLUDE BUT NOT BE LIMITED TO TEMPORARILY RELOCATING THE PANEL AND MODIFYING THE EXISTING FEEDER AND BRANCH CIRCUIT WIRING AS REQUIRED.
- CAREFULLY REMOVE EQUIPMENT AND DEVICES THAT ARE NOTED TO BE REMOVED, STORED AND REUSED. REPLACE ANY OF THESE THAT ARE DAMAGED DURING REMOVAL, STORAGE, OR REINSTALLATION.
- EXISTING SWITCHBOARDS, PANELS, TRANSFORMERS, AND ASSOCIATED DEVICES SHALL REMAIN UNLESS OTHERWISE INDICATED. SEE SINGLE LINE DIAGRAM FOR DISTRIBUTION EQUIPMENT AND FEEDERS TO BE REMOVED. ALL EQUIPMENT SHOWN ON THIS PLAN IS EXISTING.
- OUTLETS AND WIRING IN EXISTING WALLS TO REMAIN U.O.I.
- WHenever outlets are removed in existing walls that remain, PATCH THE WALL OR PROVIDE A BLANK COVERPLATE FOR THE OUTLET BOX. COORDINATE THE REQUIREMENTS WITH THE OWNER'S PROJECT MANAGER.
- ALL EXISTING EXTERIOR POWER DEVICES AND RECEPTACLES ON THE ROOF, AND ASSOCIATED WIRING SHALL REMAIN U.O.I.
- TURN OFF ALL UNUSED CIRCUIT BREAKERS AND RELABEL AS SPARES.
- DISCONNECT, ISOLATE, AND MAKE SAFE ALL ELECTRICAL CONNECTIONS TO DEMOLISHED AND RELOCATED EQUIPMENT.
- REFER TO MECHANICAL AND PLUMBING DEMOLITION DRAWINGS FOR EQUIPMENT BEING DEMOLISHED. REMOVE CIRCUITS ASSOCIATED WITH DEMOLISHED EQUIPMENT BACK TO THE SOURCE UNLESS OTHERWISE INDICATED. CIRCUIT TO EQUIPMENT REMAINING TO REMAIN AS IS AND BE PROTECTED AS NECESSARY.
- THE CONTRACTOR IS TO DEMOLISH THE EXISTING FIRE ALARM AND SECURITY SYSTEMS. COORDINATE WITH THE OWNER'S PROJECT MANAGER REGARDING THE PHASING/SEQUENCE/TIMING OF THE REMOVAL AND REPLACEMENT TO ENSURE THAT ADEQUATE COVERAGE IS MAINTAINED AT ALL TIMES TO THE SATISFACTION OF THE OWNERS AND THE A.H.J.
- REMOVE ALL DEVICES AND WIRING IN WALLS BEING DEMOLISHED BACK TO SOURCE MAINTAINING CIRCUIT CONTINUITY TO OTHER DEVICES ON THE CIRCUIT(S) THAT REMAIN.
- DEMOLITION WORK TO BE PHASED IN ACCORDANCE WITH PROGRAM/SCHEDULE AGREED WITH THE OWNER'S PROJECT MANAGER.

**KEYNOTES**

- ALL ELECTRICAL, FIRE ALARM, TELEPHONE, DATA SERVICES IN THIS AREA TO BE DEMOLISHED INCLUDING PANELS, FEEDERS, BRANCH CIRCUITS ETC.
- DISCONNECT, REMOVE AND DEMOLISH CONDUIT AND WIRING BACK TO SOURCE FOR ALL EQUIPMENT IN THIS AREA SCHEDULED FOR DEMOLITION (NOTED IN BOLD). MODIFY CIRCUITS AS REQUIRED TO MAINTAIN CONTINUITY TO REMAINING EQUIPMENT/OUTLETS WHERE AFFECTED BY UPSTREAM CHANGES.
- EXISTING PANEL BOARD/S TO BE DEMOLISHED. DEMOLISH EXISTING FEEDER AND BRANCH CIRCUITS BACK TO SOURCE.



**KEY PLAN**  
SCALE: NOT TO SCALE

**01 PARTIAL POWER DEMOLITION PLAN EAST**  
SCALE: 3/32" = 1'-0"

**KROGER**  
STORE #473

2013 UNIVERSITY AVENUE  
OXFORD, MISSISSIPPI 38655

A DEVELOPMENT OF  
THE KROGER COMPANY

**Naos Design Group Of Mississippi, PLLC.**

MARC BREETZ  
ARCHITECT

645 Lakeland East Drive  
Suite 101  
Flowood, Mississippi 39232  
(p) 303.759.5777  
(f) 720.360.4281

ARCHITECT OF RECORD

**CDS**  
COMMERCIAL DESIGN SYSTEMS, INC.

13825 SW GALLEREA DRIVE  
SHERWOOD, OREGON 97140  
503.855.7000 (p)503.855.8902

INTERIOR DECOR

**Pickering Firm, Inc.**  
Architecture - Engineering  
Planning - Surveying

6775 Lenox Center Court, Suite 300  
Memphis, TN 38115  
901.726.8810

ENGINEER OF RECORD:  
STRUCTURAL  
MECHANICAL  
ELECTRICAL  
CIVIL ENGINEER

**V-SOFT**  
INFRASTRUCTURE

11280 CHESTER ROAD  
CINCINNATI, OH 45246  
T: 513-900-3810  
LOW VOLTAGE

**telgian**  
TELGIAN CORPORATION  
10230 SOUTH 60TH PLACE  
SUITE 100  
PHOENIX, AZ 85044  
T: (677) 836-4426  
HTTP://WWW.TELGIAN.COM  
FIRE PROTECTION

**ISSUE LOG**

NO.	REV.	DESCRIPTION	DATE
1	-	PERMIT SET	12/06/18
2	-	BID SET	03/21/19

JOB	SCALE
2019041	AS SHOWN

SHEET NO.

**ED1.2.2**  
PARTIAL POWER DEMOLITION PLAN EAST

COPYRIGHT © 2018 NAOS DESIGN GROUP OF MISSISSIPPI, PLLC. THESE DRAWINGS OR PARTS THEREOF MAY NOT BE REPRODUCED, COPIED, EITHER WHOLLY OR IN PART, FOR ANY PURPOSE, WITHOUT PRIOR WRITTEN CONSENT FROM NAOS DESIGN GROUP OF MISSISSIPPI, PLLC.