



**GENERAL NOTES**

1. REFER TO SHEET ED.1 FOR PROJECT GENERAL NOTES, LEGEND AND ABBREVIATIONS.
2. FIELD VERIFY EXISTING CONDITIONS AND PROJECT SCOPE PRIOR TO BIDDING THE PROJECT.
3. SEE ARCHITECTURAL, MECHANICAL, PLUMBING AND CIVIL DEMOLITION PLANS. COORDINATE DEMOLITION WITH THE OWNER'S PROJECT MANAGER AND PROJECT PHASING PLAN.
4. THE CONTRACTOR SHALL FOLLOW ALL OSHA, EPA AND LOCAL REGULATIONS REQUIRED. ALL SHALL OBTAIN ALL PERMITS FROM JURISDICTIONAL MUNICIPALITIES PRIOR TO DEMOLITION.
5. ALL EXISTING SWITCHBOARDS, PANELS, TRANSFORMERS, AND ASSOCIATED FEEDERS ARE EXISTING AND SHALL REMAIN UNLESS OTHERWISE INDICATED. SEE SINGLE LINE DIAGRAM FOR DISTRIBUTION EQUIPMENT AND FEEDERS TO BE REMOVED. ALL EQUIPMENT SHOWN ON THIS PLAN IS EXISTING.
6. PROVIDE TEMPORARY CIRCUITS TO DEVICES AND EQUIPMENT WHERE THE SOURCE SUCH AS THE PANEL IS REMOVED IN AN EARLIER PHASE. THIS SHOULD INCLUDE BUT NOT BE LIMITED TO TEMPORARILY RELOCATING THE PANEL AND MODIFYING THE EXISTING FEEDER AND BRANCH CIRCUIT WIRING AS REQUIRED.
7. THE CONTRACTOR SHALL ALLOW FOR THE DISCONNECTION AND DEMOLITION OF POWER SUPPLIES TO ALL EQUIPMENT IDENTIFIED ON THE PLANS FOR DEMOLITION AND/OR RELOCATION. (SHOWN SOLID) DISCONNECT ISOLATE, MAKE SAFE AND REMOVE WIRING TO SOURCE. ELECTRICAL SUPPLIES TO EXISTING SERVICES/EQUIPMENT (SHOWN GRAY) NOT IDENTIFIED FOR DEMOLITION ARE TO REMAIN.
8. CAREFULLY REMOVE EQUIPMENT AND DEVICES THAT ARE NOT TO BE REMOVED, STORED, AND REUSED. REPLACE ANY OF THESE THAT ARE DAMAGED DURING REMOVAL, STORAGE, OR REINSTALLATION.
9. REMOVE ALL DEMOLISHED MATERIALS FROM THE SITE AND DISPOSE OF THEM PROPERLY AND LEGALLY.
10. FOR FIXTURES TO BE REMOVED, BEANS, EXPOSED CONDUIT AND WIRING BACK TO THE SOURCE OR TO THE NEXT UPSTREAM DEVICE, FIXTURE, OR PANEL BOARD. REMOVE UNUSED WIRING IN CONDUIT CONCEALED IN WALLS OR UNDERGROUND AND ABANDON THE CONDUITS IN PLACE. MODIFY EXISTING CIRCUITS AS REQUIRED TO MAINTAIN CIRCUIT CONTINUITY TO EXISTING FIXTURES AND SERVICES THAT ARE TO REMAIN. ALL EXISTING LIGHTING AND CONTROL SYSTEMS SHALL REMAIN OPERATIONAL DURING THE PHASED TRANSITION UNDER THE NEW SYSTEMS ARE OPERATIONAL.
11. RE-LABEL ALL UNUSED CIRCUIT BREAKERS AS SPARES AND TURN THEM OFF.

**KEYED NOTES**

1. EXISTING POLE LIGHT AND BASE TO BE DEMOLISHED. DEMOLISH CIRCUIT BACK TO SOURCE OR NEXT UPSTREAM DEVICE.
2. EXISTING WALL LIGHT TO BE DEMOLISHED. DEMOLISH CIRCUIT BACK TO SOURCE OR NEXT UPSTREAM DEVICE.
3. EXISTING BUILDING TO BE DEMOLISHED. DISCONNECT, ISOLATE AND MAKE SAFE INCOMING UTILITY SERVICES TO EACH STORE PRIOR TO BUILDING DEMOLITION.
4. EXISTING UTILITY TRANSFORMER TO BE REMOVED BY UTILITY COMPANY AFTER NEW SERVICE HAS BEEN COMMISSIONED AND SWITCH BOARD MSB HAS BEEN RE-ENERGIZED - SEE SHEET E6.2 FOR ADDITIONAL INFORMATION.
5. EXISTING MAIN SWITCH BOARD TO REMAIN. REFER SLD ON SHEET E6.2 FOR CHANGES TO BOARD.
6. EXISTING TELEPHONE DEMARCATION BOARD TO REMAIN.
7. EXISTING COMMS FEED TO FUEL CENTER TO BE CUT OVER TO NEW FEED AFTER INSTALLATION OF NEW CONDUIT AND CABLES ETC (SEE SHEET E1.6). REDUNDANT SERVICES TO BE DEMOLISHED AFTER CUT OVER.
8. EXISTING POWER FEED TO FUEL CENTER TO BE CUT OVER TO NEW FEED AFTER INSTALLATION OF NEW CONDUIT AND WIRES ETC (SEE SHEET E1.6 AND E6.2).
9. EXISTING FUEL CENTER TO REMAIN. FOR NEW WORK, REFER SHEET E1.6.
10. EXISTING POLE LIGHTS TO REMAIN AS IS (THESE FIXTURES IN BANK OF OXFORD PARCEL/LOT).
11. EXISTING PHONE COMPANY UNDERGROUND STRUCTURE/PULL BOX TO REMAIN.
12. EXISTING PHONE COMPANY UNDERGROUND STRUCTURE/PULL BOX TO BE DEMOLISHED. COORDINATE WITH PHONE COMPANY.
13. EXISTING PHONE COMPANY UNDERGROUND CONDUITS TO BE DEMOLISHED AFTER SERVICES HAVE BEEN DIVERTED AND/OR DEMOLISHED. (SEE SHEET E1.6) COORDINATE WITH PHONE COMPANY.
14. EXISTING ELECTRIC UTILITY COMPANY'S PRIMARY UNDERGROUND CONDUITS TO BE DEMOLISHED AFTER SERVICES HAVE BEEN DIVERTED (SEE SHEET E1.6) COORDINATE WITH PHONE ELECTRIC UTILITY COMPANY.
15. TELEPHONE/DATA UTILITY SERVICES TO BE RE-FED BY PHONE COMPANY VIA EXISTING CONDUITS AFTER MODIFICATIONS TO EXISTING UNDERGROUND CONDUITS (SEE SHEET E1.6).
16. EXISTING MONUMENT SIGN TO BE REMOVED. DEMOLISH CIRCUIT BA TO SOURCE OR NEXT UPSTREAM DEVICE.

Order Plans @



**Kroger**  
KROGER  
STORE #473  
2013 UNIVERSITY AVENUE  
OXFORD, MISSISSIPPI 38655  
A DEVELOPMENT OF THE KROGER COMPANY

**naos**  
Naos Design Group Of Mississippi, PLLC.  
MARC BREETZ, ARCHITECT  
645 Lakeland East Drive Suite 101  
Flowood, Mississippi 39232  
(p) 303.759.5777  
(f) 720.360.4281  
ARCHITECT OF RECORD

**CDS**  
COMMERCIAL DESIGN SYSTEMS, INC.  
13825 SW GALLBREATH DRIVE  
SHERWOOD, OREGON 97140  
503.855.7000 (p)503.855.8902  
INTERIOR DECOR

**Pickering Firm, Inc.**  
Architecture - Engineering  
Planning - Surveying  
6775 Lenox Center Court, Suite 300  
Memphis, TN 38115  
901.726.8810  
ENGINEER OF RECORD:  
STRUCTURAL  
MECHANICAL  
ELECTRICAL  
CIVIL ENGINEER

**V-SOFT**  
INFRASTRUCTURE  
11280 CHESTER ROAD  
CINCINNATI, OH 45240  
T: 513-900-3819  
LOW VOLTAGE

**telgian**  
TELGIAN CORPORATION  
10230 SOUTH 69TH PLACE  
SUITE 100  
PHOENIX, AZ 85044  
T: (602) 836-4426  
HTTP://WWW.TELGIAN.COM  
FIRE PROTECTION

**ISSUE LOG**

NO.	REV.	DESCRIPTION	DATE
1	-	PERMIT SET	12/06/18
2	-	BID SET	03/21/19

JOB: 2018041 SCALE: AS SHOWN

SHEET NO.  
**ED1.6**  
ELECTRICAL SITE DEMOLITION PLAN

COPYRIGHT © 2018 NAOS DESIGN GROUP OF MISSISSIPPI, PLLC. THESE DRAWINGS OR PARTS THEREOF MAY NOT BE REPRODUCED, COPIED, EITHER WHOLLY OR IN PART, FOR ANY PURPOSE, WITHOUT PRIOR WRITTEN CONSENT FROM NAOS.