1 ELECTRICAL SITE LIGHTING PLAN
SCALE: 3/32"=1'-0"

KEY NOTES:

1. PROVIDE A 2" EMPTY SCHEDULE 40 PVC CONDUIT AT LEAST 24" BELOW GRADE FROM PANEL 'A' TO MONUMENT/PYLON SIGNS. STEEL CONDUIT SHALL PENETRATE INTO THE GARAGE TO THE PANEL. USE PVC TO STEEL CONDUIT COUPLING. SEE DETAIL 4/E-401. IF SIGN IS USED, PULL 2#10 AND 1#10 GROUND CU CONDUCTORS. VERIFY NUMBER OF SIGNAGE CIRCUITS AND CONDUCTORS WITH SITE SIGNAGE PROVIDER. ALL SIGNAGE FLOODLIGHT HOMERUNS SHALL BE CONTROLLED BY A ROOF MOUNTED PHOTOCELL WITH MANUAL OVERRIDE. SEE DETAIL 2/E-4.01. IF MONUMENT SIGN IS NOT USED, RUN PULLSTRING IN CONDUIT AND CAP AT BOTH ENDS.
2. REFER TO 2/E-4.01 FOR LIGHTING CONTROL DIAGRAM.
3. VERIFY EXACT POLE LIGHT LOCATIONS AND HEIGHTS WITH ARCHITECT AND CIVIL DRAWING(S).
4. PROVIDE PULL BOX AND 120V GFCI RECEPTACLE FOR HOLDING TANK ALARM PANEL. SEE SHEET 6/P-5.01. VERIFY EXACT LOCATION WITH CIVIL AND PLUMBING PLANS PRIOR TO INSTALLATION.
5. VERIFY EXACT HOLDING TANK ALARM PANEL LOCATION WITH ARCHITECT PRIOR TO ROUGH-IN AND INSTALLATION.

GENERAL NOTES:

1. PROVIDE GROUNDING CONDUCTORS FOR ALL CONDUITS.

Order Plans @ WWW.LDILine.com

SRB 360
STEWART + REINDERSMA ARCHITECTURE, PLLC
5450 E. High Street, Suite 200
Phoenix, Arizona 85054
P: 480.315.5123
www.sra360.com

Christian Brothers Automotive
5650 Peachtree Industrial Boulevard
Norcross, GA 30071

Christian Brothers Automotive
17725 Ley Freeway, St. 200
Houston, TX 77084

GEORGIA REGISTERED No. 75411 PROFESSIONAL ENGINEER DARRELL R. ENGE

10/19/2018
Date

Revisions

2/26/18 - Prototype Update

Project No. 18-042
Drawn By:
Date: 10/19/18

Sheet Title:
ELEC SITE LTG PLAN

Drawing No.
E-2.00
LH9N-09-2018

Ædifica case engineering
St. Louis - Montreal
796 Merus Court
St. Louis, MO 63026
T 636.349.1600
F 636.349.1730
aedificacase.com
mechanical
electrical
plumbing
fire protection
structural
CERTIFICATE OF AUTHORITY NO. PEF006438