


DEMOLITION NOTES REFERENCE TO GENERAL NOTES.

- DIMENSIONS ARE TO FACE OF STRUCTURAL MASONRY AND/OR TO COLUMN CENTERLINES, UNLESS NOTED OTHERWISE.
- THESE DRAWINGS WERE PREPARED BASED ON INFORMATION OBTAINED FROM A SITE SURVEY. CONTRACTOR TO VERIFY ALL EXISTING CONDITIONS IN FIELD PRIOR TO DEMOLITION & NOTIFY THE ARCHITECT IN CASE OF DISCREPANCIES IMMEDIATELY. DEMOLITION IS TO BE EXECUTED SUCH THAT NOT TO DISTURB EXISTING STRUCTURAL & ROOFING SYSTEMS AND OTHER AREAS THAT ARE INTENDED TO REMAIN INTACT. VERIFY ALL CONSTRUCTION TO BE REMOVED THAT IS NOT INTEGRAL TO STRUCTURAL SYSTEM PRIOR TO DEMOLITION UNLESS NOTED.
- ALL DIMENSIONS SHOWN AS EXISTING SHOULD BE FIELD VERIFIED BY CONTRACTOR PRIOR TO DEMOLITION. VERIFY ALL DEMOLITION WORK W/ NEW CONSTRUCTION & INSTALLATION DRAWINGS PRIOR TO BEGINNING CONSTRUCTION.
- DEMOLITION CONTRACTOR TO COORDINATE & REVIEW ALL CONSTRUCTION DOCUMENTS & DETERMINE THE EXTENT OF DEMOLITION WORK & BECOME FAMILIAR WITH THEM THOROUGHLY BEFORE PERFORMING ANY DEMOLITION WORK. BY THE ACT OF STARTING DEMOLITION, THE CONTRACTOR WILL BE DEEMED TO HAVE COMPLIED WITH THE FOREGOING, TO HAVE ACCEPTED SUCH CONDITIONS, AND TO HAVE MADE THE NECESSARY ALLOWANCES IN PREPARING HIS BID.
- VERIFY DISPOSITION OF ALL FURNISHINGS, MILLWORK, LIGHTING FIXTURES, ETC. TO BE REMOVED W/ VERIZON PROJECT MANAGER. ALL ITEMS TO BE DISPOSED SHALL BE DISPOSED OF OFF-SITE AND IN AN EXPEDITIOUS MANNER.
- SAWCUT & REMOVE EXISTING SLABS AS REQUIRED FOR UNDERGROUND ELECTRICAL & PLUMBING LINES. REFER TO ELECTRICAL DRAWINGS FOR ALL SAWCUT & TRENCHING WORK REQUIRED. ALL CONCRETE FLOOR WORK TO BE FINISHED FLUSH WITH EXISTING FLOOR. DOWEL NEW SLABS TO EXISTING W/ #4 REBAR @ 24" O.C. EACH SIDE (STAGGERED) UNLESS NOTIFIED OTHERWISE IN STRUCTURAL DRAWINGS. REBAR TO EXTEND 6" INTO EXISTING SLAB & ACROSS CUT OPENING UNLESS NOTED OTHERWISE IN STRUCTURAL DRAWINGS. SECURE REBAR INTO EXISTING SLAB W/ EPOXY GROUT. REPLACE OR REPAIR ANY VAPOR BARRIERS DISTURBED DURING EXCAVATIONS.
- PROTECT FROM DAMAGE DURING CONSTRUCTION ALL EXISTING WALLS, FLOORS, CEILINGS, ETC. THAT ARE TO REMAIN. CONTRACTOR TO PATCH & REPAIR ANY DAMAGED PORTIONS OF THE EXISTING BUILDING AS REQUIRED TO MATCH THE EXISTING ADJACENT CONSTRUCTION & FINISHES.
- IF CONTRACTOR ENCOUNTERS ANY HAZARDOUS MATERIALS DURING DEMOLITION OR CONSTRUCTION, HE SHALL IMMEDIATELY SUSPEND WORK & NOTIFY THE AREA CONSTRUCTION MANAGER BEFORE PROCEEDING.
- ALL DEMOLITION SHALL BE CARRIED OUT IN A SAFE MANNER & IN STRICT ACCORDANCE WITH OSHA REGULATIONS.
- REMOVE ANY SINKS, WATER CLOSETS, URINALS, LAVATORIES, FLOOR DRAINS, NOTED ON DRAWINGS AS WELL AS ALL ASSOCIATED PLUMBING ACCESSORIES. CAP PLUGS ALL ABANDONED SUPPLY & WASTE LINES. PATCH & SEAL ALL FLOOR PENETRATIONS. SEE MECHANICAL & PLUMBING DRAWINGS FOR DETAILED DEMOLITION NOTES.
- WHEN UTILITIES ARE REMOVED, CAP & SEAL A MINIMUM OF 8" BELOW FINISH FLOOR OR A MINIMUM OF 6" ABOVE FINISH CEILING.
- ALL EXISTING MECHANICAL EQUIPMENTS AND DUCTWORK TO REMAIN.
- REMOVE EXISTING FLOOR BOX COVER PLATE AND WIRES NOT BEING USED. INFILL EMPTY BOX WITH CONCRETE TRENCHING FLOOR AS REQUIRED FOR NEW UNDER SLAB CONDUITS AND FLOOR BOX PER ELECTRICAL PLAN.

CEILING PLAN KEYNOTES

- EXISTING CEILING GRID AND TILE TO BE REMOVED.
- EXISTING HVAC GRILLES TO BE REPLACED ON THE SALES AND 5-POS AREA PER REFLECTED CEILING PLAN.
- EXISTING EXIT SIGN AND EXTERIOR LIGHTS TO REMAIN.
- EXISTING EXIT SIGN TO BE RELOCATED PER REFLECTED CEILING PLAN.
- EXISTING LIGHT FIXTURE TO BE REMOVED.
- EXISTING TRACK AND TRACK LIGHTS HEADS TO BE REMOVED.
- EXISTING SECURITY SHUTTERS TO REMAIN.
- EXISTING DECORATIVE SOFFIT TO BE REMOVED.
- EXISTING SOFFIT/BULKHEAD ABOVE TO BE REMOVED.
- EXISTING LIGHT FIXTURES TO REMAIN.
- EXISTING HVAC DIFFUSERS TO REMAIN
- EXISTING GRID AND CEILING TILE TO REMAIN.

DEMO LEGEND NOT ALL SYMBOLS BELOW MAY BE USED.



Order Plans @ [www.LDILine.com](http://www.LDILine.com)

1 DEMOLITION CEILING PLAN  
 SCALE: 1/4" = 1'-0"



Verizon Wireless Hendersonville, NC 1602 Four Seasons Blvd, VT#221 VAMRPL\_CoverageD-102\_1602 Four Seasons Blvd\_VTW\_Demolition Ceiling Plan.dwg  
 Author: JLD/2019/03/28/19

| ISSUE | DATE     | DESCRIPTION       |
|-------|----------|-------------------|
| -     | 03/25/19 | ISSUED FOR PERMIT |

| PROJECT INFORMATION |             |
|---------------------|-------------|
| PROJECT NO:         | V2W.26121   |
| DATE:               | 03/13/2019  |
| SCALE:              | AS NOTED    |
| DRAWN BY:           | N.GLUKHOMAN |
| CHECKED BY:         | V.ALVAREZ   |

SHEET TITLE  
 DEMOLITION  
 CEILING PLAN

SHEET NUMBER  
 D-102