LEGEND

CONTRACTOR SHALL REMOVE ASBESTOS-CONTAINING FLOOR TILE AND ASSOCIATED MASTIC UTILIZING A FULL NEGATIVE PRESSURE ENCLOSURE.

CONTRACTOR SHALL REMOVE ASBESTOS-CONTAINING TRANSITE AWNING AND FASCIA PANELS.

CONTRACTOR SHALL PERFORM COMPONENT REMOVAL AND DISPOSAL OF LEAD COATED PORCELAIN SINKS AND LEAD GLAZED CERAMIC TILE BASEBOARDS. CONTRACTOR SHALL UTILIZE CERTIFIED RENOVATION, REPAIR, AND PAINTING (RRP) PERSONNEL AT A MINIMUM TO PERFORM COMPONENT REMOVAL OF TOILETS.

CONTRACTOR SHALL REMOVE SINK AS A COMPONENT WITH ASBESTOS-CONTAINING SINK MASTIC UTILIZING NON-FRIABLE, NON-REGULATED REMOVAL TECHNIQUES.

NOTES

1. THIS DRAWING ACCOMPANIES THE TECHNICAL SPECIFICATIONS FOR ASBESTOS ABATEMENT.
2. BOUNDARIES AND LOCATIONS ARE APPROXIMATE. CONTRACTOR IS RESPONSIBLE FOR CONFIRMING ALL QUANTITIES.
3. THE SCOPE OF WORK REQUIRES THE ASBESTOS ABATEMENT CONTRACTOR TO REMOVE ASBESTOS-CONTAINING FLOOR TILE AND ASSOCIATED MASTIC UTILIZING A FULL NEGATIVE PRESSURE ENCLOSURE. ASBESTOS ABATEMENT CONTRACTOR SHALL ALSO REMOVE IDENTIFIED TRANSITE AWNING AND FASCIA PANELS UTILIZING NONFRIABLE, NONREGULATED REMOVAL TECHNIQUES.
4. ASBESTOS ABATEMENT CONTRACTOR SHALL COORDINATE WITH THE OWNER AND DESIGNER FOR THE SCHEDULING OF ALL WORK.
5. ASBESTOS ABATEMENT ACTIVITIES MUST BE PERFORMED INSIDE THE CONTAINMENT AREA BOUNDARIES INDICATED ON THE DRAWINGS AND INSIDE A FULL NEGATIVE PRESSURE ENCLOSURE.

A1 B-101 FLOOR PLAN - DEMOLITION

Order Plans @ WWW.LDLine.com

Biltmore Hills

MATRIX Health & Safety Consultants, L.L.C.

ASBESTOS ABATEMENT PLAN
BILTMORE HILLS COMMUNITY CENTER
RALEIGH, NORTH CAROLINA

STAMP

TODD E. DAUGHERTY
N.C. ASBESTOS DESIGNER NO.40353

DATE: 11-28-18
DRAWN BY: A.C.S.
CHECKED BY: T.E.D.
APPROVED BY: T.E.D.

No	Revision	Date

Site: .
Building: .
Zone / Floor:
Discipline: .
Project: .
Scale: NTS

Title:
ASBESTOS ABATEMENT PLAN

Drawing Number: AB-1
Rev: