Design No. P717 JUNE 15, 2018

Restrained Assembly Rating — 1, 1-1/2 or 2 H (See Items 3, 4 and 10)
Unrestrained Assembly Rating — 1, 1-1/2 or 2 H (See Items 3, 4 and 10)

Unrestrained Beam Rating — 1, 1-1/2 or 2 H (See Item 10)
Restricted Load Condition — See Item 1
Load Restricted for Canadian Applications — See Guide BXUV7



1. Beam — W6x16 min size, or Steel Joist — 12H4, 14J7, 12K3 or 16K3 min sizes. (See Items 10 and 10A).
NOTE: Design load shall stress M-Series joists to a max tensile stress of 22 KSI.
2. Roof Covering*** — Consisting of hot mopped or cold applicationbituminous materials compatible with the insulation(s) described herein which provide Class A, B or C rcvrngs. See Roofing Materials and Systems Directory-Roof Covering Materials (TEVT).
2A. In lieu of Item 2, roof covering consisting of single-ply Roofing Membrane* — that is either ballasted, adhered or mechanically attached as permitted under the respective manufacturer's Classification. See Fire Resistance Directory — Roofing Membrane (CHET).
2B. Metal Roof Deck Panels* — (Not Shown) — In addition to or in lieu of Items 2 or 2A, the roof covering may consist of a mechanically fastened metal roof deck panel assembly. See Fire Resistance Directory — Metal Roof Deck Panels (CETW).
3. Roof Insulation — Foamed Plastic* — Polyisocyanurate foamed plastic insulation boards nom 48 by 48 or 96 in., to be applied in one or more layers. Min thickness is 1.3 in. for the 1 h rating without gypsum wallboard (Item 4), and for the 1-1/2 and 2 h ratings with gypsum wallboard and 2.6 in. for the 1-1/2 h ratings without gypsum wallboard. (No limit on max overall thickness). Boards to be installed with end joints staggered a min of 6 in. in adjacent rows. When applied in more than one layer, each layer to be offset in both directions from layer below a min of 6 in. in order to lap all joints.
ATLAS ROOFING CORP —ACFoam-15 Polyisocyanurate Foam Insulation.
CARLISLE SYNTEC INCORPORATED —Types HP, HP-H, HP-N, HP-W.
THE DOW CHEMICAL CO —Types Hy-Therm AP, Hy-Therm Tapered.
DYFLAST PRODUCTS I, L C
FIRESTONE BUILDING PRODUCTS CO L L C — "ISO 95+GL", "ISO 300".
GAF MATERIALS CORP —Isotherm R.
HUNTER PANELS —H Shield.
JOHNS MANVILLE — ENRGY 3, ISO-1, PSI 25.
LOADMASTER SYSTEMS INC —Loadmaster Polyisocyanurate Insulation.
RMAX OPERATING L L C —Multi-Max-3, Multi-Max FA-3, Ultra-Max, Tapered Thermaxx-3, Tapered Thermaxx FA-3, Ultra-Max Tapered.
DOW ROOFING SYSTEMS L L C —"Stevens ISO 2000", "Stevens ISO 3000".
GENFLEX ROOFING SYSTEMS L L C — "GenFlex ISO"
3A. Foamed Plastic* — 1 to 8 in. thick, density of 2.5 pcf min, polyisocyanurate foamed plastic insulation boards secured to the gypsum wallboard (Item 4) with asphalt glaze coat or adhesive.
(Note: Adhesive* (Item 6) and/or asphalt glazer coat may be omitted when Item 2A is used). See Foamed Plastic (BRYX) category in the Building Materials Directory or Foamed Plastic (CCVW) category in the Fire Resistance Directory for names of manufacturers.
3B. Mineral and Fiber Boards* — (Not Shown) — Optional — Applied in one or more layers over the Foamed Plastic (Item 3). To be applied with adhesive (Item 6), asphalt or coal tar pitch (Item 7) or mechanical fasteners (Item 8).
OWENS CORNING FT INC, DIV OF OWENS CORNING
SIPLAST INC
3C. Building Units* — As an alternate to Item 3, polyisocyanurate foamed plastic insulation boards, nom 48 by 48 or 96 in., faced on the top surface with oriented strand board. Min thickness of the polyisocyanurate core is 1.3 in. for the 1 hr rating without gypsum wallboard (Item 4) and for the 1, 1-1/2 and 2 hr ratings with gypsum wallboard and 2.6 for the 1-1/2 hr ratings without gypsum wallboard. No limit on max overall thickness. Boards to be installed with end joints staggered a min of 6 in. in adjacent rows.
ATLAS ROOFING CORP —ACFoam Nailbase Installation, Nested-R.
FIRESTONE BUILDING PRODUCTS CO L L C —Heatgard.
JOHNS MANVILLE —Nailboard.
3D. Roof Insulation — Foamed Plastic* — Polyisocyanurate foamed plastic insulation boards, nom 48 by 48 or 96 in., to be applied in one or more layers over gypsum wallboard (Item 4). Min thickness is 1 in. Boards to be installed with end joints staggered a min of 6 in. in adjacent rows. When applied in more than one layer, each layer to be offset in both directions from layer below a min of 6 in. in order to lap all joints.
RMAX OPERATING L L C
3E. Building Units* — Polyisocyanurate foamed plastic insulation boards faced on the underside (or both sides) with oriented fiber board. Min thickness of the polyisocyanurate core is 1.3 in. for the 1 hr rating without gypsum wallboard (Item 4) and for the 1-1/2 and 2 hr ratings with gypsum wallboard and 2.6 in. for the 1-1/2 hr ratings without gypsum wallboard. No limit on max overall thickness. Boards to be installed with end joints staggered a min of 6 in. in adjacent rows. See Foamed Plastic (CKNX) category for names of manufacturers.
3F. Building Units* — As an alternate to Items 3 through 3E, polyisocyanurate foamed plastic insulation boards faced on the underside with wood fiber board. Min thickness of the polyisocyanurate core is 1.3 in. for the 1 hr rating without gypsum wallboard (Item 4) and for the 1-1/2 and 2 hr ratings with wallboard and 2.6 in. for the 1-1/2 hr ratings without gypsum wallboard. No limit on max overall thickness. Boards to be installed with end joints staggered a min of 6 in. in adjacent rows.
FIRESTONE BUILDING PRODUCTS CO L L C —"ISO 95+ Wood Fiberboard Composite".
JOHNS MANVILLE —ENRGY2 Plus.
3G. Building Units* — As an alternate to Items 2 and 3 through 3H, insulated steel panels, 36 in. wide, installed over gypsum wallboard (Item 4). Building units mechanically fastened to the steel deck through the gypsum wallboard in accordance with the manufacturer's recommendations.
CENTRIA —Types VP-1.25, VP-2.5, VP-4.6
3H. Building Units* — Not Shown — As an alternate to Items 3 through 3F, composite polyisocyanurate foamed plastic insulation board, nom 48 by 48 or 96 in., with an adhered roofing surface may be used with the following limitations. These composite building units have ventilation slots internal to the panels. The thickness of the panel depends upon the thickness position of the polyisocyanurate insulation. The following dimensions apply to the polyisocyanurate insulation: min 1.3 in. thick for the 1 hr rating without gypsum wallboard applied to the roof deck, min 1.3 in. thick for the 1-1/2 and 2 hr ratings with gypsum wallboard and min 2.6 in. for the 1-1/2 hr rating without gypsum wallboard. There is no limit on the max insulation thickness.
GAF MATEI ALS CORP —Type INSUL-AIR.
JOHNS MAI VILLE —Type ISO-VENT.
3I. Building Units* — As an alternate to Items 3 through 3I, polyisocyanurate foamed plastic insulation boards, nom 48 by 48 or 96 in., faced on the top surface with gypsum board. Min thickness of the polyisocyanurate core is 1.3 in. for 1 hr rating without gypsum wallboard (Item 4) and for the 1-1/2 and 2 hr ratings with wallboard (Item 4) and 2.6 in. for the 1-1/2 ratings without gypsum wallboard (Item 4). No limit on overall thickness. Boards to be installed with end joints staggered a min of 6 in. in adjacent rows. Adhesive (Item 6) may be applied between the building units and the vapor retarder (or gypsum wallboard if vapor retarder is not used).
JOHNS MANVILLE — ENRGY 2 Gypsum Composite.
3J. Roof Insulation — Foamed Plastic* — (Not Shown) — As an alternate to Items 3 through 3J, polyisocyanurate foamed plastic insulation boards, nom 48 by 48 or 96 in., to be applied in one or more layers over gypsum wallboard (Item 4). Min thickness is 1.3 in. Boards to be installed with end joints staggered a min of 6 in. in adjacent rows. Adhesive (Item 6) may be applied between the building units and the vapor retarder (or gypsum wallboard if vapor retarder is not used).
3K. Mineral and Fiber Boards* — (Not Shown) - Optional - Applied in one or more layers over Foamed Plastic (Item 3) to be applied with adhesive (Item 6), asphalt or coal tar pitch (Item 7) or mechanically fastened (Item 8).
JOHNS MANVILLE — Fesco, Retrofit, Dura Board
3L. Roof Insulation — Foamed Plastic* — — (Not Shown) — Optional, 1/4 in. thick - Placed over minimum 1-1/2 in. thick polyisocyanurate foamed plastic (Item 3) to be applied with adhesive (Item 6), asphalt or coat tar pitch (Item 7) or mechanically fastened (Item 8). Boards to be installed with end joints to be offset in both directions from layer below a min of 6 in. in order to lap all joints.
JOHNS MANVILLE — Invinsa Roof Board
4. Gypsum Board — (Not shown — Classified as Unclassified) — May be used to obtain various Restrained and Unrestrained Assembly Ratings as described in Item 10. Required for the 2 Hr Assembly and Beam Ratings. Also required as per 1, 1-1/2 and 2 hr Assembly and Beam Ratings when insulated steel bonding units are used. Supplied in sheets nom 2 by 4 ft to 4 by 12 ft, by nom 5/8 in. thick. Min weight 2.2 psf. Applied perpendicular to steel roof deck fluestrips with adhesive (Item 6), hot asphalt (Item 7) or laid loosely. End joints to occur over crests of steel roof and to be staggered 2 ft in adjacent rows. See Gypsum Board (CKNX) category for names of manufacturers.
5. Vapor Retarder — Sheathing Material* — (Optional — Not shown) — Vinyl film or other vapor retarder material applied to steel roof deck or gypsum wallboard with adhesive (Item 6), hot asphalt (Item 7) or laid loosely, overlapped approx 2 in. on adjacent sheets. See Sheathing Material (CHIZ) category for names of manufacturers.
5A. Sheathing Material* — (Optional) — In lieu of Item 5, a self-adhered rubberized asphalt sealing underlayment membrane which may be placed on top of gypsum wallboard or on the roof insulation.
CARLISLE COATINGS & WATERPROOFING INC —CCW-702
W R GRACE & CO - CONN — Grace Ice and Water Shield.
Grace Select, Grace Ultra, and Grace Resist.
6. Adhesive* — (Optional) — The vapor retarder, the gypsum wallboard or the first layer of roof insulation may be secured with adhesive to the steel roof deck surface. Also used to attach the vapor retarder to gypsum wallboard, the first layer of insulation to vapor retarder or gypsum wallboard and each additional layer of insulation. Applied in 1/2 in. wide ribbons 8 in. OC at 0.6 gal per 100 sq ft. See Adhesives (CYRH) category for names of manufacturers.
6A. Adhesive* — (Optional) — Bearing the UL Classification Marking for Roof Systems (FOFU) - The vapor retarder, the gypsum wallboard or the first layer of roof insulation may be secured with adhesive to the steel roof surfaces. Also used to attach the vapor retarder to gypsum wallboard, the first layer of insulation to vapor retarder or gypsum wallboard and each additional layer of insulation. Applied at a min rate of 19.8 g/ft². When FAST 100 adhesive is used, additional Spray-Applied Fire Resistence Materials* (CHPG) is required on the deck for the 1-1/2 and 2 hr Unrestrained Assembly Ratings. The thickness specified for the deck shall be increased by 1/16 in. for 1-1/2 hr Unrestrained Assembly Rating and 1/4 in. for 2 hr Unrestrained Assembly Rating when Item 6A is used.
CARLISLE SYNTEC INCORPORATED — FAST 100.
7. Asphalt or Coal Tar Pitch* — (Optional — Not shown) — The vapor retarder, the gypsum wallboard or the first layer or roof insulation may be secured with asphalt or coal tar pitch to the steel roof surfaces at a max rate of 15 lbs per sq ft. Also used to attach the vapor retarder to gypsum wallboard, the first layer of insulation to vapor retarder or gypsum wallboard and each additional layer of roof insulation, applied at a max rate of 25 lbs/100 sq ft.
8. Mechanical Fasteners — (Optional — Not shown) — Mechanical screw-type fasteners with metal or plastic washer designed for the purpose may be used to attach one or more layers of insulation to steel roof deck.
9. Steel Roof Deck — (Unclassified) — Min 1-1/2 in. deep and 30 in. wide galv fluted steel deck. Flutes 6 in. OC with crest width ranging from 3-5/8 to 5-7/8 in. Min gauge is 22 MSG. Ends overlapped at supports min 1-1/2 in. and welded to supports at deck laps at a max of 12 in. OC between sides of units. Side laps of adjacent units welded, bottom-punched or seconed together with No. 12 by 3/4 in. long self-drilling, self-tapping steel screws spaced a max of 36 in. OC.
ASC STEEL DECK, DIV OF ASC PROFILES INC —Type N.
CANAM STEEL CORP — Type P-3688, P-3615, P-2436, and P-2404.
CMC JOIST & DECK - MANUFACTURERS OF UNITED STEEL DECK PRODUCTS —Types B, BI, N and NS. Units may be phsis/painted or painted/painted.
CONSOLIDATED SYSTEMS INC —Types B, BI, B, N, NI. Units may be phas/phas.
LOADMASTER SYSTEMS INC —Types PS, SS-150, SS-300. Units may be zncf/phf.
MARLYN STEEL DECKS INC—Types B, B N, NV.
VERCO DECKING INC - A NUCOR CO— Types FLR, B, FLR or N Formlock. Galvanize be phas/phf. Types FLR, HSB, PLN or N Formlock. Units may be phf/phf.
WELCRAFT, DIV OF NUCOR CORP —Galv. or phf/phf Types 1.5B, 1.5BI, 1.5F, 3N1.
WHEELING-PITTSBURGH STEEL CORP, DIV OF WHEELING CORRUGATING CO —Galv or phas/phf Types A, BW, E High Strength B, High Strength BW, N.
Ratings. Also required on 1, 1-1/2 and 2 hr Assembly and Beam Ratings when insulated steel bonding units are used. Supplied in sheets nom 2 by 4 ft to 4 by 12 ft, by nom 5/8 in. thick. Min weight 2.2 psf. Applied perpendicular to steel roof deck fluestrips with adhesive (Item 6), hot asphalt (Item 7) or laid loosely. End joints to occur over crests of steel roof and to be staggered 2 ft in adjacent rows. See Gypsum Board (CKNX) category for names of manufacturers.
10. Spray-Applied Resistive Materials* — Applied by mixing with water and spraying in more than one coat to final thicknesses as shown in the illustration above and in the table below, to steel surfaces which must be clean and free of dirt, loose scale and oil. Steel deck surfaces must be "spatter" coated with Types DK, DK2, DK3, SK-1B spray-applied resistive material prior to application of spray-applied resistive material. Types DK, DK2, DK3, SK-1B spray-applied resistive material applied in accordance with the manufacturer's application instructions. Min avg and min ind density of 15/14 pcf, respectively. Min avg and min ind density of 19/18 pcf respectively for Types 7GP and 7HD. For method of density determination, see Design Information Section. Thickness of the spatter coat is included in the total final thickness of the protection material.

Restrained & Unrestrained Assembly Rating Hr	Unrestrained Beam Rating Hr	Spray-Applied Fire Resistive Mtl Thk In. on Steel	on Joists	on Joists
1	1	1-1/8	2	1-1/2
1-1/2	1-1/4	1	2	—
2	1-1/2	1-7/16	2	—

Restrained & Unrestrained Assembly Rating Hr	Spray-Applied Fire Resistive Mtl Thk In. On Deck Without Cgypsum Wallboard	With Cgypsum Wallboard	With Gypsum Board Laminated Steel Bonding Unit
1	1-13/16	1-1/8	1-13/16
1-1/2	2	1-5/8	2
2	NR	1-7/8	2-1/8

#The required minimum thickness of Spray-Applied Fire Resistive Materials on the steel deck is increased by 1/16 in. for 1-1/2 hr Unrestrained Assembly Rating and 1/4 in. for 2 hr Unrestrained Assembly Rating when Item 6A is used.
NR-Indicates no rating.
+2 Hr. assembly and beam ratings apply only to assembly with gypsum wallboard.
ARABIAN VERMICULITE INDUSTRIES —Type MK-5
W R GRACE & CO - CONN —Types MK-4, MK-5, SK-1B.
PYROK INC —Type LD.
SOUTHWEST FIREPROFING PRODUCTS CO —Types 4, 5, 5EF, 5GP, 5AR, 5GP/AR, 5EF/AR, 5MD/AR, 5MD, 7GP, 7HD, 8EF, 8GP, 8MD, 9EF, 9GP, 9MD.
GCP APLIED TECHNOLOGIES INC —Types MK6/HY, MK-6s, Monokote Acoustic 1, Monokote Acoustic 5, RG, Z106, Z106/G.
11. Steel Framing — Studs — (Unclassified) — Min 2-1/2 in. wide, 0.033 in. thick (20 MSG) galv steel studs spaced max 24 in. OC. Studs to be installed in both floor and ceiling runners. Runners to be secured to floor and ceiling with fasteners spaced max 24 in. OC. Min 1 in. deep flange on runners. Studs may be cut 1/2 in. short of full height of assembly. Studs may be friction fitted or secured to runners with 1/2 in. long sheet metal screws, one at each flange.
12. Bridging — (Not shown) — Minimum 1-1/4 by 1-1/4 by 1/8 in. galv steel angles, cut from the same runner stock used for the studs, secured to studs with two screws through each leg of angle. Bridging to be located at mid-height of studs and secured to studs with two screws through each leg of angle.
13. Wallboard, Gypsum* — (Optional) — Nominal 1/2 in. thick gypsum wallboard applied parallel or perpendicular to studs with screws spaced max 12 in. OC. Screws to be min 1 in. long for single layer application and min 1-1/4 in. long for two layer application. Wallboard applied with long dimension parallel to studs. Joints of base layer of wallboard shall not occur in the same stud bay as joints in the face layer. Joints of base layer shall be staggered with respect to joints of face layer. Joints of face layer shall be staggered 24 in. with respect to joints of base layer. Joints of base layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer on opposite sides of partition shall not occur in the same stud bay. Joints of base layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition.
14. Steel Framing — Studs — (Unclassified) — Min 2-1/2 in. wide, 0.033 in. thick (20 MSG) galv steel studs spaced max 24 in. OC. Studs to be installed in both floor and ceiling runners. Runners to be secured to floor and ceiling with fasteners spaced max 24 in. OC. Min 1 in. deep flange on runners. Studs may be cut 1/2 in. short of full height of assembly. Studs may be friction fitted or secured to runners with 1/2 in. long sheet metal screws, one at each flange.
15. Wallboard, Gypsum* — (Optional) — Nominal 1/2 in. thick gypsum wallboard applied parallel or perpendicular to studs with screws spaced max 12 in. OC. Screws to be min 1 in. long for single layer application and min 1-1/4 in. long for two layer application. Wallboard applied with long dimension parallel to studs. Joints of base layer of wallboard shall not occur in the same stud bay as joints in the face layer. Joints of base layer shall be staggered with respect to joints of face layer. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer on opposite sides of partition shall not occur in the same stud bay. Joints of base layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition.
16. Steel Framing — Studs — (Unclassified) — Min 3-5/8 in. wide, 0.033 in. thick (20 MSG) galv steel studs spaced max 24 in. OC. Studs to be installed in both floor and ceiling runners. Runners to be secured to floor and ceiling with fasteners spaced max 24 in. OC. Min 1 in. deep flange on runners. Studs may be cut 1/2 in. short of full height of assembly. Studs may be friction fitted or secured to runners with 1/2 in. long sheet metal screws, one at each flange.
17. Wallboard, Gypsum* — (Optional) — Nominal 1/2 in. thick gypsum wallboard applied parallel or perpendicular to studs with screws spaced max 12 in. OC. Screws to be min 1 in. long for single layer application and min 1-1/4 in. long for two layer application. Wallboard applied with long dimension parallel to studs. Joints of base layer of wallboard shall not occur in the same stud bay as joints in the face layer. Joints of base layer shall be staggered with respect to joints of face layer. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer on opposite sides of partition shall not occur in the same stud bay. Joints of base layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition.
18. Steel Framing — Studs — (Unclassified) — Min 4 in. wide, 0.033 in. thick (20 MSG) galv steel studs spaced max 24 in. OC. Studs to be installed in both floor and ceiling runners. Runners to be secured to floor and ceiling with fasteners spaced max 24 in. OC. Min 1 in. deep flange on runners. Studs may be cut 1/2 in. short of full height of assembly. Studs may be friction fitted or secured to runners with 1/2 in. long sheet metal screws, one at each flange.
19. Wallboard, Gypsum* — (Optional) — Nominal 1/2 in. thick gypsum wallboard applied parallel or perpendicular to studs with screws spaced max 12 in. OC. Screws to be min 1 in. long for single layer application and min 1-1/4 in. long for two layer application. Wallboard applied with long dimension parallel to studs. Joints of base layer of wallboard shall not occur in the same stud bay as joints in the face layer. Joints of base layer shall be staggered with respect to joints of face layer. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer on opposite sides of partition shall not occur in the same stud bay. Joints of base layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition.
20. Steel Framing — Studs — (Unclassified) — Min 6 in. wide, 0.033 in. thick (20 MSG) galv steel studs spaced max 24 in. OC. Studs to be installed in both floor and ceiling runners. Runners to be secured to floor and ceiling with fasteners spaced max 24 in. OC. Min 1 in. deep flange on runners. Studs may be cut 1/2 in. short of full height of assembly. Studs may be friction fitted or secured to runners with 1/2 in. long sheet metal screws, one at each flange.
21. Wallboard, Gypsum* — (Optional) — Nominal 1/2 in. thick gypsum wallboard applied parallel or perpendicular to studs with screws spaced max 12 in. OC. Screws to be min 1 in. long for single layer application and min 1-1/4 in. long for two layer application. Wallboard applied with long dimension parallel to studs. Joints of base layer of wallboard shall not occur in the same stud bay as joints in the face layer. Joints of base layer shall be staggered with respect to joints of face layer. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer on opposite sides of partition shall not occur in the same stud bay. Joints of base layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition.
22. Steel Framing — Studs — (Unclassified) — Min 8 in. wide, 0.033 in. thick (20 MSG) galv steel studs spaced max 24 in. OC. Studs to be installed in both floor and ceiling runners. Runners to be secured to floor and ceiling with fasteners spaced max 24 in. OC. Min 1 in. deep flange on runners. Studs may be cut 1/2 in. short of full height of assembly. Studs may be friction fitted or secured to runners with 1/2 in. long sheet metal screws, one at each flange.
23. Wallboard, Gypsum* — (Optional) — Nominal 1/2 in. thick gypsum wallboard applied parallel or perpendicular to studs with screws spaced max 12 in. OC. Screws to be min 1 in. long for single layer application and min 1-1/4 in. long for two layer application. Wallboard applied with long dimension parallel to studs. Joints of base layer of wallboard shall not occur in the same stud bay as joints in the face layer. Joints of base layer shall be staggered with respect to joints of face layer. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer on opposite sides of partition shall not occur in the same stud bay. Joints of base layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition.
24. Steel Framing — Studs — (Unclassified) — Min 10 in. wide, 0.033 in. thick (20 MSG) galv steel studs spaced max 24 in. OC. Studs to be installed in both floor and ceiling runners. Runners to be secured to floor and ceiling with fasteners spaced max 24 in. OC. Min 1 in. deep flange on runners. Studs may be cut 1/2 in. short of full height of assembly. Studs may be friction fitted or secured to runners with 1/2 in. long sheet metal screws, one at each flange.
25. Wallboard, Gypsum* — (Optional) — Nominal 1/2 in. thick gypsum wallboard applied parallel or perpendicular to studs with screws spaced max 12 in. OC. Screws to be min 1 in. long for single layer application and min 1-1/4 in. long for two layer application. Wallboard applied with long dimension parallel to studs. Joints of base layer of wallboard shall not occur in the same stud bay as joints in the face layer. Joints of base layer shall be staggered with respect to joints of face layer. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer on opposite sides of partition shall not occur in the same stud bay. Joints of base layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition.
26. Steel Framing — Studs — (Unclassified) — Min 12 in. wide, 0.033 in. thick (20 MSG) galv steel studs spaced max 24 in. OC. Studs to be installed in both floor and ceiling runners. Runners to be secured to floor and ceiling with fasteners spaced max 24 in. OC. Min 1 in. deep flange on runners. Studs may be cut 1/2 in. short of full height of assembly. Studs may be friction fitted or secured to runners with 1/2 in. long sheet metal screws, one at each flange.
27. Wallboard, Gypsum* — (Optional) — Nominal 1/2 in. thick gypsum wallboard applied parallel or perpendicular to studs with screws spaced max 12 in. OC. Screws to be min 1 in. long for single layer application and min 1-1/4 in. long for two layer application. Wallboard applied with long dimension parallel to studs. Joints of base layer of wallboard shall not occur in the same stud bay as joints in the face layer. Joints of base layer shall be staggered with respect to joints of face layer. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer on opposite sides of partition shall not occur in the same stud bay. Joints of base layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition.
28. Steel Framing — Studs — (Unclassified) — Min 14 in. wide, 0.033 in. thick (20 MSG) galv steel studs spaced max 24 in. OC. Studs to be installed in both floor and ceiling runners. Runners to be secured to floor and ceiling with fasteners spaced max 24 in. OC. Min 1 in. deep flange on runners. Studs may be cut 1/2 in. short of full height of assembly. Studs may be friction fitted or secured to runners with 1/2 in. long sheet metal screws, one at each flange.
29. Wallboard, Gypsum* — (Optional) — Nominal 1/2 in. thick gypsum wallboard applied parallel or perpendicular to studs with screws spaced max 12 in. OC. Screws to be min 1 in. long for single layer application and min 1-1/4 in. long for two layer application. Wallboard applied with long dimension parallel to studs. Joints of base layer of wallboard shall not occur in the same stud bay as joints in the face layer. Joints of base layer shall be staggered with respect to joints of face layer. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer on opposite sides of partition shall not occur in the same stud bay. Joints of base layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition.
30. Steel Framing — Studs — (Unclassified) — Min 16 in. wide, 0.033 in. thick (20 MSG) galv steel studs spaced max 24 in. OC. Studs to be installed in both floor and ceiling runners. Runners to be secured to floor and ceiling with fasteners spaced max 24 in. OC. Min 1 in. deep flange on runners. Studs may be cut 1/2 in. short of full height of assembly. Studs may be friction fitted or secured to runners with 1/2 in. long sheet metal screws, one at each flange.
31. Wallboard, Gypsum* — (Optional) — Nominal 1/2 in. thick gypsum wallboard applied parallel or perpendicular to studs with screws spaced max 12 in. OC. Screws to be min 1 in. long for single layer application and min 1-1/4 in. long for two layer application. Wallboard applied with long dimension parallel to studs. Joints of base layer of wallboard shall not occur in the same stud bay as joints in the face layer. Joints of base layer shall be staggered with respect to joints of face layer. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer on opposite sides of partition shall not occur in the same stud bay. Joints of base layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition.
32. Steel Framing — Studs — (Unclassified) — Min 18 in. wide, 0.033 in. thick (20 MSG) galv steel studs spaced max 24 in. OC. Studs to be installed in both floor and ceiling runners. Runners to be secured to floor and ceiling with fasteners spaced max 24 in. OC. Min 1 in. deep flange on runners. Studs may be cut 1/2 in. short of full height of assembly. Studs may be friction fitted or secured to runners with 1/2 in. long sheet metal screws, one at each flange.
33. Wallboard, Gypsum* — (Optional) — Nominal 1/2 in. thick gypsum wallboard applied parallel or perpendicular to studs with screws spaced max 12 in. OC. Screws to be min 1 in. long for single layer application and min 1-1/4 in. long for two layer application. Wallboard applied with long dimension parallel to studs. Joints of base layer of wallboard shall not occur in the same stud bay as joints in the face layer. Joints of base layer shall be staggered with respect to joints of face layer. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer on opposite sides of partition shall not occur in the same stud bay. Joints of base layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition.
34. Steel Framing — Studs — (Unclassified) — Min 20 in. wide, 0.033 in. thick (20 MSG) galv steel studs spaced max 24 in. OC. Studs to be installed in both floor and ceiling runners. Runners to be secured to floor and ceiling with fasteners spaced max 24 in. OC. Min 1 in. deep flange on runners. Studs may be cut 1/2 in. short of full height of assembly. Studs may be friction fitted or secured to runners with 1/2 in. long sheet metal screws, one at each flange.
35. Wallboard, Gypsum* — (Optional) — Nominal 1/2 in. thick gypsum wallboard applied parallel or perpendicular to studs with screws spaced max 12 in. OC. Screws to be min 1 in. long for single layer application and min 1-1/4 in. long for two layer application. Wallboard applied with long dimension parallel to studs. Joints of base layer of wallboard shall not occur in the same stud bay as joints in the face layer. Joints of base layer shall be staggered with respect to joints of face layer. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer on opposite sides of partition shall not occur in the same stud bay. Joints of base layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition.
36. Steel Framing — Studs — (Unclassified) — Min 22 in. wide, 0.033 in. thick (20 MSG) galv steel studs spaced max 24 in. OC. Studs to be installed in both floor and ceiling runners. Runners to be secured to floor and ceiling with fasteners spaced max 24 in. OC. Min 1 in. deep flange on runners. Studs may be cut 1/2 in. short of full height of assembly. Studs may be friction fitted or secured to runners with 1/2 in. long sheet metal screws, one at each flange.
37. Wallboard, Gypsum* — (Optional) — Nominal 1/2 in. thick gypsum wallboard applied parallel or perpendicular to studs with screws spaced max 12 in. OC. Screws to be min 1 in. long for single layer application and min 1-1/4 in. long for two layer application. Wallboard applied with long dimension parallel to studs. Joints of base layer of wallboard shall not occur in the same stud bay as joints in the face layer. Joints of base layer shall be staggered with respect to joints of face layer. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer on opposite sides of partition shall not occur in the same stud bay. Joints of base layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition.
38. Steel Framing — Studs — (Unclassified) — Min 24 in. wide, 0.033 in. thick (20 MSG) galv steel studs spaced max 24 in. OC. Studs to be installed in both floor and ceiling runners. Runners to be secured to floor and ceiling with fasteners spaced max 24 in. OC. Min 1 in. deep flange on runners. Studs may be cut 1/2 in. short of full height of assembly. Studs may be friction fitted or secured to runners with 1/2 in. long sheet metal screws, one at each flange.
39. Wallboard, Gypsum* — (Optional) — Nominal 1/2 in. thick gypsum wallboard applied parallel or perpendicular to studs with screws spaced max 12 in. OC. Screws to be min 1 in. long for single layer application and min 1-1/4 in. long for two layer application. Wallboard applied with long dimension parallel to studs. Joints of base layer of wallboard shall not occur in the same stud bay as joints in the face layer. Joints of base layer shall be staggered with respect to joints of face layer. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer on opposite sides of partition shall not occur in the same stud bay. Joints of base layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition.
40. Steel Framing — Studs — (Unclassified) — Min 26 in. wide, 0.033 in. thick (20 MSG) galv steel studs spaced max 24 in. OC. Studs to be installed in both floor and ceiling runners. Runners to be secured to floor and ceiling with fasteners spaced max 24 in. OC. Min 1 in. deep flange on runners. Studs may be cut 1/2 in. short of full height of assembly. Studs may be friction fitted or secured to runners with 1/2 in. long sheet metal screws, one at each flange.
41. Wallboard, Gypsum* — (Optional) — Nominal 1/2 in. thick gypsum wallboard applied parallel or perpendicular to studs with screws spaced max 12 in. OC. Screws to be min 1 in. long for single layer application and min 1-1/4 in. long for two layer application. Wallboard applied with long dimension parallel to studs. Joints of base layer of wallboard shall not occur in the same stud bay as joints in the face layer. Joints of base layer shall be staggered with respect to joints of face layer. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer on opposite sides of partition shall not occur in the same stud bay. Joints of base layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition.
42. Steel Framing — Studs — (Unclassified) — Min 28 in. wide, 0.033 in. thick (20 MSG) galv steel studs spaced max 24 in. OC. Studs to be installed in both floor and ceiling runners. Runners to be secured to floor and ceiling with fasteners spaced max 24 in. OC. Min 1 in. deep flange on runners. Studs may be cut 1/2 in. short of full height of assembly. Studs may be friction fitted or secured to runners with 1/2 in. long sheet metal screws, one at each flange.
43. Wallboard, Gypsum* — (Optional) — Nominal 1/2 in. thick gypsum wallboard applied parallel or perpendicular to studs with screws spaced max 12 in. OC. Screws to be min 1 in. long for single layer application and min 1-1/4 in. long for two layer application. Wallboard applied with long dimension parallel to studs. Joints of base layer of wallboard shall not occur in the same stud bay as joints in the face layer. Joints of base layer shall be staggered with respect to joints of face layer. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer on opposite sides of partition shall not occur in the same stud bay. Joints of base layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition. Joints of face layer shall be staggered 24 in. with respect to joints of base layer on opposite side of partition.
44. Steel Framing — Studs — (Unclassified) — Min 30 in. wide, 0.033 in. thick (20 MSG) galv steel studs spaced max 24 in. OC. Studs to be installed in both floor and ceiling runners. Runners to be secured to floor and ceiling with fasteners spaced max 24 in. OC. Min 1 in. deep flange on runners. Studs may be cut 1/2 in. short of full height of assembly. Studs may be friction fitted or secured to runners with 1/2 in. long sheet metal screws, one at each flange.
45. Wallboard, Gyp